

NOTICE TO CONTRACTORS

CALL ORDER 605
FEDERAL PROJECT NO. STPD-70-3(107)
LOCATION: N-70, BROKEN BOW EAST.
COUNTIES: CUSTER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 10:30 A.M. on January 23, 2009 . At that time the bids will be opened and read for SEED GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 11.8 MILES
START DATE 03/30/2009 WORKING DAYS 135
Price Range \$ 4,000,000 to \$ 7,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning December 30, 2008 at the Lincoln Central Office and January 05, 2009 at the District Engineer's Office at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	64 SHEETS	\$	16.00
STANDARD PLANS	12 SHEETS	\$	3.00

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T3	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W11	WETLANDS
2-N1 - 2-N2	GENERAL INFORMATION
3 - 13	PLAN SHEETS
14	TEMPORARY PAVEMENT MARKING PLAN
15 - 35	DRAINAGE STRUCTURE CROSS SECTIONS
36	SPECIAL PLAN 1C CONCRETE FLUME, TYPE I
37	SPECIAL PLAN 2C CONCRETE FLUME, TYPE II
38 - 39	SPECIAL PLAN 3C CONCRETE FLUME, TYPE VIII
40 - 47	SPECIAL PLAN 4C GUARDRAIL PLAN

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
307	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE B		46 ACRE
MULCH		103 TON

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
ROADWAY GRADING		7 STA
W-BEAM GUARDRAIL		193 LF
REMOVE GUARDRAIL		825 LF
IMPACT ATTENUATOR		1 EACH
BRIDGE APPROACH SECTIONS		7 EACH
GUARDRAIL END TREATMENT, TYPE II		7 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		95 EACH
REMOVE DELINEATOR UNITS		60 EACH
REMOVE CURB		52,020 LF
REMOVE INLET		21 EACH
REMOVE CONCRETE FLUME		63 EACH
GRAVEL SURFACE COURSE		285 CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS		386 SY
MAILBOX POST		8 EACH
CAST IRON GRATE & FRAME		20,188 LB
FLUME SPILLWAY		490 LF
CONCRETE FLUME, TYPE I		33 EACH
CONCRETE FLUME, TYPE II		1 EACH
47B-3000 CONC FOR INLET & JUNCTION BOXES		89 CY
EPOXY RE-STEEL FOR INLET & JCT. BOX		5,565 LB
HYDRATED LIME FOR ASPHALT MIXTURES		336 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		5 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 SPECIAL(0.5)		500 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)		200 TON
ASPH CONC, TYPE SPS		6,400 TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)		33,380 TON
PLACE ASPH CONC FOR DRIVE & INTER		7,014 SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH		27 TON
PERF GRADED BINDER (58-28)		345 TON
PERF GRADED BINDER (64-28)		1,813 TON
CONSTRUCTING ASPH CONC CURB		53,610 LF
TACK COAT		46,930 GAL
FOG SEAL		33,750 GAL
WATER		312 MGAL
WATER FOR FLY ASH STABILIZED BITUMINOUS		925 MGAL
EARTH SHOULDER CONSTRUCTION		1,248 STA
WIDENING		708 STA
COLD MILLING, CLASS 3		280 STA
MILLING CONC FOR INLAYS		2 EACH
SURFACE UNDER GUARDRAIL		543 SY
FLY ASH STABILIZED BITUMINOUS		624 STA
FLY ASH		7,005 TON
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
EROSION CONTROL, CLASS 1D		896 SY
EROSION CONTROL, CLASS 2A		2,745 SY
15" CULV PIPE 3,4,5,6		1,420 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	71,280	BDAY
BARRICADE, TYPE III	2,596	BDAY
TEMPORARY SIGN DAY	1,050	EACH
SIGN DAY	21,811	EACH
OVERLAY BROKEN LINES	1,872	STA
OVERLAY SOLID LINES	3,744	STA
FLAGGING	150	DAY
FURNISHING AND OPERATING PILOT VEHICLE	75	DAY
FIELD OFFICE	1	EACH
TRAINING	2,000	HOURL
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	30	HOURL
RENTAL OF MOTOR GRADER, FULLY OPERATED	20	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	30	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	30	HOURL
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HOURL
TEMPORARY SILT FENCE	800	LF