

NOTICE TO CONTRACTORS

CALL ORDER 705
FEDERAL PROJECT NO. STP-S42A(101)
LOCATION: S42A, HUNTLEY SPUR
COUNTIES: HARLAN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 10:30 A.M. on January 23, 2009. At that time the bids will be opened and read for GRAD GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 4.2 MILES
START DATE 07/20/2009 WORKING DAYS 60
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning December 30, 2008 at the Lincoln Central Office and January 05, 2009 at the District Engineer's Office at MCCOOK

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	45	SHEETS	\$ 11.25
CROSS SECTIONS (SHEETS X1 THRU X51)	51	SHEETS	\$ 12.75
STANDARD PLANS	17	SHEETS	\$ 4.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W4	WETLANDS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N	GENERAL INFORMATION
2-L1 - 2-L5	EROSION CONTROL
3 - 6	PLAN SHEETS
7	TEMPORARY PAVEMENT MARKING PLAN
8	TYPICAL PAVEMENT MARKING PLAN
9 - 12	EARTHWORK DATA SHEETS
13 - 18	DRAINAGE STRUCTURE CROSS SECTIONS
19 - 21	SPECIAL PLAN 1C CABLE GUARDRAIL
R1 - R8	RIGHT-OF-WAY SHEETS
X1 - X51	CROSS SECTIONS

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
307	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
547	(2 SHEETS) CONCRETE FLUME, TYPE VII
804	PRECAST CONCRETE R.O.W. MARKER
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		96 MGAL
RIGHT-OF-WAY MARKERS		4 EACH
EARTHWORK MEASURED IN EMBANKMENT	4,256	CY
24" DRIVE PIPE 2,3,4,5,6,7 OR 8		56 LF
REMOVE & SALVAGE FES		1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		1 CY
INSTALL 36" METAL F.E.S.		1 EACH
REMOVE GUARDRAIL	6,388	LF
EROSION CONTROL, CLASS 1C	12,027	SY
EROSION CONTROL, CLASS 2A		440 SY
FABRIC SILT FENCE-LOW POROSITY	1,708	LF
36" CULV PIPE 3,4,5		12 LF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
CABLE GUARDRAIL	7,072	LF
TERMINAL ANCHORAGE SECTIONS		24 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		659 STA
OVERLAY SOLID LINES		1,319 STA
PERMANENT PAVEMENT MARKING PAINT	55,000	LF
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		20 EACH
INSTALL CHEVRONS		8 EACH
GRAVEL SURFACE COURSE		95 CY
SPEC SURF CRSE FOR MAILBOX TURNOUTS		25 SY
MAILBOX POST		1 EACH
CAST IRON GRATE & FRAME	2,060	LB
47B-3000 CONC FOR INLET & JUNCTION BOXES		17 CY
RE-STEEL FOR INLET & JCT BOX	1,200	LB
HYDRATED LIME FOR ASPHALT MIXTURES		111 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		25 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 SPECIAL(0.5)	2,500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)		500 TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	10,638	TON
PLACE ASPH CONC FOR DRIVE & INTER	2,210	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH		135 TON
PERF GRADED BINDER (64-28)		601 TON
CONSTRUCTING ASPH CONC CURB 3"	3,553	LF
TACK COAT	13,154	GAL
WATER		109 MGAL
EARTH SHOULDER CONSTRUCTION		437 STA
COLD MILLING, CLASS 3		225 STA
SURFACE UNDER GUARDRAIL	3,460	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		16 ACRE
MULCH		36 TON
15" CULV PIPE 3,4,5,6		596 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	23,040	B DAY
BARRICADE, TYPE III		584 B DAY
TEMPORARY SIGN DAY		700 EACH
SIGN DAY	4,704	EACH
FLAGGING		70 DAY
FURNISHING AND OPERATING PILOT VEHICLE		35 DAY

TRAFFIC CONTROL MANAGEMENT	104 DAY
FIELD OFFICE	1 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	80 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	80 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	80 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	40 HOUR
TEMPORARY SILT FENCE	2,000 LF
TEMPORARY MULCH	4 TON