

NOTICE TO CONTRACTORS

CALL ORDER 710
 FEDERAL PROJECT NO. STP-34-2(118)
 LOCATION: US-34, COLORADO LINE-HAIGLER
 COUNTIES: DUNDY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 10:30 A.M. on January 23, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.8 MILES
 START DATE 07/20/2009 WORKING DAYS 60
 Price Range \$ 2,000,000 to \$ 4,000,000

Plans and specifications may be seen beginning December 30, 2008 at the Lincoln Central Office and January 05, 2009 at the District Engineer's Office at MCCOOK

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	23	SHEETS	\$	5.75
STANDARD PLANS	7	SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W7	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 9	PLAN SHEETS
10	TEMPORARY PAVEMENT MARKING PLAN
11	TYPICAL PAVEMENT MARKING PLAN

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
309	MAILBOX SUPPORT POST
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	9,240	B DAY
BARRICADE, TYPE III	416	B DAY
TEMPORARY SIGN DAY	840	EACH
SIGN DAY	8,808	EACH
OVERLAY BROKEN LINES	1,077	STA
OVERLAY SOLID LINES	2,154	STA
PERMANENT PAVEMENT MARKING PAINT	90,000	LF
FLAGGING	120	DAY
FURNISHING AND OPERATING PILOT VEHICLE	50	DAY
TRAFFIC CONTROL MANAGEMENT	104	DAY
FIELD OFFICE	1	EACH
TRAINING	1,000	HOUR
MOBILIZATION	LUMP	LUMP

DELINEATOR, TYPE III	52	EACH
INSTALL CHEVRONS	8	EACH
REMOVE DELINEATOR UNITS	48	EACH
GRAVEL SURFACE COURSE	135	CY
MAILBOX POST	3	EACH
MEMBRANE WATERPROOFING	343	SY
HYDRATED LIME FOR ASPHALT MIXTURES	123	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	25	TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	2,500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	1,000	TON
ASPH CONC, TYPE SPS	12,500	TON
ASPH CONC, TYPE SP4(0.5)	11,260	TON
HIGH RAP BASE	20,690	TON
PLACE ASPH CONC FOR DRIVE & INTER	3,696	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	135	TON
PERF GRADED BINDER (58-28)	672	TON
PERF GRADED BINDER (58-34)	675	TON
PERF GRADED BINDER (64-28)	662	TON
TACK COAT	43,520	GAL
FOG SEAL	120	GAL
RENTAL OF LOADER, FULLY OPERATED	85	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	80	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	85	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	85	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5	HOUR
WATER	177	MGAL
EARTH SHOULDER CONSTRUCTION	707	STA
COLD MILLING, CLASS 3	360	STA
COLD MILLING, CLASS 4	343	SY
RUMBLE STRIPS, ASPHALT	706	STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	30	ACRE
TEMPORARY SILT FENCE	500	LF
MULCH	68	TON