

NOTICE TO CONTRACTORS

CALL ORDER 110  
STATE PROJECT NO. RD-77-1(1025)  
LOCATION: US-77/US-136 NORTH, BEATRICE  
COUNTIES: GAGE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 12, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

START DATE 09/21/2009 WORKING DAYS 20  
Price Range \$ 250,000 to \$ 1,000,000

Plans and specifications may be seen beginning February 17, 2009 at the Lincoln Central Office and February 23, 2009 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. 110, {Project No. RD-77-1(1025)} and Call Order No. 115, {Project No. STP-77-1(129)}. Award of Contract, if awarded, will be made on the combined bid for these call order nos. Separate contracts will be awarded for each Call Order Number. Please order plans and proposals accordingly.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	21 SHEETS	\$	5.25
STANDARD PLANS	7 SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A1 - 2-A2	PHOTO MAPS
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 4	PLAN SHEETS
5 - 7	TYPICAL URBAN TRAFFIC CONTROL PLAN
8	TEMPORARY PAVEMENT MARKING PLAN
9	PAVEMENT MARKING PLAN
10	SPECIAL PLAN 1C CURB RAMPS

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	1,070 BDAY
BARRICADE, TYPE III	40 BDAY
TEMPORARY SIGN DAY	65 EACH
SIGN DAY	738 EACH
CONTRACTOR FURNISHED SIGN DAY	6 EACH
OVERLAY BROKEN LINES	76 STA
FLASHING ARROW PANEL	12 DAY
FLAGGING	20 DAY
TRAFFIC CONTROL MANAGEMENT	41 DAY

FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
REMOVE WALK		42 SY
CONCRETE CURB REPAIR TACK-ON CURB		73 LF
CONCRETE CURB REPAIR		111 LF
CONC 47B-3000 SIDEWALKS		42 SY
DETECTABLE WARNING PANEL		20 EACH
CONC PVMT REPAIR TYPE A FULL DEPTH		11 CY
CONC PVMT REPAIR TYPE B FULL DEPTH		34 CY
CONC PVMT REPAIR TYPE C FULL DEPTH		40 CY
4" WHITE THERMOPLASTIC, GROOVED		1,030 LF
4" YELLOW THERMOPLASTIC, GROOVED		4,950 LF
12" WHITE THERMOPLASTIC, GROOVED		308 LF
24" WHITE THERMOPLASTIC, GROOVED		504 LF
4" WHITE THERMOPLASTIC		830 LF
ARROW, WET RFLC PRF PVMT MKNG, T 4 GVD		6 EACH
HYDRATED LIME FOR ASPHALT MIXTURES		22 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)		5 TON
ASPH CONC, TYPE SP4(0.5)		2,150 TON
PERF GRADED BINDER (64-28)		116 TON
TACK COAT		2,650 GAL
RENTAL OF LOADER, FULLY OPERATED		5 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		5 HOUR
COLD MILLING, CLASS 3 TYPE B		13,071 SY
COLD MILLING, CLASS 3 TYPE A		245 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
ADJUST VALVE BOX TO GRADE		1 EACH