

NOTICE TO CONTRACTORS

CALL ORDER 125
STATE PROJECT NO. RD-79-2(1013)
LOCATION: N-79, PRAGUE-DODGE COUNTY LINE
COUNTIES: SAUNDERS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 12, 2009. At that time the bids will be opened and read for GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 11.5 MILES
START DATE 06/15/2009 WORKING DAYS 80
Price Range \$ 3,000,000 to \$ 6,000,000

Plans and specifications may be seen beginning February 17, 2009 at the Lincoln Central Office and February 23, 2009 at the District Engineer's Office at LINCOLN. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	63	SHEETS	\$	15.75
CROSS SECTIONS (SHEETS X1 THRU X35)	35	SHEETS	\$	8.75
STANDARD PLANS	14	SHEETS	\$	3.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W12	WETLANDS
2-H1 - 2-H9	HORIZONTAL ALIGNMENT, CONTROL POINTS, & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 13	PLAN SHEETS
14	TEMPORARY PAVEMENT MARKING PLAN
15 - 17	EARTHWORK DATA SHEETS
18 - 21	SPECIAL PLAN 1 REMODEL OF BRIDGE RAIL END SECTION STA. 371+82.00 STA. 403+40.00 STA. 589+04.00
22 - 30	SPECIAL PLAN 1C GUARDRAIL PLAN
31 - 33	SPECIAL PLAN 2C CABLE GUARDRAIL
34 - 35	SPECIAL PLAN 3C SAFETY SLOPED END SECTIONS CORRUGATED METAL & CONCRETE PIPE
X1 - X35	CROSS SECTIONS

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
307	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		47 MGAL
EARTHWORK MEASURED IN EMBANKMENT	3,131	CY
47BD-4000 CONC FOR CONC. RAIL		21 CY
RE-STEEL FOR CONC RAIL	2,685	LB
PREP BRIDGE		1 EACH
AT STA. 371+82.00		
PREP BRIDGE		1 EACH
AT STA. 403+40.00		
PREP BRIDGE		1 EACH
AT STA. 589+04.00		
W-BEAM GUARDRAIL	506	LF
CABLE GUARDRAIL	608	LF
REMOVE GUARDRAIL	1,431	LF
BRIDGE APPROACH SECTIONS		12 EACH
TERMINAL ANCHORAGE SECTIONS		4 EACH
GUARDRAIL END TREATMENT, TYPE I		1 EACH
GUARDRAIL END TREATMENT, TYPE II		13 EACH
EROSION CONTROL, CLASS 1D	8,188	SY

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE III		65 EACH
INSTALL CHEVRONS		20 EACH
GRAVEL SURFACE COURSE		230 TON
CRUSHED ROCK SURFACE COURSE		185 TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS	1,383	SY
MAILBOX POST		22 EACH
24" SAFETY SLOPED END SECTION		1 EACH
MEMBRANE WATERPROOFING	1,054	SY
HYDRATED LIME FOR ASPHALT MIXTURES		233 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		3 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE		300 TON
SP4 SPECIAL(0.5)		
ASPH CONCRETE FOR PATCHING, TYPE		250 TON
SP4 SPECIAL(0.5)		
ASPH CONC, TYPE SP4 SPECIAL(0.5)	23,067	TON
HIGH RAP BASE	42,150	TON
PLACE ASPH CONC FOR DRIVE & INTER	9,981	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH		16 TON
PERF GRADED BINDER (58-34)	1,369	TON
PERF GRADED BINDER (64-28)	1,258	TON
TACK COAT	41,720	GAL
WATER		304 MGAL
EARTH SHOULDER CONSTRUCTION	1,216	STA
TRENCHED WIDENING	1,099	STA
COLD MILLING, CLASS 3		608 STA
RUMBLE STRIPS, ASPHALT		116 STA
SURFACE UNDER GUARDRAIL	1,005	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		15 ACRE
FABRIC SILT FENCE-LOW POROSITY	3,530	LF
MULCH		34 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	23,760	BDAY
BARRICADE, TYPE III	3,196	BDAY
TEMPORARY SIGN DAY	1,120	EACH
SIGN DAY	18,501	EACH
OVERLAY BROKEN LINES	1,825	STA
OVERLAY SOLID LINES	3,651	STA
FLAGGING	160	DAY
FURNISHING AND OPERATING PILOT VEHICLE	62	DAY

TRAFFIC CONTROL MANAGEMENT	139 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	70 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	30 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	70 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	70 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	40 HOUR
TEMPORARY SILT FENCE	500 LF