

NOTICE TO CONTRACTORS

CALL ORDER 600
 FEDERAL PROJECT NO. IM-80-4(104)
 LOCATION: I-80, MAXWELL INTERCHANGE
 COUNTIES: LINCOLN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 12, 2009. At that time the bids will be opened and read for GR CONC PAVE BR GDRL ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT
 START DATE 06/08/2009 WORKING DAYS 70
 Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning February 17, 2009 at the Lincoln Central Office and February 23, 2009 at the District Engineer's Office at NORTH PLATTE
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	59	SHEETS	\$ 14.75
CROSS SECTIONS (SHEETS X1 THRU X27)	27	SHEETS	\$ 6.75
STANDARD PLANS	17	SHEETS	\$ 4.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-P1 - 2-P10	PHASING PLANS
2-L1 - 2-L2	GEOMETRICS
2-L3	CONSTRUCTION & REMOVAL
3 - 4	PLAN & PROFILE SHEETS
5 - 12	TRAFFIC CONTROL PLAN--PHASES
13	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS--NARROW ROADWAY, 10' TRAVEL LANE
14	TEMPORARY TRAFFIC SIGNAL
15	TYPICAL PAVEMENT MARKING PLAN
16	TEMPORARY PAVEMENT MARKING PLAN
17 - 20	ROADWAY LIGHTING PLANS
21 - 22	EARTHWORK DATA SHEETS
23	DRAINAGE STRUCTURE CROSS SECTIONS
24	SPECIAL PLAN 1C MODIFIED AREA INLET WITH 2" PIPE
25	SPECIAL PLAN 2C MODIFIED AREA INLET WITH 2" PIPE
26 - 30	SPECIAL PLAN 3C BRIDGE REPAIRS STA. 1015+00
31 - 37	SPECIAL PLAN 4C GUARDRAIL PLAN
38 - 39	SPECIAL PLAN 5C CONCRETE PROTECTION BARRIER
40	SPECIAL PLAN 6C TRAFFIC CONTROL PLAN--LANE CLOSURE (INTERSTATE/FREEWAY)
X1 - X27	CROSS SECTIONS

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	2,300	CY
WATER	10	MGAL
REMOVE PAVEMENT	4,628	SY
REMOVE ASPHALT SURFACE	5,018	SY
REMOVE INLET	4	EACH
REMOVE GUARDRAIL	756	LF
EROSION CONTROL, CLASS 1D	776	SY

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
8" CONC PVMT, 47B-3500	3,065	SY
8" DOWELED CONC PAVE, CLASS 47B-3500	6,822	SY
TEMPORARY SURFACING	4,211	SY
47B-3000 CONC FOR INLET & JUNCTION BOXES	4	CY
RE-STEEL FOR INLET & JCT BOX	330	LB
FOUNDATION COURSE	9,887	SY
WATER	38	MGAL
EARTH SHOULDER CONSTRUCTION	34	STA
SUBGRADE PREPARATION	9,887	SY
SEEDING, TYPE B	1	ACRE
MULCH	1	TON

GROUP 6 BRIDGE AT STA. 1015+00.00

MOBILIZATION	LUMP	LUMP
PREFORMED EXPANSION JOINT, TYPE B	62	LF
EXPANSION BEARING, TFE TYPE	8	EACH
CLASS I REPAIR	744	SY
CLASS II REPAIR	223	SY
CLASS III REPAIR	5	SY
PLACE, FINISH, & CURE CONC OVERLAY-SF	744	SY
47BD-4000 CONC FOR BRIDGE	77	CY
CONCRETE FOR OVERLAYS-SF	71	CY
PREP BRIDGE	1	EACH
AT STA. 1015+00.00		
EPOXY COATED RE-STEEL	7,660	LB
BEARING DEVICE REPLACEMENT	8	EACH

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL	275	LF
BRIDGE APPROACH SECTIONS	4	EACH
GUARDRAIL END TREATMENT, TYPE II	4	EACH

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
STREET LIGHTING UNIT REPLACEMENT, TYPE "B"	6	EACH
STREET LIGHTING UNIT REPLACEMENT, TYPE "A"	2	EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	8,755	B	DAY
BARRICADE, TYPE III	4,341	B	DAY
TEMPORARY SIGN DAY	144	E	EACH
SIGN DAY	11,914	E	EACH
CONTRACTOR FURNISHED SIGN DAY	2,470	E	EACH
PAVEMENT MARKING REMOVAL	14,000	L	LF
TEMP PVMT MARKING, TYPE PAINT	18,750	L	LF
TEMP PVMT MARKING SURF PREP	9,375	L	LF
PERMANENT PAVEMENT MARKING PAINT	12,600	L	LF
FLASHING ARROW PANEL	12	D	DAY
CONCRETE PROTECTION BARRIER	975	L	LF
RELOCATE CONC PROTECTION BARRIER	2,325	L	LF
TEMPORARY RUMBLE STRIP	4	E	EACH
TEMPORARY TRAFFIC SIGNAL	1	E	EACH
TRAFFIC CONTROL MANAGEMENT	118	D	DAY
FIELD OFFICE	1	E	EACH
TRAINING	500	H	HOUR
MOBILIZATION	LUMP	L	LUMP
RENTAL OF LOADER, FULLY OPERATED	10	H	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	H	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	H	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	H	HOUR
TEMPORARY SILT FENCE	200	L	LF
TEMPORARY MULCH	2	T	TON