

NOTICE TO CONTRACTORS

CALL ORDER 630
FEDERAL PROJECT NO. IM-80-5(69)
LOCATION: I-80, LEXINGTON-OVERTON
COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 12, 2009. At that time the bids will be opened and read for SEED GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.5 MILES
START DATE 05/11/2009 WORKING DAYS 75
Price Range \$ 6,000,000 to \$ 10,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning February 17, 2009 at the Lincoln Central Office and February 23, 2009 at the District Engineer's Office at NORTH PLATTE. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	41	SHEETS	\$	10.25
CROSS SECTIONS (SHEETS X1 THRU X7)	7	SHEETS	\$	1.75
STANDARD PLANS	11	SHEETS	\$	2.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1 - 2-N2	GENERAL INFORMATION & MILLED RUMBLE STRIPS
3 - 12	PLAN SHEETS
13	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
14	TEMPORARY PAVEMENT MARKING PLAN
15	EARTHWORK DATA SHEET
16 - 17	SPECIAL PLAN 1C PIER COLUMN PROTECTION STA. 174+96.50
18 - 19	SPECIAL PLAN 2C PIER COLUMN PROTECTION STA. 353+78.35
20 - 29	SPECIAL PLAN 3C GUARDRAIL PLAN
30	SPECIAL PLAN 4C TYPICAL PAVEMENT MARKING PLAN
X1 - X7	CROSS SECTIONS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE B		81 ACRE
EROSION CONTROL, CLASS 1D		4,118 SY
MULCH		182 TON

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR PIER PROTECTION		7 CY
EPOXY COAT RE-STEEL FOR PIER PROTECTION		2,470 LB
THRIE-BEAM GUARDRAIL		162 LF
REMOVE GUARDRAIL		300 LF
REMOVE & SALVAGE GUARDRAIL		800 LF
RESET GUARDRAIL		800 LF
BULLNOSE-12.5'		2 EACH
GUARDRAIL POSTS		4 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE I		420 EACH
REMOVE DELINEATOR UNITS		420 EACH
EARTHWORK MEASURED IN EMBANKMENT		476 CY
CONC PVTM REPAIR TYPE A FULL DEPTH		15 CY
CONC PVTM REPAIR TYPE B FULL DEPTH		35 CY
CONC PVTM REPAIR TYPE C FULL DEPTH		50 CY
CONC PVTM, PR-3500		20 CY
JOINT REPAIR		
5" WHITE THERMOPLASTIC, GROOVED		139,000 LF
5" YELLOW THERMOPLASTIC, GROOVED		111,000 LF
HYDRATED LIME FOR ASPHALT MIXTURES		724 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		2 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP5(0.5)		250 TON
ASPH CONC, TYPE SPS		23,680 TON
ASPH CONC, TYPE SP5(0.5)		72,390 TON
PERF GRAD BIND (70-28)FOR ST MAINT PATCH		13 TON
PERF GRADED BINDER (58-28)		1,278 TON
PERF GRADED BINDER (70-28)		3,909 TON
TACK COAT		91,510 GAL
WATER		568 MGAL
EARTH SHOULDER CONSTRUCTION		2,228 STA
MILLING CONC FOR INLAYS		4 EACH
RUMBLE STRIPS, ASPHALT		2,216 STA
SURFACE UNDER GUARDRAIL		539 SY
SURFACE UNDER GUARDRAIL		254 SY
3"		

ASPH PVTM SMOOTHNESS TESTING I/D	LUMP	LUMP
----------------------------------	------	------

GROUP 10 GENERAL ITEMS

SURV OF TEMP TRAFFIC CONT DEVICES		118 CDAY
BARRICADE, TYPE II		30,000 BDAY
BARRICADE, TYPE III		622 BDAY
TEMPORARY SIGN DAY		1,800 EACH
SIGN DAY		3,115 EACH
OVERLAY BROKEN LINES		1,108 STA
OVERLAY SOLID LINES		2,216 STA
FLASHING ARROW PANEL		150 DAY
FIELD OFFICE		1 EACH
TRAINING		4,000 HOUR
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		5 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		5 HOUR
TEMPORARY SILT FENCE		500 LF