

NOTICE TO CONTRACTORS

CALL ORDER 100
STATE PROJECT NO. STR-1-7(1007)
LOCATION: N-1, ELMWOOD NORTH BRIDGES
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 07/06/2009 WORKING DAYS 50
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

| | | | | |
|---|----|--------|----|------|
| INFORMATIONAL PROPOSAL | | EACH | \$ | 5.00 |
| PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS) | 25 | SHEETS | \$ | 6.25 |
| CROSS SECTIONS (SHEETS X1 THRU X6) | 6 | SHEETS | \$ | 1.50 |
| STANDARD PLANS | 10 | SHEETS | \$ | 2.50 |

SHEET NO.

| | |
|-------------|---|
| 1 | TITLE PAGE |
| 2-T | TYPICAL CROSS SECTIONS |
| 2-S | SUMMARY OF QUANTITIES |
| 2-W1 - 2-W2 | WETLANDS |
| 2-H | HORIZONTAL ALIGNMENT & CONTROL POINTS |
| 2-N | GENERAL INFORMATION |
| 3 - 4 | PLAN SHEETS |
| 5 | TYPICAL TRAFFIC CONTROL PLAN--TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY TRAFFIC (NARROW BRIDGE, BARRELS ONLY) |
| 6 | EARTHWORK DATA SHEET |
| 7 - 9 | SPECIAL PLAN 1C REMODEL BRIDGE RAIL STA. 246+72.00 |
| 10 - 12 | SPECIAL PLAN 2C REMODEL BRIDGE RAIL STA. 358+89.55 |
| 13 - 20 | SPECIAL PLAN 3C GUARDRAIL PLAN |
| X1 - X6 | CROSS SECTIONS |

STANDARD PLANS

| | |
|--------|--|
| 501-R5 | (3 SHEETS) EROSION CONTROL |
| 502 | SILT FENCE DETAILS |
| 920-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 921-R5 | (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE |
| 922-R7 | (2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING |

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 246+72

| | | |
|---------------------------------------|------|--------|
| MOBILIZATION | LUMP | LUMP |
| CLASS I REPAIR | | 268 SY |
| CLASS II REPAIR | | 80 SY |
| CLASS III REPAIR | | 5 SY |
| PLACE, FINISH, & CURE CONC OVERLAY-SF | | 268 SY |
| 47BD-4000 CONC FOR CONC. RAIL | | 13 CY |

| | | |
|-------------------------------------|-------|------|
| CONCRETE FOR OVERLAYS-SF | 46 | CY |
| EPOXY COATED RE-STEEL FOR CONC RAIL | 2,525 | LB |
| PREP BRIDGE | 1 | EACH |
| AT STA. 246+72 | | |

GROUP 6A BRIDGE AT STA. 358+89.55

| | LUMP | LUMP |
|---------------------------------------|-------|------|
| MOBILIZATION | | |
| CLASS I REPAIR | 193 | SY |
| CLASS II REPAIR | 58 | SY |
| CLASS III REPAIR | 5 | SY |
| PLACE, FINISH, & CURE CONC OVERLAY-SF | 193 | SY |
| 47BD-4000 CONC FOR CONC. RAIL | 10 | CY |
| CONCRETE FOR OVERLAYS-SF | 29 | CY |
| EPOXY COATED RE-STEEL FOR CONC RAIL | 1,920 | LB |
| PREP BRIDGE | 1 | EACH |
| AT STA. 358+89.55 | | |

GROUP 7 GUARDRAIL

| | LUMP | LUMP |
|----------------------------------|------|------|
| MOBILIZATION | | |
| W-BEAM GUARDRAIL | 187 | LF |
| BRIDGE APPROACH SECTIONS | 8 | EACH |
| GUARDRAIL END TREATMENT, TYPE II | 8 | EACH |

GROUP 9 BITUMINOUS

| | LUMP | LUMP |
|----------------------------------|-------|--------|
| MOBILIZATION | | |
| GENERAL CLEARING AND GRUBBING | | |
| WATER | | 7 MGAL |
| EARTHWORK MEASURED IN EMBANKMENT | 716 | CY |
| REMOVE GUARDRAIL | 693 | LF |
| ASPH CONC, TYPE SP4 SPECIAL(0.5) | 90 | TON |
| EARTH SHOULDER CONSTRUCTION | 7 | STA |
| COLD MILLING, CLASS 5 | 1,013 | SY |
| SURFACE UNDER GUARDRAIL | 419 | SY |
| EROSION CONTROL, CLASS 1C | 2,866 | SY |
| FABRIC SILT FENCE-LOW POROSITY | 655 | LF |

GROUP 10 GENERAL ITEMS

| | | |
|--|-------|-------|
| BARRICADE, TYPE II | 1,152 | B DAY |
| BARRICADE, TYPE III | 324 | B DAY |
| TEMPORARY SIGN DAY | 200 | EACH |
| SIGN DAY | 2,970 | EACH |
| PAVEMENT MARKING REMOVAL | 350 | LF |
| TEMP PVMT MARKING, TYPE PAINT | 4,000 | LF |
| FLAGGING | 10 | DAY |
| FIELD OFFICE | 1 | EACH |
| MOBILIZATION | LUMP | LUMP |
| RENTAL OF LOADER, FULLY OPERATED | 15 | HOURL |
| RENTAL OF DUMP TRUCK, FULLY OPERATED | 15 | HOURL |
| RENTAL OF SKID LOADER, FULLY OPERATED | 15 | HOURL |
| RENT CRAWLER MNTED HYD EXCAVATOR, F.O. | 15 | HOURL |
| TEMPORARY SILT FENCE | 500 | LF |