

NOTICE TO CONTRACTORS

CALL ORDER 115
 STATE PROJECT NO. RD-8-7(1013)
 LOCATION: N-8, WEST OF SALEM
 COUNTIES: RICHARDSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for GR CULV SEED BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.0 MILES
 START DATE 06/08/2009 WORKING DAYS 100
 Price Range \$ 2,000,000 to \$ 4,000,000

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	83	SHEETS	\$ 20.75
CROSS SECTIONS (SHEETS X1 THRU X38)	38	SHEETS	\$ 9.50
STANDARD PLANS	17	SHEETS	\$ 4.25

SHEET NO.

1	TITLE PAGE
2	INDEX OF SHEETS
2-T1 - 2-T3	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-W1 - 2-W7	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1 - 2-N2	GENERAL INFORMATION
2-L1 - 2-L9	EROSION CONTROL
3 - 9	PLAN SHEETS
10	TRAFFIC CONTROL PLAN--BRIDGE CURB/RAIL REPAIR
11	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL YIELD CONTROL FOR LOW VOLUME, ONE LANE, TWO WAY TRAFFIC
12	TEMPORARY PAVEMENT MARKING PLAN
13 - 15	DRAINAGE STRUCTURE CROSS SECTIONS
16 - 22	SPECIAL PLAN 1 CONCRETE SLAB BRIDGE BRIDGE RAIL REMODEL BENT NO. 2 WALL EXTENSION CHANNEL SHAPING PLAN STA. 220+50.00
23 - 25	SPECIAL PLAN 2 BRIDGE RAIL REMODEL STA. 19+75.00
26 - 27	SPECIAL PLAN 3 BRIDGE RAIL REMODEL STA. 174+85.00
28 - 29	SPECIAL PLAN 1C 5' X 4' TWIN SPAN RC BOX CULVERT STA. 1282+23.97
30 - 31	SPECIAL PLAN 2C 12' X 6' SINGLE SPAN RC BOX CULVERT STA. 1310+93.00
32 - 33	SPECIAL PLAN 3C SOIL SAVER INLET STA. 220+73.00 TO STA. 221+30.00
34 - 35	SPECIAL PLAN 4C ENERGY DISSIPATER STA. 220+73.00 TO STA. 221+30.00
36	SPECIAL PLAN 5C CONCRETE HEADWALL STA. 220+69.00
37 - 49	SPECIAL PLAN 6C GUARDRAIL PLAN
50 - 52	SPECIAL PLAN 7C CABLE GUARDRAIL
R1 - R3	RIGHT-OF-WAY SHEETS
X1 - X38	CROSS SECTIONS

STANDARD PLANS

307	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
403-R2	(2 SHEETS) BENDS AND BREAKS FOR CONCRETE BOX CULVERTS
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		17 MGAL
RIGHT-OF-WAY MARKERS		8 EACH
EARTHWORK MEASURED IN EMBANKMENT	3,540	CY
REMOVE GUARDRAIL	2,819	LF
SEEDING, TYPE BUFFER		1 ACRE
EROSION CONTROL, CLASS 1C	8,967	SY
FABRIC SILT FENCE-LOW POROSITY	747	LF

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
PREPARATION OF STRUCTURE AT STA. 1282+23.97		1 EACH
PREPARATION OF STRUCTURE AT STA. 1310+93.00		1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	480	CY
EXCAVATION FOR BOX CULVERTS	80	CY
47B-3000 CONC FOR HDWL	16	CY
47B-3000 CONC FOR BOX CULV	59	CY
RE-STEEL FOR HEADWALL	1,219	LB
RE-STEEL FOR BOX CULVERT	5,518	LB
24" METAL FLARED-END SECTION	3	EACH
54" CULV PIPE 3,4,5	60	LF
24" CULV PIPE 3,4,5,6	113	LF

GROUP 5 SEEDING

MOBILIZATION	LUMP	LUMP
SEEDING, TYPE A		1 ACRE
SEEDING, TYPE B		20 ACRE
MULCH		47 TON

GROUP 6 BRIDGE AT STA. 220+50.00

MOBILIZATION	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	314	CY
SALVAGING AND PLACING TOPSOIL 6"	302	SY
BENT NO.2 EXCAVATION	LUMP	LUMP
47B-3000 CONC FOR BRIDGE		13 CY
47BD-4000 CONC FOR CONC. RAIL		19 CY
EPOXY COATED RE-STEEL FOR CONC RAIL	3,495	LB

PREP BRIDGE	1	EACH
AT STA. 220+50.00		
ROCK RIPRAP, TYPE B	445	TON
EPOXY COATED RE-STEEL	1,087	LB

GROUP 6A BRIDGE AT STA. 19+75.00

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR CONC. RAIL		9 CY
EPOXY COATED RE-STEEL FOR CONC RAIL	1,870	LB
PREP BRIDGE		1 EACH
AT STA. 19+75.00		

GROUP 6B BRIDGE AT STA. 174+85.00

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR CONC. RAIL		15 CY
EPOXY COATED RE-STEEL FOR CONC RAIL	2,950	LB
PREP BRIDGE		1 EACH
AT STA. 174+85.00		

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
CULV MOUNTED GDRL POST		8 EACH
W-BEAM GUARDRAIL	1,787	LF
CABLE GUARDRAIL	2,212	LF
BRIDGE APPROACH SECTIONS		12 EACH
TERMINAL ANCHORAGE SECTIONS		8 EACH
GUARDRAIL END TREATMENT, TYPE II		22 EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
REMOVE ASPH SURF FROM PAVEMENT	2,214	SY
GRAVEL SURFACE COURSE		175 TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS		355 SY
MAILBOX POST		10 EACH
CONC PVMT REPAIR TYPE A FULL DEPTH		14 CY
CONC PVMT REPAIR TYPE B FULL DEPTH		86 CY
CONC PVMT REPAIR TYPE C FULL DEPTH		222 CY
HYDRATED LIME FOR ASPHALT MIXTURES		225 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		5 TON
GRANULAR SUBDRAIN		75 EACH
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 SPECIAL(0.5)		500 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)		200 TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	22,290	TON
PLACE ASPH CONC FOR DRIVE & INTER	3,786	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH		27 TON
PERF GRADED BINDER (64-28)		1,214 TON
TACK COAT	20,280	GAL
WATER		185 MGAL
CRACKING & SEATING CONC PVMT	97,151	SY
EARTH SHOULDER CONSTRUCTION		736 STA
MILLING CONC FOR INLAYS		8 EACH
SURFACE UNDER GUARDRAIL		2,201 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	4,220	B DAY
TEMPORARY SIGN DAY	1,400	EACH
SIGN DAY	16,848	EACH
PAVEMENT MARKING REMOVAL		150 LF

TEMP PVMT MARKING, TYPE PAINT	2,900	LF
TEMP PVMT MARKING SURF PREP	2,900	LF
OVERLAY BROKEN LINES	737	STA
OVERLAY SOLID LINES	1,474	STA
FLAGGING	264	DAY
FURNISHING AND OPERATING PILOT VEHICLE	80	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	35	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	35	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	35	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	15	HOUR
TEMPORARY SILT FENCE	500	LF
TEMPORARY MULCH	2	TON