

NOTICE TO CONTRACTORS

CALL ORDER 300
FEDERAL PROJECT NO. STPD-116-4(102)
LOCATION: N-116, SOUTHWEST OF CONCORD
COUNTIES: DIXON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for GRAD,CULV,BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 08/03/2009 WORKING DAYS 50
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	23	SHEETS	\$	5.75
CROSS SECTIONS (SHEETS X1 THRU X4)	4	SHEETS	\$	1.00
STANDARD PLANS	9	SHEETS	\$	2.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2-W	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L2	CONSTRUCTION & REMOVALS
2-L3 - 2-L4	EROSION CONTROL
3	PLAN SHEET
4	EARTHWORK DATA SHEET
5	DRAINAGE STRUCTURE CROSS SECTION
6	SPECIAL PLAN 1C ABUTMENT PROTECTION STA. 33+83.00
7 - 8	SPECIAL PLAN 2C 10' X 8' QUINTUPLE SPAN RC BOX CULVERT STA. 48+40.00
9	SPECIAL PLAN 3C CONCRETE APRON STA. 48+40.00
R1 - R2	RIGHT-OF-WAY SHEETS
X1 - X4	CROSS SECTIONS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		488 CY
WATER		26 MGAL
EARTHWORK MEASURED IN EMBANKMENT		1,822 CY
ROCK RIPRAP, TYPE C		338 TON
REMOVE GUARDRAIL		300 LF
COVER CROP SEEDING		1 ACRE
EROSION CONTROL, CLASS 1D		717 SY
FABRIC SILT FENCE-LOW POROSITY		854 LF
FABRIC SILT FENCE, COIR FIBER		160 LF

GROUP 4 CULVERT AT STA. 48+40

MOBILIZATION	LUMP	LUMP
EXCAVATION FOR BOX CULVERTS		1,179 CY
47B-3000 CONC FOR BOX CULV		421 CY
RE-STEEL FOR BOX CULVERT		43,936 LB
REMOVE STRUCTURE		1 EACH
AT STA. 48+79		

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
HYDRATED LIME FOR ASPHALT MIXTURES		5 TON
BIT FOUNDATION COURSE 4"		1,053 SY
GRANULAR SUBDRAIN		6 EACH
ASPH CONC, TYPE SP4 SPECIAL(0.5)		520 TON
PERF GRADED BINDER (64-28)		28 TON
TACK COAT		160 GAL
WATER		3 MGAL
EARTH SHOULDER CONSTRUCTION		6 STA
SUBGRADE PREPARATION		1,053 SY
COLD MILLING, CLASS 4		764 SY
SEEDING, TYPE B		1 ACRE
MULCH		2 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		1,080 BDAY
SIGN DAY		1,440 EACH
CONTRACTOR FURNISHED SIGN DAY		180 EACH
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		15 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		15 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		15 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		15 HOUR
TEMPORARY SILT FENCE		500 LF
TEMPORARY MULCH		2 TON