

NOTICE TO CONTRACTORS

CALL ORDER 400
 FEDERAL PROJECT NO. STP-70-4(107)
 LOCATION: N-70, MIDDLE LOUP BRIDGE, ARCADIA
 COUNTIES: VALLEY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for GR BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES
 START DATE 07/20/2009 WORKING DAYS 155
 Price Range \$ 2,000,000 to \$ 4,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at GRAND ISLAND
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	75	SHEETS	\$	18.75
CROSS SECTIONS (SHEETS X1 THRU X3)	3	SHEETS	\$	0.75
STANDARD PLANS	7	SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W2	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-P1 - 2-P4	PHASING PLANS
2-L	CONSTRUCTION & REMOVAL
3 - 5	TYPICAL URBAN TRAFFIC CONTROL PLAN
6	TEMPORARY TRAFFIC SIGNAL
7	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS
8	TEMPORARY PAVEMENT MARKING PLAN
9 - 53	SPECIAL PLAN 1 ROLLED BEAM GIRDER BRIDGE (WIDEN & REHAB) STA. 271+76.25
54 - 60	SPECIAL PLAN 1C GUARDRAIL PLAN
61 - 62	SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER
R1 - R2	RIGHT-OF-WAY SHEETS
X1 - X3	CROSS SECTIONS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		20 MGAL
RIGHT-OF-WAY MARKERS		7 EACH
EARTHWORK MEASURED IN EMBANKMENT		950 CY
REMOVE ASPHALT SURFACE		475 SY
REMOVE INLET		1 EACH
REMOVE DISCHARGE STRUCTURE		2 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		18 CY
REMOVE GUARDRAIL		383 LF
TEMPORARY SURFACING		116 SY
8"		
SURFACE UNDER GUARDRAIL		269 SY
EROSION CONTROL, CLASS 1D		1,071 SY
FABRIC SILT FENCE-LOW POROSITY		233 LF

GROUP 6 BRIDGE AT STA. 271+76.25

MOBILIZATION	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		5,955 CY
RIPRAP FILTER FABRIC		993 SY
CONC FOR PVMT APPROACHES CLASS 47BD-4000		176 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH		32,025 LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PIER NO.1 EXCAVATION	LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT, TYPE A		81 LF
EXPANSION BEARING, TFE TYPE		24 EACH
FIXED BEARING		6 EACH
47B-3000 CONC FOR BRIDGE		217 CY
47BD-4000 CONC FOR BRIDGE		436 CY
PREP BRIDGE		1 EACH
AT STA. 271+76.25		
ACCESS BRIDGE	LUMP	LUMP
STEEL SUPERSTRUCTURE	LUMP	LUMP
AT STA. 271+76.25		
STRUC STEEL FOR SUBSTRUCTURE		2,090 LB
ROCK RIPRAP, TYPE C		755 TON
EPOXY COATED RE-STEEL		138,890 LB
SUBSURFACE DRAINAGE MATTING		46 SY
PIPE PILING		1,730 LF
STEEL SHEET PILING		1,509 SF
PAINTING PILES AND MISC STEEL	LUMP	LUMP
TEMP BRIDGE SHORING	LUMP	LUMP
BRIDGE SHORING	LUMP	LUMP
GRANULAR BACKFILL		245 CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		50 LF
BRIDGE APPROACH SECTIONS		4 EACH
GUARDRAIL END TREATMENT, TYPE II		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		3,284 BDAY
BARRICADE, TYPE III		2,388 BDAY
SIGN DAY		19,263 EACH
PAVEMENT MARKING REMOVAL		2,700 LF
TEMP PVMT MARKING, TYPE PAINT		3,350 LF
TEMP PVMT MARKING SURF PREP		1,500 LF
FLAGGING		34 DAY

CONCRETE PROTECTION BARRIER

750 LF

RELOCATE CONC PROTECTION BARRIER	700 LF
TEMPORARY RUMBLE STRIP	4 EACH
TEMPORARY TRAFFIC SIGNAL	1 EACH
FIELD OFFICE	1 EACH
TRAINING	1,000 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10 HOUR
TEMPORARY SEEDING	1 ACRE
TEMPORARY SILT FENCE	200 LF
TEMPORARY MULCH	2 TON