

NOTICE TO CONTRACTORS

CALL ORDER 500
FEDERAL PROJECT NO. NH-385-4(129)
LOCATION: US-385, L-7E NORTH
COUNTIES: BOX BUTTE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.9 MILES
START DATE 08/03/2009 WORKING DAYS 50
Price Range \$ 2,000,000 to \$ 4,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at GERING
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	31 SHEETS	\$	7.75
STANDARD PLANS	5 SHEETS	\$	1.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W8	WETLANDS
2-H1 - 2-H6	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 10	PLAN SHEETS
11	PAVEMENT MARKING PLAN
12	TYPICAL PAVEMENT MARKING PLAN
13	TEMPORARY PAVEMENT MARKING PLAN
14	SPECIAL PLAN 1C SUPERELEVATION PLAN

STANDARD PLANS

502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	7,040 BDAY
BARRICADE, TYPE III	360 BDAY
TEMPORARY SIGN DAY	602 EACH
SIGN DAY	6,948 EACH
OVERLAY BROKEN LINES	834 STA
OVERLAY SOLID LINES	1,669 STA
FLAGGING	86 DAY
FURNISHING AND OPERATING PILOT VEHICLE	43 DAY
FIELD OFFICE	1 EACH

TRAINING	1,000	HOUR
MOBILIZATION	LUMP	LUMP
4" WHITE PREF PVMT MRKNG T-4 GROOVED	505	LF
4" YEL PREF PVMT MRKNG, T-4, GROOVED	6,000	LF
12" YEL PREF PVMT MRKING T-4 GROOVED	430	LF
HYDRATED LIME FOR ASPHALT MIXTURES	129	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	200	TON
ASPH CONC, TYPE SPS	6,330	TON
ASPH CONC, TYPE SP4(0.5)	12,610	TON
HIGH RAP BASE	25,320	TON
PLACE ASPH CONC FOR DRIVE & INTER	856	SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	25	TON
PERF GRADED BINDER (58-28)	316	TON
PERF GRADED BINDER (58-34)	822	TON
PERF GRADED BINDER (64-28)	640	TON
TACK COAT	31,630	GAL
RENTAL OF LOADER, FULLY OPERATED	50	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	50	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	50	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HOUR
WATER	210	MGAL
EARTH SHOULDER CONSTRUCTION	836	STA
COLD MILLING, CLASS 3	436	STA
RUMBLE STRIPS, ASPHALT	837	STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	8	ACRE
TEMPORARY SILT FENCE	1,000	LF
MULCH	18	TON