

# NOTICE TO CONTRACTORS

CALL ORDER 600  
FEDERAL PROJECT NO. IM-80-4(129)  
LOCATION: I-80, DARR INTERCHANGE  
COUNTIES: DAWSON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 16, 2009. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES BITUMINOUS  
START DATE 06/01/2009 WORKING DAYS 75  
Price Range \$ 250,000 to \$ 1,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning March 24, 2009 at the Lincoln Central Office and March 30, 2009 at the District Engineer's Office at NORTH PLATTE  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	41	SHEETS	\$	10.25
CROSS SECTIONS (SHEETS X1 THRU X40)	40	SHEETS	\$	10.00
STANDARD PLANS	11	SHEETS	\$	2.75

## SHEET NO.

1	TITLE PAGE
2-T1 - 2-T5	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-H1 - 2-H3	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 5	PLAN SHEETS
6	PLAN SHEET--EROSION CONTROL
7	TRAFFIC CONTROL PLAN--DARR INTERCHANGE, 10' TRAFFIC LANE
8	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS--NARROW ROADWAY, 10' TRAVEL LANE
9	TEMPORARY TRAFFIC SIGNAL
10	PAVEMENT MARKING PLAN--DARR INTERCHANGE
11	TEMPORARY PAVEMENT MARKING PLAN
12	EARTHWORK DATA SHEET
13	DRAINAGE STRUCTURE CROSS SECTIONS
14 - 20	SPECIAL PLAN 1C GUARDRAIL PLAN
21 - 26	SPECIAL PLAN 2C BRIDGE REPAIRS, ABUTMENT REPAIRS, BRIDGE RAIL REMODEL, SILICA-FUME BRIDGE DECK OVERLAY, CONCRETE REPAIR & EPOXY INJECTION REPAIRS REF. POST NO. 231+13
27	SPECIAL PLAN 3C AREA INLET
28	SPECIAL PLAN 4C PAVEMENT APPROACH REPAIR REF. POST NO. 231+13
29	SPECIAL PLAN 5C TYPICAL TRAFFIC CONTROL PLAN--LANE CLOSURE (FREEWAY-INTERSTATE)
30 - 31	SPECIAL PLAN 6C CONCRETE PROTECTION BARRIER
X1 - X40	CROSS SECTIONS

## STANDARD PLANS

425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 6 BRIDGE AT R.P. 231.13

MOBILIZATION	LUMP	LUMP
EXPANSION JOINT SEAL		64 LF
PRECOMPRESSED POLY FOAM JOINT, TYPE A		14 LF
PRECOMPRESSED POLY FOAM JOINT, TYPE B		60 LF
CLASS I REPAIR	1,094 SY	
CLASS II REPAIR	437 SY	
CLASS III REPAIR	15 SY	
PLACE, FINISH, & CURE CONC OVERLAY-SF	1,094 SY	
47B-3000 CONC FOR BRIDGE	43 CY	
47BD-4000 CONC FOR CONC. RAIL	42 CY	
CONCRETE FOR OVERLAYS-SF	109 CY	
EPOXY COATED RE-STEEL FOR CONC RAIL	7,005 LB	
PREP BRIDGE		1 EACH
AT R.P. 231.13		
EPOXY COATED RE-STEEL	1,015 LB	
CRACK EPOXY INJECTION	650 LF	

## GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		5 MGAL
EARTHWORK MEASURED IN EMBANKMENT	332 CY	
W-BEAM GUARDRAIL	243 LF	
REMOVE GUARDRAIL	711 LF	
BRIDGE APPROACH SECTIONS	4 EACH	
GUARDRAIL END TREATMENT, TYPE II	4 EACH	
EROSION CONTROL, CLASS 1B	919 SY	

## GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
REMOVE ASPHALT SURFACE	321 SY	
REMOVE CURB	99 LF	
REMOVE INLET	2 EACH	
CONC PVTM REPAIR TYPE A FULL DEPTH	9 CY	
CONC PVTM REPAIR TYPE B FULL DEPTH	66 CY	
CONC PVTM REPAIR TYPE C FULL DEPTH	39 CY	
CONC PVTM, PR-3500	28 CY	
JOINT REPAIR		
47B-3000 CONC FOR INLET & JUNCTION BOXES	1 CY	
47B-3000 CONC FOR CONCRETE CO	1 CY	
EPOXY RE-STEEL FOR INLET & JCT. BOX	149 LB	
RE-STEEL FOR COLLARS	76 LB	
18" CORRUGATED METAL PIPE	6 LF	
BRIDGE APPROACH REPAIR	3 CY	
HYDRATED LIME FOR ASPHALT MIXTURES	22 TON	
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	2 TON	
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	200 TON	
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	100 TON	
ASPH CONC, TYPE SP4(0.5)	2,150 TON	
SURFACING 6"	566 SY	
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	10 TON	
PERF GRADED BINDER (64-28)	121 TON	
TACK COAT	2,670 GAL	
WATER	29 MGAL	

COLD MILLING, CLASS 2	7,534 SY
SEEDING, TYPE B	2 ACRE
MULCH	5 TON

## GROUP 10 GENERAL ITEMS

SURV OF TEMP TRAFFIC CONT DEVICES	95 CDAY
BARRICADE, TYPE II	2,810 BDAY
BARRICADE, TYPE III	872 BDAY
TEMPORARY SIGN DAY	376 EACH
SIGN DAY	6,965 EACH
PAVEMENT MARKING REMOVAL	5,000 LF
TEMP PVMT MARKING, TYPE PAINT	3,250 LF
TEMP PVMT MARKING SURF PREP	1,625 LF
PERMANENT PAVEMENT MARKING PAINT	16,250 LF
FLASHING ARROW PANEL	8 DAY
FLAGGING	40 DAY
FURNISHING AND OPERATING PILOT VEHICLE	15 DAY
CONCRETE PROTECTION BARRIER	725 LF
RELOCATE CONC PROTECTION BARRIER	725 LF
TEMPORARY RUMBLE STRIP	4 EACH
TEMPORARY TRAFFIC SIGNAL	1 EACH
TRAFFIC CONTROL MANAGEMENT	30 DAY
FIELD OFFICE	1 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10 HOUR
TEMPORARY SILT FENCE	500 LF
TEMPORARY MULCH	2 TON