

NOTICE TO CONTRACTORS

CALL ORDER 100
STATE PROJECT NO. RD-79-2(1014)
LOCATION: N-79, EAST JUNCTION N-92 NORTH
COUNTIES: SAUNDERS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 21, 2009. At that time the bids will be opened and read for GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.9 MILES
START DATE 07/06/2009 WORKING DAYS 70
Price Range \$ 2,000,000 to \$ 4,000,000

Plans and specifications may be seen beginning April 28, 2009 at the Lincoln Central Office and May 04, 2009 at the District Engineer's Office at LINCOLN

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	48	SHEETS	\$	12.00
CROSS SECTIONS (SHEETS X1 THRU X49)	49	SHEETS	\$	12.25
STANDARD PLANS	14	SHEETS	\$	3.50

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-W1 - 2-W7	WETLANDS
2-H1 - 2-H7	HORIZONTAL ALIGNMENT ORIENTATION & CONTROL POINT TIES
2-N	GENERAL INFORMATION
3 - 9	PLAN SHEETS
10	TEMPORARY PAVEMENT MARKING PLAN
11 - 13	EARTHWORK DATA SHEETS
14	DRAINAGE STRUCTURE CROSS SECTION
15 - 16	SPECIAL PLAN 1C PARAPET & WING EXTENSION AT INLET STA. 93+47.00 LT.
17 - 18	SPECIAL PLAN 2C PARAPET & WING EXTENSION AT OUTLET STA. 93+47.00 RT.
19 - 25	SPECIAL PLAN 3C GUARDRAIL PLAN
26 - 28	SPECIAL PLAN 4C CABLE GUARDRAIL
X1 - X49	CROSS SECTIONS

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
307	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP

WATER	57 MGAL
EARTHWORK MEASURED IN EMBANKMENT	3,784 CY
CABLE GUARDRAIL	3,744 LF
REMOVE GUARDRAIL	3,929 LF
REMOVE & SALVAGE GUARDRAIL	300 LF
RESET GUARDRAIL	300 LF
TERMINAL ANCHORAGE SECTIONS	18 EACH
GUARDRAIL END TREATMENT, TYPE II	8 EACH
EROSION CONTROL, CLASS 1D	11,333 SY
FABRIC SILT FENCE-LOW POROSITY	5,505 LF

GROUP 9 BITUMINOUS

	LUMP	LUMP
MOBILIZATION		
DELINEATOR, TYPE III		22 EACH
REMOVE ASPHALT SURFACE		602 SY
GRAVEL SURFACE COURSE		130 TON
CRUSHED ROCK SURFACE COURSE		80 TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS		546 SY
MAILBOX POST		9 EACH
EXCAVATION FOR BOX CULVERTS		5 CY
47B-3000 CONC FOR BOX CULV		5 CY
RE-STEEL FOR BOX CULVERT		815 LB
HYDRATED LIME FOR ASPHALT MIXTURES		133 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		3 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4 SPECIAL(0.5)		300 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4 SPECIAL(0.5)		250 TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)		13,000 TON
HIGH RAP BASE		26,920 TON
PLACE ASPH CONC FOR DRIVE & INTER		4,659 SY
PERF GRAD BIND (64-28)FOR ST MAINT PATCH		15 TON
PERF GRADED BINDER (58-34)		942 TON
PERF GRADED BINDER (64-28)		662 TON
TACK COAT		26,760 GAL
WATER		182 MGAL
EARTH SHOULDER CONSTRUCTION		727 STA
TRENCHED WIDENING		727 STA
COLD MILLING, CLASS 3		365 STA
SURFACE UNDER GUARDRAIL		2,278 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		10 ACRE
MULCH		23 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	24,336 BDAY
BARRICADE, TYPE III	734 BDAY
TEMPORARY SIGN DAY	560 EACH
SIGN DAY	8,567 EACH
OVERLAY BROKEN LINES	728 STA
OVERLAY SOLID LINES	1,456 STA
FLAGGING	100 DAY
FURNISHING AND OPERATING PILOT VEHICLE	40 DAY
TRAFFIC CONTROL MANAGEMENT	119 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP
RENTAL OF LOADER, FULLY OPERATED	90 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	30 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	90 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	90 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	60 HOUR
TEMPORARY SILT FENCE	500 LF