

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 2
PROJECT NO. RD-159-7(1012)
CONTROL NO. 12995
CALL ORDER 105
US-159, FALLS CITY - RULO
LETTING DATE: MAY 21, 2009

On page 50 in the Special Provisions, in the provision titled **SECTION 1028 – SUPERPAVE ASPHALTIC CONCRETE**, Table 1028.19 is void and superseded by the following:

Table 1028.19

Production Tolerances*	
Test	Allowable Single Test Deviation from Specification
Voids in the Mineral Aggregate	-1.00% from Min.
Dust to Asphalt Ratio	None
Coarse Aggregate Angularity	-5% below Min.
Fine Aggregate Angularity	-0.50% below Min. for cold feed -1.00% below Min. for ignition oven
Minimum Binder Content 0.375 inch (9.5 mm) Gradation Band = 5.5% 0.5 inch (12.5 mm) Gradation Band and Type SPS = 5.0%	None

* These tolerances are applied to the mix design specification values, not the submitted mix design targets.

* * * * *

The Special Provisions are amended to include the following:

**SPECIAL PROSECUTION AND PROGRESS
(Tentative Start Date and the Availability of Material)**

Depending on the availability of GTR Modified Performance Graded (PG) Binder, the start of the project may be delayed until such time as the product can be delivered to the project.

Project No. RD-159-7(1012)
Addendum No. 2
Page Two

DEPARTMENT OF ROADS

Original Signed by Claude Oie

Claude Oie
Construction Engineer

Issued: May 18, 2009

CO:105AD205

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.