

NOTICE TO CONTRACTORS

CALL ORDER 400
FEDERAL PROJECT NO. STPD-30-4(148)
LOCATION: N-10/US-30, IN KEARNEY
COUNTIES: BUFFALO

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 21, 2009. At that time the bids will be opened and read for GR CONC PAVE CULV ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT

START DATE 07/20/2009 WORKING DAYS 130
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning April 28, 2009 at the Lincoln Central Office and May 04, 2009 at the District Engineer's Office at GRAND ISLAND. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	132	SHEETS	\$	33.00
CROSS SECTIONS (SHEETS X1 THRU X26)	26	SHEETS	\$	6.50
STANDARD PLANS	21	SHEETS	\$	5.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-A1 - 2-A3	PHOTO MAPS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1 - 2-N2	GENERAL INFORMATION
2-P1 - 2-P11	PHASING PLANS
2-L1 - 2-L7	ROADWAY GEOMETRICS
2-L8 - 2-L14	SIDEWALK GEOMETRICS
2-L15 - 2-L20	GRADES
2-L21 - 2-L27	DRAINAGE
2-L28 - 2-L34	CONSTRUCTION
2-L35 - 2-L41	REMOVAL
3 - 8	PLAN & PROFILE SHEETS
9 - 16	TRAFFIC SIGNAL PLAN
17	TEMPORARY TRAFFIC SIGNAL PLAN
18 - 20	TYPICAL URBAN TRAFFIC CONTROL PLAN
21 - 31	TEMPORARY TRAFFIC CONTROL--PHASES
32	TYPICAL PAVEMENT MARKING PLAN
33	PAVEMENT MARKING DETAILS
34 - 35	PAVEMENT MARKING PLAN
36	TEMPORARY PAVEMENT MARKING PLAN
37 - 40	PLAN SHEETS--UTILITIES
41 - 50	ROADWAY LIGHTING PLANS
51	EARTHWORK DATA SHEET
52 - 61	DRAINAGE STRUCTURE CROSS SECTIONS
62	SPECIAL PLAN 1C CURB RAMPS
63 - 64	SPECIAL PLAN 2C TEMPORARY SILT CHECKS
R1 - R6	RIGHT-OF-WAY SHEETS
X1 - X26	CROSS SECTIONS

STANDARD PLANS

301-R9	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
411	(4 SHEETS) BEDDING AND BACKFILL REQUIREMENTS FOR CONCRETE PIPE
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
435-R1	(3 SHEETS) MANHOLE
443-R7	(2 SHEETS) CURB INLETS AND JUNCTION BOX
502	SILT FENCE DETAILS
914-R5	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)		7,643 CY
RE-ESTABLISH PROPERTY CORNER		4 EACH
REMOVE PAVEMENT		17,529 SY
SAWING PAVEMENT		4,000 LF
REMOVE ASPHALT SURFACE		143 SY
REMOVE DRIVEWAY		2,233 SY
REMOVE WALK		3,124 SY
REMOVE CONCRETE MEDIAN SURFACING		1,564 SY
REM SIGN, STRUCTURE, AND FOUNDATION		2 EACH

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
CRUSHED ROCK SURFACE COURSE		400 CY
TIE BARS		350 EACH
CONC 47B-3500 BARRIER CURB		1,627 LF
CONC 47B-3000 SIDEWALKS		2,504 SY
CONC 47B-3000 IMPRINTED SURFACING		592 SY
CONC 47B-3000 MEDIAN SURFACING		194 SY
CONC 47B-3000 IMPRINTED MEDIAN SURF		768 SY
CONC 47B-3500 DRIVEWAY		1,569 SY
6" CONC PVMT, 47B-3500		537 SY
10" DOWELED CONC PVMT, 47B-3500		19,186 SY
ADJUST MANHOLE TO GRADE		5 EACH
RECONSTRUCT MANHOLE		1 EACH
4" PERFORATED PIPE UNDERDRAIN		4,121 LF
4" WHITE PREF PVMT MRKNG T-4 GROOVED		4,100 LF
12" WHT PREF PVMT MRKING T-4 GROOVED		144 LF
24" WHITE PREF PVMT MKING T-4 GROOVED		528 LF
FOUNDATION COURSE		19,186 SY
4"		
TEMPORARY SURFACING		334 SY
10"		
PREP OF INTER & DRIVE		1,679 SY
WATER		68 MGAL
EARTH SHOULDER CONSTRUCTION		44 STA
SUBGRADE PREPARATION		19,186 SY
SODDING		1,459 SY
ADJUST VALVE BOX TO GRADE		29 EACH

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE MANHOLE		4 EACH
REMOVE INLET		9 EACH
REMOVE JUNCTION BOX		2 EACH
CAST IRON COVER & FRAME	5,125	LB
CAST IRON COVER, FRAME & FLANGE	5,830	LB
MANHOLE		8 EACH
REMOVE SEWER PIPE	2,258	LF
47B-3000 CONC FOR INLET & JUNCTION BOXES		83 CY
47B-3000 CONC FOR CONCRETE CO		5 CY
RE-STEEL FOR INLET & JCT BOX	5,505	LB
RE-STEEL FOR COLLARS		333 LB
CURB INLET SEDIMENT FILTER		24 EACH
15" STORM SEWER PIPE 1,7,8		781 LF
18" STORM SEWER PIPE 1,7,8		177 LF
36" STORM SEWER PIPE 1,7,8		895 LF
48" STORM SEWER PIPE 1		99 LF
60" STORM SEWER PIPE 1		10 LF
24" RND EQ STORM SEWER PIPE 1		279 LF
30" RND EQ STORM SEWER PIPE 1		429 LF
36" RND EQ STORM SEWER PIPE 1		494 LF

GROUP 4A WATER MAIN CONSTRUCTION

MOBILIZATION	LUMP	LUMP
ABANDON WATER SERVICE		1 EACH
INSTALL CONNECTION		1 EACH
8"		
6" WATER MAIN PIPE		98 LF
6" VALVE		1 EACH
INSTALL FIRE HYDRANT		1 EACH
AT STA. 39+47		
8" X 6" TEE		1 EACH
6" - 45 DEGREE BEND		4 EACH
REPLACE INOPERABLE VALVE	LUMP	LUMP
8"		
LOWER WATER SERVICE		5 EACH
LOWER 8" WATER MAIN		7 EACH
LOWER 12" WATER MAIN		4 EACH
RELOCATE WATER SERVICE		13 EACH
REMOVE TEE		1 EACH
8" X 4"		
REMOVE WATER MAIN PIPE		30 LF
4"		
REMOVE VALVE		1 EACH
4"		
REMOVE HYDRANT		1 EACH
AT STA. 39+47		
REMOVE AND RESET HYDRANT		4 EACH

GROUP 8B ELECTRICAL

TEMPORARY TRAFFIC SIGNAL		1 EACH
AT AVE. E		
TEMPORARY TRAFFIC SIGNAL		1 EACH
AT AVE. G		
MOBILIZATION	LUMP	LUMP
PULL BOX, TYPE PB-1A		2 EACH
PULL BOX, TYPE PB-5		2 EACH
PULL BOX, TYPE PB-6		1 EACH
PEDESTRIAN PUSHBUTTON, PPB		4 EACH
VEHICLE DETECTOR, TYPE A PREFORMED		32 EACH
VEHICLE DETECTOR, TYPE B PREFORMED		8 EACH
LIGHTING CONTROL CENTER, R		2 EACH

1 1/2" CONDUIT IN TRENCH	1,979 LF
2" CONDUIT IN TRENCH	145 LF
1 1/2" CONDUIT UNDER ROADWAY	1,130 LF
2" CONDUIT UNDER ROADWAY	53 LF
3" CONDUIT UNDER ROADWAY	76 LF
2/C #14 AWG TRAF SIG CABLE	708 LF
12/C #14 AWG TRAF SIG CABLE	708 LF
2/C #14 AWG DETECTOR LEAD-IN CABLE	1,527 LF
GROUNDING CONDUCTOR	240 LF
STREET LIGHT CABLE, NO. 6 BARE	3,190 LF
STREET LIGHT CABLE, NO. 6 USE	6,218 LF
2 PAIR COMMUNICATION CABLE	3,048 LF
INST TRAF SIG CONTROLLER, TC-170	1 EACH
REMOVE LIGHTING UNIT	12 EACH
REMOVE PEDESTRIAN PUSHBUTTON	4 EACH
REMOVE PULL BOX	1 EACH
REMOVE GROUNDING CONDUCTOR	1,692 LF
REMOVE TRAFFIC SIGNAL CABLE	5,482 LF
RELOCATE STREET LIGHTING UNIT	2 EACH
RELOCATE PULL BOX	8 EACH
TYPE PB-1	
RELOCATE PULL BOX	5 EACH
TYPE PB-1A	

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	17,967 BDAY
BARRICADE, TYPE III	3,671 BDAY
SIGN DAY	5,342 EACH
CONTRACTOR FURNISHED SIGN DAY	2,156 EACH
PAVEMENT MARKING REMOVAL	2,150 LF
TEMP PVMT MARKING, TYPE PAINT	14,400 LF
FLASHING ARROW PANEL	437 DAY
FIELD OFFICE	1 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	5 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	5 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5 HOUR
TEMPORARY SILT CHECK	500 LF
TEMPORARY SILT FENCE	500 LF