

# NOTICE TO CONTRACTORS

CALL ORDER 710  
FEDERAL PROJECT NO. URB-6156(2)  
LOCATION: WEST J STREET, WEST 10th-NORRIS AVENUE, McCOOK  
COUNTIES: RED WILLOW

The Nebraska Department of Roads will receive sealed bids for the CITY OF McCOOK in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on July 09, 2009 .  
At that time the bids will be opened and read for  
CONC PAVE CULV

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT  
START DATE 07/27/2009 WORKING DAYS 75  
Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning June 18, 2009 at the Lincoln Central Office and June 18, 2009 at the District Engineer's Office at MCCOOK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	22 SHEETS	\$	5.50
STANDARD PLANS	10 SHEETS	\$	2.50

## SHEET NO.

1	TITLE PAGE
2-T1	TYPICAL CROSS SECTIONS/DETAILS
2-S	SUMMARY OF QUANTITIES
2-A1	PHOTO MAP
2-P1	PHASING PLAN
3 - 9	CONSTRUCTION/PLAN & PROFILE SHEETS
10 - 12	REMOVALS
13	STORM SEWER PLAN/DETAILS
14	WATER PLAN/DETAILS
15	SIGNAGE PLAN
16	PAINTING PLAN
17 - 19	SPECIAL PLAN 1C TYPICAL URBAN TRAFFIC CONTROL PLAN

## STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
443-R7	(2 SHEETS) CURB INLETS AND JUNCTION BOX
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
REMOVE PAVEMENT	8,198 SY	
REMOVE ASPHALT SURFACE	38 SY	
REMOVE WALK	1,001 SY	
TIE BARS	2,570 EACH	
COMB CONC 47B-3500 CURB & GUTTER 6"	913 SY	
COMB CONC 47B-3500 CURB & GUTTER 8"	98 SY	
CONC 47B-3000 SIDEWALKS	887 SY	
CONC 47B-3500 DRIVEWAY	63 SY	

PAVEMENT PATCHING	38 SY
8" CONC PVMT, 47B-3500	13,850 SY
ADJUST MANHOLE TO GRADE	11 EACH
4" WHITE PERMANENT PVMT MARKING PAINT	400 LF
4" YEL PERMANENT PVMT MARKING PAINT	2,012 LF
12" WHITE PERMANENT PVMT MARKING PAINT	102 LF
ARROW	4 EACH
ARROW	4 EACH
DOUBLE	
BIT FOUNDATION COURSE	14,868 SY
3"	
SUBGRADE PREPARATION	15,819 SY
COLD MILLING, CLASS 4	12,642 SY
ADJUST VALVE BOX TO GRADE	6 EACH

#### GROUP 4 CULVERTS

	LUMP	LUMP
MOBILIZATION		
REMOVE MANHOLE		1 EACH
AREA INLET		1 EACH
AT STA. 58+76.61 LT..		
AREA INLET		1 EACH
AT STA. 58+76.61 RT.		
INLET		5 EACH
LID		
CURB INLET		1 EACH
AT STA. 36+33.43 RT.		
CURB INLET		1 EACH
AT STA. 56+37.83 LT.		
CURB INLET		1 EACH
AT STA. 56+38.92 RT.		
CURB INLET		1 EACH
AT STA. 57+09.68 LT.		
CURB INLET		1 EACH
AT STA. 57+10.80 RT.		
MANHOLE		1 EACH
AT STA. 56+46.31 LT.		
MANHOLE		1 EACH
AT STA. 56+61.23 RT.		
47B-3000 CONC FOR CONCRETE CO		1 CY
RE-STEEL FOR COLLARS		94 LB
24" REINF CONCRETE SEWER PIPE		18 LF
10" DUCTILE IRON SEWER PIPE		88 LF
12" DUCTILE IRON SEWER PIPE		234 LF
16" DUCTILE IRON SEWER PIPE		44 LF
CURB STOP AND BOX		40 EACH
1" WATER SERVICE		887 LF
METER PIT		1 EACH
FIRE HYDRANT		2 EACH
5'-0" BURY		

#### GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	625 BDAY
BARRICADE, TYPE III	3,876 BDAY
SIGN DAY	2,080 EACH
CONTRACTOR FURNISHED SIGN DAY	1,646 EACH
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP