NOTICE TO CONTRACTORS

CALL ORDER 105

FEDERAL PROJECT NO. IM-NH-80-9(841)

LOCATION: I-80, 134th STREET BRIDGE, LINCOLN

COUNTIES: LANCASTER

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on September 03, 2009. At that time the bids will be opened and read for GRAD, MSE, CULV, BR, GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 10/13/2009 WORKING DAYS 115
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning August 11, 2009 at the Lincoln Central Office and August 17, 2009 at the District Engineer's Office at LINCOLN Additional letting information may be found at the Nebraska Department of Roads Web Site at http://www.dor.state.ne.us/letting/.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	118	SHEETS	\$ 29.50
CROSS SECTIONS (SHEETS X1 THRU X22)	22	SHEETS	\$ 5.50
STANDARD PLANS	13	SHEETS	\$ 3.25

SHEET NO.

2-K1 - 2-K2 2-W 2-H1 - 2-H2 2-N 2-L1 - 2-L4 2-L5 2-L6 - 2-L7 3	TITLE PAGE TYPICAL CROSS SECTIONS SUMMARY OF QUANTITIES SUMMARY OF SOILS & GEOTECHNICAL INFORMATION WETLANDS HORIZONTAL ALIGNMENT & ORIENTATION GENERAL INFORMATION & DETOUR LOCATION MAP CONSTRUCTION, REMOVALS, & DRAINAGE GEOMETRICS EROSION CONTROL PLAN & PROFILE SHEET
	SIGN LOCATION PLAN
	TYPICAL TRAFFIC CONTROL PLANTYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
7	TYPICAL TRAFFIC CONTROLFREEWAY RAMP CLOSURE
8	TYPICAL TRAFFIC CONTROL PLANINERTIAL BARRIER SYSTEM
9	TYPICAL TRAFFIC CONTROL PLANFREEWAY CLOSURE
10	TEMPORARY PAVEMENT MARKING PLAN
11 - 13	EARTHWORK DATA SHEETS
14 - 15	DRAINAGE STRUCTURE CROSS SECTIONS
16 - 48	SPECIAL PLAN 1 NU2000 PRESTRESSED CONCRETE GIRDER BRIDGE STA. 15+10.37
49 - 81	SPECIAL PLAN 2 STEEL PLATE GIRDER BRIDGE STA. 15+10.37
82 - 83	SPECIAL PLAN 1C 10' X 6' SINGLE SPAN RC BOX CULVERT
	STA. 19+10.00
84 - 85	SPECIAL PLAN 2C 5-BAR GRATE INLET WITH CURB
	SPECIAL PLAN 3C 5-BAR GRATE INLET WITH CURB
88 - 89	SPECIAL PLAN 4C MECHANICALLY STABILIZED EARTH WALL
90 - 96	SPECIAL PLAN 5C GUARDRAIL PLAN
97	SPECIAL PLAN 6C EROSION CHECKS (ALL TYPES)
	& FABRIC SILT CHECKS
	SPECIAL PLAN 7C TEMPORARY SILT CHECKS
	RIGHT-OF-WAY SHEETS
X1 - X22	CROSS SECTIONS

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
411	(4 SHEETS) BEDDING AND BACKFILL REQUIREMENTS
	FOR CONCRETE PIPE
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROLROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION GENERAL CLEARING AND GRUBBING WATER	LUMP LUMP 240	LUMP LUMP MGAL
EARTHWORK MEASURED IN EMBANKMENT	28,415	CY
GRAVEL SURFACE COURSE	197	TON
CRUSHED ROCK EMBEDMENT	5,182	SY
CRUSHED ROCK SURFACE COURSE	548	TON
REMOVE GUARDRAIL	859	LF
REMOVE SIGN	2	EACH
REMOVE SIGN STRUCTURE	1	EACH
REMOVE LUMINAIRE	2	EACH
SEEDING, TYPE A	3	ACRE
SEEDING, TYPE B	1	ACRE
COVER CROP SEEDING	4	ACRE
EROSION CONTROL, CLASS 1D	11,797	SY
EROSION CHECKS, TYPE WATTLE	160	LF
FABRIC SILT FENCE-LOW POROSITY	1,470	LF
MULCH	9	TON

GROUP 1A MSE WALL

MOBILIZATION	LUMP	LUMP
EXCAVATION FOR MSE WALL	2,785	CY
CONCRETE FACE PANELS	6,207	SF
CONCRETE LEVELING PADS	375	LF
COPING	391	LF
CONCRETE COATING	LUMP	LUMP
AT STA. 13+64.84		
CONCRETE COATING	LUMP	LUMP
AT STA. 16+55.91		
SELECT GRANULAR BACKFILL FOR MSE WALL	4,793	CY

GROUP 4 CULVERTS

MOBILIZATION RIPRAP FILTER FABRIC REMOVE INLET	4	LUMP SY EACH
CAST IRON GRATE & FRAME PREPARATION OF STRUCTURE AT STA. 19+14.62	2,520 1	LB EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL EXCAVATION FOR BOX CULVERTS 47B-3000 CONC FOR BOX CULV	464 196 132	CY
47B-3000 CONC FOR INLET & JUNCTION BOXES RE-STEEL FOR BOX CULVERT RE-STEEL FOR INLET & JCT BOX	7 15,945 610	
24" METAL FLARED-END SECTION ROCK RIPRAP, TYPE B 24" CULV PIPE 3,4,5,6	2 35 176	EACH TON LF
24" CULV PIPE 2,4,5,7,8	109	LF

GROUP 6 BRIDGE AT STA. 15+10.37

MOBILIZATION CONC FOR PVMT APPROACHES CLASS 47BD-4000 EPOXY COATED RE-STEEL FOR PVMT APPROACH ABUTMENT NO.1 EXCAVATION ABUTMENT NO.2 EXCAVATION PIER NO.1 EXCAVATION PREFORMED EXPANSION JOINT, TYPE B EXPANSION BEARING, TFE TYPE FIXED BEARING 47B-3000 CONC FOR BRIDGE 47BD-4000 CONC FOR BRIDGE	LUMP LUMP 158 CY 28,480 LB LUMP LUMP LUMP LUMP LUMP LUMP T9 LF 8 EACH 8 EACH 340 CY 408 CY
PRECAST/PRESTRESSED CONC SUPERSTR AT STA. 15+10.37	LUMP LUMP
REMOVE STRUCTURE AT STA. 15+26.89	1 EACH
EXPANDED POLYSTYRENE GEOFOAM STEEL DIAPHRAGM EPOXY COATED RE-STEEL SUBSURFACE DRAINAGE MATTING HP 12"X53# STEEL PILING TEMP BRIDGE SHORING BRIDGE SHORING CONCRETE COATING AT STA. 15+10.37 GRANULAR BACKFILL	605 CY 6 EACH 122,605 LB 242 SY 5,820 LF LUMP LUMP LUMP LUMP LUMP LUMP LUMP
GROUP 6A BRIDGE AT STA. 15+10.37	300 C1
MOBILIZATION CONC FOR PVMT APPROACHES CLASS 47BD-4000 EPOXY COATED RE-STEEL FOR PVMT APPROACH ABUTMENT NO.1 EXCAVATION ABUTMENT NO.2 EXCAVATION PIER NO.1 EXCAVATION PREFORMED EXPANSION JOINT, TYPE A EXPANSION BEARING, TFE TYPE FIXED BEARING 47B-3000 CONC FOR BRIDGE 47BD-4000 CONC FOR BRIDGE REMOVE STRUCTURE AT STA. 15+26.89	28,480 LB LUMP LUMP LUMP LUMP LUMP T9 LF 8 EACH 8 EACH 344 CY 389 CY 1 EACH
STEEL SUPERSTRUCTURE AT STA. 15+10.37 EXPANDED POLYSTYRENE GEOFOAM EPOXY COATED RE-STEEL SUBSURFACE DRAINAGE MATTING HP 12"X53# STEEL PILING TEMP BRIDGE SHORING BRIDGE SHORING CONCRETE COATING AT STA. 15+10.37	LUMP 605 CY 133,345 LB 242 SY 5,540 LF LUMP LUMP LUMP LUMP LUMP LUMP LUMP LUMP LUMP
GRANULAR BACKFILL GROUP 7 GUARDRAIL	360 CY
MOBILIZATION W-BEAM GUARDRAIL PERMANENT INERTIAL BARRIER SYSTEM BRIDGE APPROACH SECTIONS GUARDRAIL END TREATMENT, TYPE II SURFACE UNDER GUARDRAIL	LUMP LUMP 112 LF 2 EACH 4 EACH 4 EACH 52 SY

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE		9,008	
BARRICADE, TYPE		5,302	
TEMPORARY SIGN	DAY	·	EACH
SIGN DAY		20,416	
CONTRACTOR FURN	ISHED SIGN DAY	* - *	EACH
PAVEMENT MARKIN	G REMOVAL	2,200	LF
TEMP PVMT MARKI	NG, TYPE PAINT	5,700	LF
TEMP PVMT MARKI	NG SURF PREP	5,700	LF
FLASHING ARROW	PANEL	62	DAY
CONCRETE PROTEC	TION BARRIER	1,000	LF
RELOCATE CONC P	ROTECTION BARRIER	1,100	LF
RELOC INERTIAL	BARRIER SYSTEM	4	EACH
INERTIAL BARRIE	R SYSTEM	4	EACH
REPLACEMENT MOD	ULE	5	EACH
FIELD OFFICE		1	EACH
TRAINING		1,000	HOUR
MOBILIZATION		LUMP	LUMP
CONSTRUCTION ST	AKING AND SURVEYING	LUMP	LUMP
TEMPORARY FENCE		500	LF
RENTAL OF LOADE	R, FULLY OPERATED	25	HOUR
RENTAL OF DUMP	TRUCK, FULLY OPERATED	25	HOUR
RENTAL OF SKID	LOADER, FULLY OPERATED	25	HOUR
RENT CRAWLER MN	TED HYD EXCAVATOR, F.O.	25	HOUR
TEMPORARY SILT	CHECK	100	LF
TEMPORARY SILT	FENCE	750	LF
TEMPORARY EARTH	CHECK	100	LF
TEMPORARY MULCH		2	TON