

NOTICE TO CONTRACTORS

CALL ORDER 105
STATE PROJECT NO. S-1-7(1006)
LOCATION: N-1, ELMWOOD NORTH & SOUTH
COUNTIES: CASS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 08, 2009. At that time the bids will be opened and read for CULV BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 2.4 MILES
START DATE 08/23/2010 WORKING DAYS 35
Price Range \$ 250,000 to \$ 1,000,000

Plans and specifications may be seen beginning September 15, 2009 at the Lincoln Central Office and September 21, 2009 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	39	SHEETS	\$	9.75
CROSS SECTIONS (SHEETS X1 THRU X30)	30	SHEETS	\$	7.50
STANDARD PLANS	24	SHEETS	\$	6.00

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S1 - 2-S2	SUMMARY OF QUANTITIES & DETOUR LOCATION MAP
2-W1 - 2-W5	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L5	CONSTRUCTION & REMOVAL
3 - 5	PLAN SHEETS
6 - 8	TYPICAL URBAN TRAFFIC CONTROL PLAN
9	TEMPORARY PAVEMENT MARKING PLAN
10	EARTHWORK DATA SHEET
11 - 12	DRAINAGE STRUCTURE CROSS SECTIONS
13 - 14	SPECIAL PLAN 1C 6.5' X 5' SINGLE SPAN RC BOX CULVERT STA. 112+24.00
15	SPECIAL PLAN 2C DOWELING INTO EXISTING CONCRETE BOX CULVERT FOR CULVERT EXTENSION STA. 112+24.00
16	SPECIAL PLAN 3C CURB RAMPS
17	SPECIAL PLAN 4C GUARDRAIL PLAN
R1 - R4	RIGHT-OF-WAY SHEETS
X1 - X30	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
307-R1	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
411	(4 SHEETS) BEDDING AND BACKFILL REQUIREMENTS FOR CONCRETE PIPE
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
804	PRECAST CONCRETE R.O.W. MARKER
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
REMOVE HEADWALLS FROM CULV		6 EACH
PREPARATION OF STRUCTURE		1 EACH
AT STA. 112+24		
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		930 CY
EXCAVATION FOR BOX CULVERTS		68 CY
47B-3000 CONC FOR BOX CULV		23 CY
RE-STEEL FOR BOX CULVERT		2,112 LB
24" CONCRETE FLARED-END SECTION		8 EACH
24" CULV PIPE 2		355 LF

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
RIGHT-OF-WAY MARKERS		24 EACH
EARTHWORK MEASURED IN EMBANKMENT		2,987 CY
REMOVE WALK		110 SY
GRAVEL SURFACE COURSE		55 TON
SPEC SURF CRSE FOR MAILBOX TURNOUTS		270 SY
MAILBOX POST		8 EACH
CONC 47B-3000 SIDEWALKS		136 SY
DETECTABLE WARNING PANEL		10 EACH
REMOVE GUARDRAIL		150 LF
GUARDRAIL END TREATMENT, TYPE II		4 EACH
HYDRATED LIME FOR ASPHALT MIXTURES		73 TON
ASPH CONCRETE FOR PATCHING, TYPE		250 TON
SP4 SPECIAL (0.5)		
ASPH CONC, TYPE SP4 SPECIAL(0.5)		7,130 TON
PLACE ASPH CONC FOR DRIVE & INTER		809 SY
PERF GRADED BINDER (64-28)		369 TON
TACK COAT		7,940 GAL
WATER		65 MGAL
EARTH SHOULDER CONSTRUCTION		175 STA
TRENCHED WIDENING		175 STA
COLD MILLING, CLASS 3		87 STA
COLD MILLING, CLASS 3		15,777 SY
TYPE A		
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE A		1 ACRE
SEEDING, TYPE B		1 ACRE
COVER CROP SEEDING		1 ACRE
EROSION CONTROL, CLASS 1C		6,137 SY
MULCH		4 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		4,500 BDAY
BARRICADE, TYPE III		558 BDAY
TEMPORARY SIGN DAY		280 EACH
SIGN DAY		3,078 EACH
CONTRACTOR FURNISHED SIGN DAY		52 EACH
OVERLAY BROKEN LINES		337 STA
OVERLAY SOLID LINES		660 STA
FLAGGING		40 DAY
FURNISHING AND OPERATING PILOT VEHICLE		20 DAY
FIELD OFFICE		1 EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED		30 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		20 HOUR

RENTAL OF DUMP TRUCK, FULLY OPERATED	30 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	30 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10 HOUR
TEMPORARY EROSION CONTROL	500 SY
BLANKET	
TEMPORARY SILT FENCE	800 LF
TEMPORARY MULCH	2 TON