

# NOTICE TO CONTRACTORS

CALL ORDER 305  
STATE PROJECT NO. RD-81-3(1044)  
LOCATION: US-81, IN NORFOLK  
COUNTIES: MADISON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on October 08, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 1.8 MILES  
START DATE 04/05/2010 WORKING DAYS 120  
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning September 15, 2009 at the Lincoln Central Office and September 21, 2009 at the District Engineer's Office at NORFOLK  
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	48 SHEETS	\$	12.00
STANDARD PLANS	13 SHEETS	\$	3.25

## SHEET NO.

1	TITLE PAGE
2-T1 - 2-T8	TYPICAL CROSS SECTIONS
2-S1 - 2-S5	SUMMARY OF QUANTITIES
2-H	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L6	LARGE SCALE PLAN SHEETS
3 - 11	PLAN SHEETS--REMOVAL
12 - 20	PLAN SHEETS--CONSTRUCTION
21 - 23	TYPICAL URBAN TRAFFIC CONTROL PLAN
24	PAVEMENT MARKING DETAILS
25	TEMPORARY PAVEMENT MARKING PLAN
26 - 27	TRAFFIC SIGNAL PLAN
28	SPECIAL PLAN 1C CURB RAMPS

## STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
443-R7	(2 SHEETS) CURB INLETS AND JUNCTION BOX
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 9 BITUMINOUS

BARRICADE, TYPE II	10,900 BDAY
BARRICADE, TYPE III	1,500 BDAY
TEMPORARY SIGN DAY	1,080 EACH
SIGN DAY	11,739 EACH
CONTRACTOR FURNISHED SIGN DAY	600 EACH
OVERLAY BROKEN LINES	383 STA
OVERLAY SOLID LINES	56 STA
FLASHING ARROW PANEL	180 DAY
FLAGGING	30 DAY
TRAFFIC CONTROL MANAGEMENT	209 DAY
FIELD OFFICE	1 EACH
MOBILIZATION	LUMP LUMP

REMOVE PAVEMENT	1,984 SY
SAWING PAVEMENT	8,290 LF
REMOVE BRICK SURFACE	37 SY
REMOVE WALK	494 SY
REMOVE CONCRETE MEDIAN SURFACING	2,621 SY
TIE BARS	3,074 EACH
CONCRETE CURB REPAIR	115 LF
CONC 47B-3000 SIDEWALKS	498 SY
COLOR IMPRINTED CONC 47B-3000 SIDEWALKS	51 SY
DETECTABLE WARNING PANEL	35 EACH
CONC 47B-3000 IMPRINTED MEDIAN SURF	2,621 SY
CONC PVMT REPAIR TYPE A FULL DEPTH	43 CY
CONC PVMT REPAIR TYPE B FULL DEPTH	108 CY
CONC PVMT REPAIR TYPE C FULL DEPTH	1,887 CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH	10 CY
10" CONC PVMT, 47B-3500	1,984 SY
CONCRETE PAVEMENT JOINT REPAIR	312 CY
CAST IRON COVER & FRAME	625 LB
RECONSTRUCT INLET	1 EACH
AT STA. 766+90 RT.	
RECONSTRUCT INLET	1 EACH
AT STA. 770+75 RT.	
RECONSTRUCT INLET	1 EACH
AT STA. 782+70 LT.	
RECONSTRUCT INLET	1 EACH
AT STA. 787+10 LT.	
RECONSTRUCT INLET	1 EACH
AT STA. 792+00 LT.	
24" WHT WET RFLC PRF PVMT MKNG T4 GVD	60 LF
ARROW, WET RFLC PRF PVMT MKNG, T 4 GVD	1 EACH
HYDRATED LIME FOR ASPHALT MIXTURES	90 TON
FOUNDATION COURSE	1,797 SY
4"	
ASPH CONCRETE FOR PATCHING, TYPE	50 TON
SP4(.375)	
ASPH CONC, TYPE SP4(0.375)	9,070 TON
PLACE ASPH CONC FOR DRIVE & INTER	950 SY
PERF GRADED BINDER (64-28)	510 TON
TACK COAT	10,000 GAL
RENTAL OF LOADER, FULLY OPERATED	10 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10 HOUR
WATER	20 MGAL
EARTH SHOULDER CONSTRUCTION	56 STA
SUBGRADE PREPARATION	1,797 SY
COLD MILLING, CLASS 4	17,699 SY
CONCRETE SURFACE MILLING	49,274 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
VEHICLE DETECTOR, TYPE A PREFORMED	8 EACH
SODDING	1,112 SY