

NOTICE TO CONTRACTORS

CALL ORDER 315
FEDERAL PROJECT NO. NH-20-5(111)
LOCATION: US-20, ROYAL-PLAINVIEW
COUNTIES: ANTELOPE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 12, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 14.3 MILES
START DATE 05/24/2010 WORKING DAYS 95
Price Range \$ 4,000,000 to \$ 7,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning October 20, 2009 at the Lincoln Central Office and October 26, 2009 at the District Engineer's Office at NORFOLK

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	5 SHEETS	\$	1.25
STANDARD PLANS	4 SHEETS	\$	1.00

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
3	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	49,500	BDAY
BARRICADE, TYPE III	640	BDAY
TEMPORARY SIGN DAY	1,176	EACH
SIGN DAY	22,880	EACH
OVERLAY BROKEN LINES	3,097	STA
OVERLAY SOLID LINES	6,194	STA
FLAGGING	168	DAY
FURNISHING AND OPERATING PILOT VEHICLE	84	DAY
FIELD OFFICE	1	EACH
TRAINING	1,500	HOURL
MOBILIZATION	LUMP	LUMP
HYDRATED LIME FOR ASPHALT MIXTURES	247	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	500	TON
ASPH CONC, TYPE SPS	14,210	TON
ASPH CONC, TYPE SP4(0.5)	24,210	TON
HIGH RAP BASE	47,920	TON
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	25	TON

PERF GRADED BINDER (58-34)	1,677 TON
PERF GRADED BINDER (64-28)	1,235 TON
PERF GRADED BINDER (52-34)	710 TON
TACK COAT	63,720 GAL
RENTAL OF LOADER, FULLY OPERATED	80 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	80 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	80 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	80 HOUR
WATER	380 MGAL
EARTH SHOULDER CONSTRUCTION	1,506 STA
COLD MILLING, CLASS 3	800 STA
COLD MILLING, CLASS 3	783 STA
TYPE A	
COLD MILLING, CLASS 3	27 STA
TYPE B	
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	21 ACRE
MULCH	47 TON