

NOTICE TO CONTRACTORS

CALL ORDER 635  
FEDERAL PROJECT NO. IM-80-3(119)  
LOCATION: I-80/I-76, BIG SPRINGS WEST  
COUNTIES: DEUEL

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on November 12, 2009 . At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 4.1 MILES  
START DATE 05/03/2010 WORKING DAYS 100  
Price Range \$ 3,000,000 to \$ 6,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning October 20, 2009 at the Lincoln Central Office and October 26, 2009 at the District Engineer's Office at NORTH PLATTE

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	65 SHEETS	\$	16.25
STANDARD PLANS	13 SHEETS	\$	3.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T7	TYPICAL CROSS SECTIONS
2-S1 - 2-S3	SUMMARY OF QUANTITIES
2-W1 - 2-W8	WETLANDS
2-H1 - 2-H6	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 10	PLAN SHEETS
11	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
12	TYPICAL TRAFFIC CONTROL PLAN--TYPE 3 BARRICADE PLACEMENT WHEN GUARDRAIL IS REMOVED
13	TYPICAL TRAFFIC CONTROL PLAN--INERTIAL BARRIER SYSTEM
14	TEMPORARY PAVEMENT MARKING PLAN
15 - 16	PAVEMENT MARKING PLAN--BIG SPRINGS WEST
17	TYPICAL PAVEMENT MARKING PLAN (INTERSTATE/EXPRESSWAY)
18	TRAFFIC CONTROL PLAN--RAMPS
19	DRAINAGE STRUCTURE CROSS SECTION
20 - 21	SPECIAL PLAN 1C SILICA-FUME CONCRETE OVERLAY REPAIR STA. 67+00.00 LT.
22 - 23	SPECIAL PLAN 2C SILICA-FUME CONCRETE OVERLAY REPAIR STA. 67+00.00 RT.
24 - 38	SPECIAL PLAN 3C GUARDRAIL PLAN
39 - 40	SPECIAL PLAN 4C CONCRETE PROTECTION BARRIER

STANDARD PLANS

410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
425-R4	COLLARS AND ELBOWS FOR CONCRETE PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
902	HIGHWAY DELINEATORS FOR RAMP AND GORE LOCATIONS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 67+00.00 LT.

MOBILIZATION	LUMP	LUMP
CLASS I REPAIR		321 SY
PLACE, FINISH, & CURE CONC OVERLAY-SF		321 SY
CONCRETE FOR OVERLAYS-SF		17 CY

GROUP 6A BRIDGE AT STA. 67+00.00 RT.

MOBILIZATION	LUMP	LUMP
CLASS I REPAIR		321 SY
PLACE, FINISH, & CURE CONC OVERLAY-SF		321 SY
CONCRETE FOR OVERLAYS-SF		17 CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
ROADWAY GRADING		51 STA
REMOVE FLARED- END SECTION		1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		3 CY
47B-3000 CONC FOR CONCRETE CO		1 CY
RE-STEEL FOR COLLARS		38 LB
18" REINFORCED CONCRETE PIPE		8 LF
18" CONCRETE FLARED-END SECTION		1 EACH
W-BEAM GUARDRAIL		1,881 LF
THRIE-BEAM GUARDRAIL		1,437 LF
REMOVE GUARDRAIL		4,237 LF
BRIDGE APPROACH SECTIONS		8 EACH
END ANCHORAGE ASSEMBLY		2 EACH
BULLNOSE-12.5'		10 EACH
GUARDRAIL END TREATMENT, TYPE I		10 EACH
EROSION CONTROL, CLASS 1D		21,970 SY
FABRIC SILT FENCE-LOW POROSITY		4,009 LF

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE I		149 EACH
DELINEATOR, TYPE II		70 EACH
REMOVE DELINEATOR UNITS		219 EACH
CONC PVM T REPAIR TYPE A FULL DEPTH		1 CY
CONC PVM T REPAIR TYPE B FULL DEPTH		411 CY
CONC PVM T REPAIR TYPE C FULL DEPTH		8 CY
4" WHITE WET REFLECT THERMOPLASTIC, GRVD		18,700 LF
5" WHITE WET REFLECT THERMO, GRVD		82,500 LF
5" YELLOW WET REFLECT THERMO, GRVD		82,500 LF
LN DP ARROW RT PREF PVM T MKG T-4 GROOVED		2 EACH
4" WHT WET RFLC PRF PVM T MKNG T4 GVD		50 LF
5" WHT WET RFLC PRF PVM T MKNG T4 GVD		170 LF
12" WHT WET RFLC PRF PVM T MKNG T4 GVD		9,500 LF
5" YEL WET RFLC PRF PVM T MKNG T4 GVD		170 LF
12" YEL WET RFLC PRF PVM T MKNG T4 GVD		550 LF
HYDRATED LIME FOR ASPHALT MIXTURES		267 TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC		5 TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP5(0.5)		500 TON
ASPH CONCRETE FOR PATCHING, TYPE SPS		300 TON
ASPH CONCRETE FOR PATCHING, TYPE SP5(0.5)		300 TON
ASPH CONC, TYPE SPS		9,180 TON
ASPH CONC, TYPE SP5(0.5)		26,540 TON
PLACE ASPH CONC FOR DRIVE & INTER		933 SY
PERF GRAD BIND (70-28)FOR ST MAINT PATCH		25 TON
PERF GRADED BINDER (70-28)		1,342 TON

PERF GRADED BINDER (52-34)

474 TON

GROUP 9 BITUMINOUS

PREP OF INTER & DRIVE	306 SY
TACK COAT	49,890 GAL
WATER	192 MGAL
EARTH SHOULDER CONSTRUCTION	769 STA
COLD MILLING, CLASS 3	804 STA
RUMBLE STRIPS, ASPHALT	1,538 STA
SURFACE UNDER GUARDRAIL	2,366 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP
SEEDING, TYPE B	5 ACRE
MULCH	11 TON

GROUP 10 GENERAL ITEMS

SURV OF TEMP TRAFFIC CONT DEVICES	180 CDAY
BARRICADE, TYPE II	27,050 BDAY
BARRICADE, TYPE III	1,881 BDAY
TEMPORARY SIGN DAY	1,760 EACH
SIGN DAY	4,916 EACH
OVERLAY BROKEN LINES	1,292 STA
OVERLAY SOLID LINES	3,116 STA
FLASHING ARROW PANEL	195 DAY
FLAGGING	20 DAY
CONCRETE PROTECTION BARRIER	1,125 LF
RELOCATE CONC PROTECTION BARRIER	1,125 LF
RELOC INERTIAL BARRIER SYSTEM	2 EACH
INERTIAL BARRIER SYSTEM	2 EACH
REPLACEMENT MODULE	16 EACH
FIELD OFFICE	1 EACH
TRAINING	1,000 HOUR
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	80 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	80 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	80 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	40 HOUR
TEMPORARY SILT FENCE	500 LF