

NOTICE TO CONTRACTORS

CALL ORDER 105
FEDERAL PROJECT NO. BR-3430(6)
LOCATION: ON A COUNTY ROAD, IN PRAGUE
COUNTIES: SAUNDERS

The Nebraska Department of Roads will receive sealed bids for
SAUNDERS COUNTY in Room 104 of the Central Office Building at
1500 Hwy 2 at Lincoln, until 1:30 P.M. on December 17, 2009.
At that time the bids will be opened and read for
GR CONC PAVE CULV WATER MAIN

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: CULVERTS

START DATE 07/26/2010 WORKING DAYS 70
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning November 24, 2009 at the Lincoln
Central Office and November 30, 2009 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all
appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	18	SHEETS	\$ 4.50
CROSS SECTIONS (SHEETS X1 THRU X3)	3	SHEETS	\$ 0.75
STANDARD PLANS	19	SHEETS	\$ 4.75

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTION OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION
3	PLAN & PROFILE SHEET
4A	WATER MAIN PLAN & PROFILE SHEET
4B	SANITARY SEWER MAIN PLAN & PROFILE SHEET
5 - 11	DRAINAGE STRUCTURE CROSS SECTIONS
12 - 13	SPECIAL PLAN 1 16' X 16' TRIPLE SPAN RC BOX CULVERT STA. 5+00.00
14	TYPICAL PAVEMENT MARKING PLAN--4" PAVEMENT MARKING
R1	RIGHT-OF-WAY SHEET
X1 - X3	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
404-R3	CONTROL JOINTS FOR CONCRETE BOX CULVERTS
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		1 EACH

GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER		10 MGAL
EARTHWORK MEASURED IN EMBANKMENT	3,593	CY
REMOVE ASPHALT SURFACE	588	SY
REMOVE HEADWALLS FROM CULV	2	EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	613	CY
30" CORRUGATED METAL PIPE	235	LF
30" METAL FLARED-END SECTION	1	EACH
COVER CROP SEEDING	2	ACRE
EROSION CONTROL	1,139	SY
FABRIC SILT FENCE-HIGH POROSITY	385	LF

GROUP 3 CONCRETE PAVEMENT

PERMANENT PAVEMENT MARKING PAINT		900 LF
MOBILIZATION	LUMP	LUMP
CONC 47B-3500 DRIVEWAY	113	SY
8" DOWELED CONC PAVE, CLASS 47B-3500	800	SY
ADJUST MANHOLE TO GRADE	2	EACH
FOUNDATION COURSE	800	SY
4"		
PREP OF INTER & DRIVE	113	SY
WATER		4 MGAL
EARTH SHOULDER CONSTRUCTION	6	STA
SUBGRADE PREPARATION	800	SY
SEEDING, TYPE A	1	ACRE
SEEDING, TYPE B	1	ACRE
MULCH	5	TON

GROUP 4 CULVERT AT STA. 5+00.00

MOBILIZATION	LUMP	LUMP
EXCAVATION FOR BOX CULVERTS	2,748	CY
47B-3000 CONC FOR BOX CULV	845	CY
RE-STEEL FOR BOX CULVERT	76,098	LB
REMOVE STRUCTURE	1	EACH
AT STA. 5+09		

GROUP 4A WATER MAIN

MOBILIZATION	LUMP	LUMP
REMOVE SEWER PIPE	448	LF
4" DUCTILE IRON SEWER PIPE	239	LF
6" PLUG	2	EACH
1" WATER SERVICE	149	LF
THRUST BLOCK	7	EACH
6" WATER MAIN PIPE	461	LF
6" GATE VALVE, M.J.	4	EACH
INSTALL FIRE HYDRANT	1	EACH
4" SOLID SLEEVE	1	EACH
6" SOLID SLEEVE	3	EACH
6" X 6" TEE	3	EACH
4" - 45 DEGREE BEND	1	EACH
4" CAP	1	EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	1,500	B DAY
SIGN DAY	2,000	EACH
CONTRACTOR FURNISHED SIGN DAY	750	EACH
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	10	HR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HR
TEMPORARY SILT FENCE	200	LF