NOTICE TO CONTRACTORS

CALL ORDER 160

FEDERAL PROJECT NO. BRO-7049(21)

LOCATION: ON A COUNTY ROAD, WEST OF STERLING

COUNTIES: JOHNSON

The Nebraska Department of Roads will receive sealed bids for the COUNTY OF JOHNSON in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on December 17, 2009. At that time the bids will be opened and read for GR BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 06/28/2010 WORKING DAYS 95
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning November 24, 2009 at the Lincoln Central Office and November 30, 2009 at the District Engineer's Office at LINCOLN Additional letting information may be found at the Nebraska Department of Roads Web Site at http://www.dor.state.ne.us/letting/.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	26	SHEETS	\$ 6.50
CROSS SECTIONS (SHEETS X1 THRU X5)	5	SHEETS	\$ 1.25
STANDARD PLANS	13	SHEETS	\$ 3.25

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION & DETOUR LOCATION MAP
3	PLAN & PROFILE SHEET
4 - 5	DRAINAGE STRUCTURE CROSS SECTIONS
6 - 15	SPECIAL PLAN 1 PRESTRESSED CONCRETE IT-900 GIRDER BRIDGE
	STA. 32+50.00
16 - 23	SPECIAL PLAN 1C GUARDRAIL PROTECTION
R1	RIGHT-OF-WAY SHEET
X1 - X5	CROSS SECTIONS

STANDARD PLANS

308-R1	LOCAL ROADS MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROLROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL	1	EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
WATER	37	MGAL
EARTHWORK MEASURED IN EMBANKMENT	5,302	CY
18" RD EQUIV CMP FOR DR CULV PIPE	120	LF
24" RD EQUIV CMP FOR DR CULV PIPE	74	LF

CRUSHED ROCK EMBEDMENT CRUSHED ROCK SURFACE COURSE SPEC SURF CRSE FOR MAILBOX TURNOUTS MAILBOX POST EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL 24" CORRUGATED METAL PIPE 42" CORRUGATED METAL PIPE 24" METAL FLARED-END SECTION 42" METAL FLARED-END SECTION SEEDING, TYPE A COVER CROP SEEDING EROSION CONTROL, CLASS 1D FABRIC SILT FENCE-LOW POROSITY MULCH GROUP 6 BRIDGE AT STA. 32+50.00	11 STA 451 TON 22 SY 1 EACH 1,353 CY 240 LF 218 LF 2 EACH 1 EACH 3 ACRE 3 ACRE 3,529 SY 471 LF 7 TON
GROUP 0 BRIDGE AT STA. 32+30.00	
MOBILIZATION RIPRAP FILTER FABRIC ABUTMENT NO.1 EXCAVATION ABUTMENT NO.2 EXCAVATION BENT NO.1 EXCAVATION BENT NO.2 EXCAVATION 47B-3000 CONC FOR BRIDGE 47BD-4000 CONC FOR BRIDGE PRECAST/PRESTRESSED CONC SUPERSTR AT STA. 32+50.00 RE-STEEL FOR BRIDGE REMOVE STRUCTURE	LUMP LUMP 1,342 SY LUMP LUMP LUMP LUMP LUMP LUMP LUMP 225 CY 190 CY LUMP 55,595 LB 1 EACH
AT STA. 32+41.00 ACCESS CROSSING STRUC STEEL FOR SUBSTRUCTURE ROCK RIPRAP, TYPE B PIPE PILING	LUMP LUMP 4,015 LB 1,030 TON 2,230 LF
GROUP 7 GUARDRAIL	
MOBILIZATION BRIDGE APPROACH SECTIONS MELT	LUMP LUMP 4 EACH 4 EACH
GROUP 10 GENERAL ITEMS BARRICADE, TYPE III SIGN DAY CONTRACTOR FURNISHED SIGN DAY MOBILIZATION RENTAL OF LOADER, FULLY OPERATED RENTAL OF DUMP TRUCK, FULLY OPERATED RENTAL OF SKID LOADER, FULLY OPERATED RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	1,908 BDAY 2,544 EACH 318 EACH LUMP LUMP 10 HOUR 10 HOUR 10 HOUR 10 HOUR