

NOTICE TO CONTRACTORS

CALL ORDER 310
FEDERAL PROJECT NO. IM-129-1(29)
LOCATION: I-129, US-20-MISSOURI RIVER
COUNTIES: DAKOTA

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 17, 2009. At that time the bids will be opened and read for GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 2.8 MILES
START DATE 05/17/2010 WORKING DAYS 100
Price Range \$ 2,000,000 to \$ 4,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 4.0 %

Plans and specifications may be seen beginning November 24, 2009 at the Lincoln Central Office and November 30, 2009 at the District Engineer's Office at NORFOLK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING STANDARDS)	77	SHEETS	\$ 19.25
STANDARD PLANS	8	SHEETS	\$ 2.00

SHEET NO.

1	TITLE PAGE
2	INDEX OF SHEETS
2-T1 - 2-T12	TYPICAL CROSS SECTIONS
2-S1 - 2-S6	SUMMARY OF QUANTITIES
2-W1 - 2-W10	WETLANDS
2-H1 - 2-H7	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1 - 2-N2	GENERAL INFORMATION
2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3 - 13	PLAN SHEETS
14	TYPICAL TRAFFIC CONTROL PLAN--TYPE 3 BARRICADE PLACEMENT WHEN GUARDRAIL IS REMOVED
15	TRAFFIC CONTROL PLAN
16	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
17 - 19	TYPICAL URBAN TRAFFIC CONTROL PLAN
20	TYPICAL PAVEMENT MARKING PLAN (INTERSTATE/EXPRESSWAY)
21	TEMPORARY PAVEMENT MARKING PLAN
22	SPECIAL PLAN 1C PAVEMENT APPROACH REPAIR
23 - 38	SPECIAL PLAN 2C GUARDRAIL PLAN
39	SPECIAL PLAN 3C CONCRETE FLUME, TYPE VI

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
ROADWAY GRADING		30 STA
W-BEAM GUARDRAIL		962 LF
THRIE-BEAM GUARDRAIL		700 LF
REMOVE GUARDRAIL		2,737 LF
REMOVE & SALVAGE GUARDRAIL		2,293 LF
RESET GUARDRAIL		2,293 LF
BRIDGE APPROACH SECTIONS		6 EACH
BULLNOSE-12.5'		6 EACH
GUARDRAIL END TREATMENT, TYPE I		6 EACH
EROSION CONTROL, CLASS 1D		10,822 SY
FABRIC SILT FENCE-LOW POROSITY		2,294 LF

GROUP 9 BITUMINOUS

PAVEMENT MARKING REMOVAL		8,300 LF
OVERLAY BROKEN LINES		582 STA
OVERLAY SOLID LINES		1,470 STA
MOBILIZATION	LUMP	LUMP
REMOVE ASPHALT SURFACE		2,207 SY
REMOVE CURB		876 LF
REMOVE CONCRETE FLUME		2 EACH
CONCRETE CURB REPAIR		40 LF
CONC PVMT REPAIR TYPE A FULL DEPTH		84 CY
CONC PVMT REPAIR TYPE B FULL DEPTH		395 CY
CONC PVMT REPAIR TYPE C FULL DEPTH		310 CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH		6 CY
CONC PVMT, PR-3500		227 CY
JOINT REPAIR		
CONCRETE FLUME, TYPE VI		2 EACH
BRIDGE APPROACH REPAIR		41 CY
4" WHITE WET REFLECT THERMOPLASTIC, GRVD		58,000 LF
4" YELLOW WET REFLECT THERM PVMT MK GRVD		48,000 LF
12" WHT WET RFLC PRF PVMT MKNG T4 GVD		6,500 LF
HYDRATED LIME FOR ASPHALT MIXTURES		261 TON
GRANULAR SUBDRAIN		96 EACH
SHOULDER SUBGRADE PREPARATION		20 STA
ASPH CONCRETE FOR PATCHING, TYPE		500 TON
SPS		
ASPH CONC, TYPE SPS		6,920 TON
ASPH CONC, TYPE SP5(0.5)		26,040 TON
PERF GRADED BINDER (70-28)		1,302 TON
PERF GRADED BINDER (52-34)		371 TON
CONSTRUCTING ASPH CONC CURB		876 LF
TACK COAT		39,110 GAL
WATER		283 MGAL
EARTH SHOULDER CONSTRUCTION		1,093 STA
COLD MILLING, CLASS 3		718 SY
MILLING CONC FOR INLAYS		30 EACH
RUMBLE STRIPS, ASPHALT		545 STA
CONCRETE SURFACE MILLING		1,741 SY
SURFACE UNDER GUARDRAIL		1,797 SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		12 ACRE
MULCH		27 TON

GROUP 10 GENERAL ITEMS

SURV OF TEMP TRAFFIC CONT DEVICES		167 CDAY
BARRICADE, TYPE II		11,000 BDAY
BARRICADE, TYPE III		904 BDAY
TEMPORARY SIGN DAY		2,400 EACH
SIGN DAY		5,791 EACH
FLASHING ARROW PANEL		240 DAY

FLAGGING	20 DAY
FIELD OFFICE	1 EACH
TRAINING	500 HOUR
MOBILIZATION	LUMP
RENTAL OF LOADER, FULLY OPERATED	70 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	70 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	70 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	30 HOUR
TEMPORARY SILT FENCE	500 LF