

# NOTICE TO CONTRACTORS

CALL ORDER 410  
FEDERAL PROJECT NO. BRO-7065(21)  
LOCATION: ON A COUNTY ROAD, OAK SOUTH  
COUNTIES: NUCKOLLS

The Nebraska Department of Roads will receive sealed bids for NUCKOLLS COUNTY in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on December 17, 2009. At that time the bids will be opened and read for CULVERTS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CULVERTS

START DATE 08/30/2010 WORKING DAYS 45

Price Range \$ 0 to \$ 500,000

THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning November 24, 2009 at the Lincoln Central Office and November 30, 2009 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	15 SHEETS	\$	3.75
CROSS SECTIONS (SHEETS X1 THRU X11)	11 SHEETS	\$	2.75
STANDARD PLANS	8 SHEETS	\$	2.00

## SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS OF IMPROVEMENT
2-S	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION & DETOUR LOCATION MAP
3 - 5	PLAN & PROFILE SHEETS
6 - 11	DRAINAGE STRUCTURE CROSS SECTIONS
12	SPECIAL PLAN 1 3.66m X 3.66m TRIPLE SPAN RC BOX CULVERT STA. 10+19
R1	RIGHT-OF-WAY SHEET
X1 - X11	CROSS SECTIONS

## STANDARD PLANS

M410	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
M502	SILT FENCE DETAILS
M920	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
M921-R1	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
M923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 4 CULVERTS

BARRICADE, TYPE III	2,160 BDAY
SIGN DAY	2,160 EACH
CONTRACTOR FURNISHED SIGN DAY	180 EACH
MOBILIZATION	LUMP LUMP
LARGE TREE REMOVAL	5 EACH
GENERAL CLEARING AND GRUBBING	LUMP LUMP
EXCAVATION (ESTABLISHED QUANTITY)	4,996 m3
WATER	358 kL
600 mm RD EQUIV CMP FOR DRVWY CULV	11 m

CRUSHED ROCK EMBEDMENT	5 StaM
CRUSHED ROCK SURFACE COURSE	334 m3
REMOVE CULVERT PIPE	27 m
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL	299 m3
EXCAVATION FOR BOX CULVERTS	1,266 m3
47B-20 CONC FOR BOX CULV	228 m3
RE-STEEL FOR BOX CULVERT	14,670 kg
600 mm CORRUGATED METAL PIPE	28 m
900 mm CORRUGATED METAL PIPE	35 m
600 mm METAL FLARED-END SECTION	3 EACH
900 mm METAL FLARED-END SECTION	1 EACH
REMOVE STRUCTURE	1 EACH
AT STA. 10+19.000	
RENTAL OF LOADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10 HOUR
SEEDING, TYPE B	2 ha
COVER CROP SEEDING	2 ha
FABRIC SILT FENCE-LOW POROSITY	92 m
MULCH	12 Mg