

NOTICE TO CONTRACTORS

CALL ORDER 760
STATE PROJECT NO. RD-83-1(1021)
LOCATION: US-83, SOUTH OF MCCOOK
COUNTIES: RED WILLOW

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 17, 2009. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 6.8 MILES
START DATE 07/19/2010 WORKING DAYS 60
Price Range \$ 1,000,000 to \$ 3,000,000

Plans and specifications may be seen beginning November 24, 2009 at the Lincoln Central Office and November 30, 2009 at the District Engineer's Office at MCCOOK
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	6 SHEETS	\$	1.50
STANDARD PLANS	4 SHEETS	\$	1.00

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES & TYPICAL CROSS SECTIONS
2-N	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TYPICAL TRAFFIC CONTROL PLAN--VEHICLE SIGNING FOR PAINT STRIPING
4	TEMPORARY PAVEMENT MARKING PLAN
5	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R7	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	26,400	BDAY
BARRICADE, TYPE III	416	BDAY
TEMPORARY SIGN DAY	602	EACH
SIGN DAY	7,528	EACH
OVERLAY BROKEN LINES	1,445	STA
OVERLAY SOLID LINES	2,890	STA
PERMANENT PAVEMENT MARKING PAINT	98,600	LF
FLAGGING	114	DAY
FURNISHING AND OPERATING PILOT VEHICLE	57	DAY
TRAFFIC CONTROL MANAGEMENT	104	DAY
MOBILIZATION	LUMP	LUMP
REMOVE CURB	550	LF
HYDRATED LIME FOR ASPHALT MIXTURES	114	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	25	TON
ASPH CONC FOR STATE MAINT PATCHING, TYPE SP4(0.5)	2,500	TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)	250	TON
ASPH CONCRETE FOR PATCHING, TYPE HIGH RAP BASE	500	TON

ASPH CONC, TYPE SPS	6,810 TON
ASPH CONC, TYPE SP4(0.5)	11,230 TON
HIGH RAP BASE	11,620 TON
PERF GRAD BIND (64-28)FOR ST MAINT PATCH	125 TON
PERF GRADED BINDER (58-34)	424 TON
PERF GRADED BINDER (64-28)	574 TON
PERF GRADED BINDER (52-34)	340 TON
CONSTRUCTING ASPH CONC CURB	550 LF
TACK COAT	30,250 GAL
RENTAL OF LOADER, FULLY OPERATED	40 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	40 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	40 HOUR
COLD MILLING, CLASS 3	390 STA
COLD MILLING, CLASS 3	379 STA
TYPE A	
RUMBLE STRIPS, ASPHALT	686 STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP