

NOTICE TO CONTRACTORS

CALL ORDER 405

FEDERAL PROJECT NO. URB-5512(8)

LOCATION: 7th STREET-BALTIMORE AVENUE TO OSWEGO AVENUE, HASTINGS

COUNTIES: ADAMS

The Nebraska Department of Roads will receive sealed bids for the  
CITY OF HASTINGS in Room 104 of the Central Office Building  
at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on January 14, 2010 .  
At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR  
WHO IS QUALIFIED FOR: BITUMINOUS

START DATE 09/20/2010 WORKING DAYS 20

Price Range \$ 0 to \$ 500,000

THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning December 22, 2009 at the Lincoln  
Central Office and December 28, 2009 at the District Engineer's Office at GRAND ISLAND

Additional letting information may be found at the Nebraska Department of Roads  
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all  
appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	15	SHEETS	\$	3.75
CROSS SECTIONS (SHEETS X1 THRU X3)	3	SHEETS	\$	0.75
STANDARD PLANS	12	SHEETS	\$	3.00

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
2-T	TYPICAL CROSS SECTIONS
2-A	PHOTO MAP
3	GENERAL NOTES
4	HORIZONTAL ALIGNMENT & ORIENTATION/R.O.W. PLAN
5	CONTROL POINT/BENCH MARK DATA
6 - 8	PLAN & PROFILE SHEETS
9	INTERSECTION PLAN
10 - 12	TYPICAL URBAN TRAFFIC CONTROL PLAN
13	SPECIAL PLAN 1C CURB RAMPS
X1 - X3	CROSS SECTION PLANS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	250	BDAY
BARRICADE, TYPE III	410	BDAY
SIGN DAY	410	EACH
CONTRACTOR FURNISHED SIGN DAY	164	EACH
FLAGGING	40	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
REMOVE PAVEMENT	318	SY
SAWING PAVEMENT	198	LF
REMOVE DRIVEWAY	16	SY
REMOVE WALK	17	SY
REMOVE COMBINATION CURB AND GUTTER	426	LF
REMOVE HEADER	2	EACH
CONCRETE		
COMB CONC 47B-3500 CURB & GUTTER	306	LF
CONC 47B-3000 SIDEWALK 5"	29	SY
CONC 47B-3500 DRIVEWAY	7	SY
CONC PVMT REPAIR TYPE A FULL DEPTH 8"	100	SY
8" CONC PVMT, 47B-3500	358	SY
ADJUST MANHOLE TO GRADE	5	EACH
CURB INLET SEDIMENT FILTER	2	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	7	TON
ASPH CONC, TYPE SPR	680	TON
PLACE ASPH CONC FOR DRIVE & INTER	68	SY
PERF GRADED BINDER FOR SPR	38	TON
TACK COAT	840	GAL
WATER	1	MGAL
SUBGRADE PREPARATION	367	SY
COLD MILLING, CLASS 3	4,114	SY