

STATE OF NEBRASKA
DEPARTMENT OF ROADS
ADDENDUM NO. 1
PROJECT NO. FL-S86B(101)
CONTROL NO. 61417
CALL NO. 610
S86B, HALSEY SPUR
LETTING DATE: JANUARY 14, 2010

On page 78 of the Special Provisions, the second paragraph of the provision titled **VINYL SHEET PILE AT STA. 136+50 TO 140+50** is void and superseded by the following:

The sheet piles shall be anchored at intervals between five and ten feet with earth anchors passing through the vertical timbers of the cap at mid-height and using "Dock Washers". The anchors shall be adequate to restrain a force equal to the average anchor spacing at the immediate location of the anchor multiplied times 500 lb. / ft.

DEPARTMENT OF ROADS

ORIGINAL SIGNED BY KENDALL STEGE

FOR Claude Oie
Construction Engineer

Issued: January 6, 2010

CO:AH:610AD101

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.