

NOTICE TO CONTRACTORS

CALL ORDER 165
FEDERAL PROJECT NO. LCLC-5247(12)
LOCATION: 70TH STREET, AYLESWORTH-VINE STREET, LINCOLN
COUNTIES: LANCASTER

The Nebraska Department of Roads will receive sealed bids for the
CITY OF LINCOLN in Room 104 of the Central Office Building
at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on January 28, 2010.
At that time the bids will be opened and read for CONC PAVE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: CONCRETE PAVEMENT BITUMINOUS
START DATE 05/30/2011 CALENDAR DAYS 74
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 7.0 %

Plans and specifications may be seen beginning January 05, 2010 at the Lincoln
Central Office and January 11, 2010 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all
appropriate Federal requirements will apply.

NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding
proposal for Call Order No. 160, {Project No. LCLC-5247(11)}, Call Order No. 165,
{Project No. LCLC-5247(12)} and Call Order No. 170, {Project No. LCLC-5244(8)}. Award
of Contract, if awarded, will be made on the combined bid for these call order nos.
Separate contracts will be awarded for each Call Order Number. Please order plans and
proposals accordingly.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	36 SHEETS	\$	9.00
STANDARD PLANS	6 SHEETS	\$	1.50

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
2-T	TYPICAL CROSS SECTIONS
2-H	SURVEY & ALIGNMENT
2-N	GENERAL INFORMATION
2-L1 - 2-L6	REMOVAL & CONSTRUCTION
3	DETOUR LOCATION MAP
4 - 5	TRAFFIC SIGNAL & LIGHTING
6 - 11	PAVEMENT MARKING & SIGNING
12 - 13	DETAILS
14 - 24	SPECIAL PLANS
25 - 27	TYPICAL URBAN TRAFFIC CONTROL PLAN

STANDARD PLANS

502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

BARRICADE, TYPE III	2,812 BDAY
SIGN DAY	2,738 EACH

CONTRACTOR FURNISHED SIGN DAY	1,258	EACH
MOBILIZATION	LUMP	LUMP
REMOVE PAVEMENT	5,974	SY
SAWING PAVEMENT	5,864	LF
REMOVE DRIVEWAY	836	SY
REMOVE WALK	733	SY
REMOVE COMBINATION CURB AND GUTTER	4,798	LF
REMOVE INLET	15	EACH
COMB CONC 47B-3500 CURB & GUTTER	4,798	LF
CONC 47B-3000 SIDEWALKS	733	SY
DETECTABLE WARNING PANEL	528	SF
CONC 47B-3500 DRIVEWAY	836	SY
8" CONCRETE BASE COURSE	5,809	SY
8" CONCRETE BASE COURSE 47B-HE-3500	40	SY
9" CONC PVMT 47B-HE-3500	1,627	SY
INLET-72" STRAIGHT	7	EACH
INLET-72" CANTED	11	EACH
MODIFY INLET	3	EACH
ADJUST MANHOLE TO GRADE	25	EACH
REMOVE SEWER PIPE	107	LF
47B-3000 CONC FOR CONCRETE CO	7	CY
RE-STEEL FOR COLLARS	836	LB
15" REINF CONCRETE SEWER PIPE	182	LF
18" REINF CONCRETE SEWER PIPE	6	LF
CURB INLET SEDIMENT FILTER	30	EACH
4" WHITE THERMOPLASTIC, GROOVED	100	LF
4" YELLOW THERMOPLASTIC, GROOVED	5,562	LF
12" WHITE THERMOPLASTIC, GROOVED	26	LF
24" WHITE THERMOPLASTIC, GROOVED	97	LF
4" WHT POLYUREA PVMT MRKING, GROOVED	274	LF
24" WHT POLYUREA PVMT MRKING, GROOVED	280	LF
4" YEL POLYUREA PVMT MRKING, GROOVED	562	LF
ASPHALTIC CONCRETE	1,857	TON
TYPE 1		
COLD MILLING, CLASS 3	6,575	SY
VEHICLE DETECTOR, 4 TURNS UC	2	EACH
VEHICLE DETECTOR	1	EACH
4 TURNS		
1/2" CONDUIT IN TRENCH	40	LF
SEEDING, TYPE B	1	ACRE
6" RETAINER GLAND	2	EACH
ANCHOR COUPLING, M.J.	1	EACH
6"		
D.I.P. SLEEVE, M.J.	1	EACH
6"		
6" WATER MAIN PIPE	10	LF
6" - 90 DEGREE BEND	1	EACH
M.J.		
ADJUST WATER VALVE BOX & COVER TO GRADE	14	EACH
RELOCATE FIRE HYDRANT AND VALVE	1	EACH