

NOTICE TO CONTRACTORS

CALL ORDER 205  
FEDERAL PROJECT NO. MAPA-5145(1)  
LOCATION: CITYWIDE, BELLEVUE  
COUNTIES: SARPY

The Nebraska Department of Roads will receive sealed bids for the  
CITY OF BELLEVUE in Room 104 of the Central Office Building  
at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on February 18, 2010 .  
At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR  
WHO IS QUALIFIED FOR: BITUMINOUS

START DATE 07/19/2010 WORKING DAYS 40  
Price Range \$ 500,000 to \$ 2,000,000  
THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning January 26, 2010 at the Lincoln  
Central Office and February 01, 2010 at the District Engineer's Office at OMAHA  
Additional letting information may be found at the Nebraska Department of Roads  
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all  
appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	20 SHEETS	\$	5.00
STANDARD PLANS	7 SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
3	COVER SHEET
4	TYPICAL SECTION--HARVELL DRIVE
5	TYPICAL SECTION--GALVIN ROAD
6	TYPICAL SECTION--FT. CROOK ROAD
7	TYPICAL SECTION--CHANDLER ROAD, 25TH STREET, 36TH STREET, & 42ND STREET
8	FORT CROOK ROAD REMOVAL & CONSTRUCTION PLAN
9	SOUTH 36TH STREET REMOVAL & CONSTRUCTION PLAN
10	HARVELL DRIVE REMOVAL & CONSTRUCTION PLAN
11	GALVIN ROAD REMOVAL & CONSTRUCTION PLAN
12	CHANDLER ROAD & SOUTH 25TH STREET REMOVAL & CONSTRUCTION PLAN
13	SOUTH 42ND STREET REMOVAL & CONSTRUCTION PLAN
14	FORT CROOK ROAD STRIPING PLAN
15	SOUTH 36TH STREET STRIPING PLAN
16	HARVELL DRIVE STRIPING PLAN
17	GALVIN ROAD STRIPING PLAN
18	CHANDLER ROAD & SOUTH 25TH STREET STRIPING PLAN
19	SOUTH 42ND STREET STRIPING PLAN
20	SPECIAL PLAN 1C CURB RAMPS

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING
924	(3 SHEETS)	TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	3,685	BDAY
TEMPORARY SIGN DAY	112	EACH
SIGN DAY	641	EACH
PERMANENT PAVEMENT MARKING PAINT	10,355	LF
FLASHING ARROW PANEL	25	DAY
FLAGGING	54	DAY
MOBILIZATION	LUMP	LUMP
REMOVE WALK	78	SY
CONCRETE CURB REPAIR	350	LF
CONC 47B-3000 SIDEWALKS	78	SY
DETECTABLE WARNING PANEL	22	EACH
CONC PVMT REPAIR TYPE C FULL DEPTH	375	SY
ADJUST MANHOLE TO GRADE	31	EACH
ONLY, PREF PVMT MRKING T-4, GROOVED	19	EACH
ARROW, PREF PVMT MRKING T-4 GROOVED	40	EACH
4" WHITE PREF PVMT MRKNG T-4 GROOVED	18,922	LF
4" YEL PREF PVMT MRKNG, T-4, GROOVED	29,022	LF
12" WHT PREF PVMT MRKING T-4 GROOVED	93	LF
24" WHITE PREF PVMT MKING T-4 GROOVED	180	LF
AGG FOR MICROSURFACING	799	TON
HYDRATED LIME FOR ASPHALT MIXTURES	76	TON
MIN FILLER FOR MICROSURFACING	16	TON
ASPH CONC, TYPE SP4(0.5)	7,660	TON
MICROSURFACING PLACEMENT	94	STA
PERF GRADED BINDER (64-28)	383	TON
EMUL ASPH FOR MICROSURFACING	27,440	GAL
TACK COAT	10,739	GAL
COLD MILLING, CLASS 3	14,156	SY
COLD MILLING, CLASS 4	57,436	SY
SEEDING, TYPE B	1	ACRE
MULCH	1	TON
ADJUST VALVE BOX TO GRADE	14	EACH