

NOTICE TO CONTRACTORS

CALL ORDER 260
FEDERAL PROJECT NO. MAPA-5052(3)
LOCATION: 13th & 14th STREET, OMAHA
COUNTIES: DOUGLAS

The Nebraska Department of Roads will receive sealed bids for the
CITY OF OMAHA in Room 104 of the Central Office Building
at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on February 18, 2010.
At that time the bids will be opened and read for ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR
WHO IS QUALIFIED FOR: ELECTRICAL

START DATE 08/10/2010 CALENDAR DAYS 60
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning January 26, 2010 at the Lincoln
Central Office and February 01, 2010 at the District Engineer's Office at OMAHA
Additional letting information may be found at the Nebraska Department of Roads
Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all
appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	24 SHEETS	\$	6.00
STANDARD PLANS	2 SHEETS	\$	0.50

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
3 - 6	TRAFFIC SIGNALS
7 - 21	SPECIAL PLANS
22 - 24	TYPICAL URBAN TRAFFIC CONTROL PLAN

STANDARD PLANS

920-R5 (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and
should not be used for bidding purposes. The Department
reserves the right to change these quantities without notice.

GROUP 8B ELECTRICAL

BARRICADE, TYPE II	1,000 BDAY
TEMPORARY SIGN DAY	300 EACH
SIGN DAY	1,200 EACH
FLASHING ARROW PANEL	50 DAY
MOBILIZATION	LUMP LUMP
REMOVE AND REINSTALL	16 EACH
OVERHEAD SIGN	
REMOVE AND REINSTALL	2 EACH
TRAFFIC SIGN AND POST	
STREET NAME SIGN	7 EACH
18"	
PULL BOX, TYPE PB-6	3 EACH
TRAFFIC SIGNAL, TYPE TS-1	21 EACH
TRAFFIC SIGNAL, TYPE TS-1A	7 EACH
TRAF SIG CONTROL, TYPE TC-2070	4 EACH
2 PHASE	
PEDESTAL POLE, TYPE PP-10	1 EACH
LUMINAIRE	12 EACH
400W METAL HALIDE	
C.M.A. SIG & LIGHT POLE CMP-35-0	2 EACH
C.M.A. SIGNAL & LIGHT POLE, CMP-40-0	3 EACH

C.M.A. SIGNAL & LIGHT POLE, CMP-40-0 AT 14TH & FARNAM	1 EACH
C.M.A. SIGNAL & LIGHT POLE, CMP-40/40-0	1 EACH
C.M.A. SIG & LGHT POLE, CMP-0-0	3 EACH
C.M.A. SIGNAL & LIGHT POLE, CMP-50-0	1 EACH
C.M.A. SIGNAL & LIGHT POLE, CMP-55-0	1 EACH
SERVICE DISCONNECT PEDESTAL	4 EACH
2" CONDUIT, JACKED	2,186 LF
7/C #14 AWG TRAF SIG CABLE	370 LF
16/C #14 AWG TRAF SIG CABLE	758 LF
#8 GROUNDING CONDUCTOR	1,093 LF
SERVICE CABLE	1,200 LF
SERVICE ENTRANCE CABLE	600 LF
STREET LIGHT CABLE, NO. 6 3/C	1,098 LF
6 PAIR COMMUNICATION CABLE	119 LF
REM, PAINT & REIN SIGNS & SIGNALS	1 EACH
INSTALL PEDSTRIAN SIGNAL PS-1	27 EACH
REMOVE TRAFFIC SIGNAL AT 13TH & FARNAM	1 EACH
REMOVE TRAFFIC SIGNAL AT 14TH & FARNAM	1 EACH
REMOVE TRAFFIC SIGNAL AT 14TH & HARNEY	1 EACH
REMOVE TRAFFIC SIGNAL AT 14TH & HOWARD	1 EACH
REMOVE PULL BOX	1 EACH
RE-ENTERABLE ENCAPSULATED SPLICE	4 EACH