

NOTICE TO CONTRACTORS

CALL ORDER 200
 FEDERAL PROJECT NO. MAPA-3772(1)
 LOCATION: 156TH STREET/GILES ROAD
 COUNTIES: SARPY

The Nebraska Department of Roads will receive sealed bids for the COUNTY OF SARPY in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on March 04, 2010. At that time the bids will be opened and read for CONC PAVE ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT
 START DATE 09/20/2010 WORKING DAYS 20
 Price Range \$ 0 to \$ 500,000
 THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning February 09, 2010 at the Lincoln Central Office and February 15, 2010 at the District Engineer's Office at OMAHA
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	20	SHEETS	\$	5.00
CROSS SECTIONS (SHEETS X1 THRU X4)	4	SHEETS	\$	1.00
STANDARD PLANS	20	SHEETS	\$	5.00

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-A	PHOTO MAP
2-H	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N	GENERAL INFORMATION & DETOUR LOCATION MAP
2-L1 - 2-L2	CONSTRUCTION & REMOVALS
2-L3 - 2-L4	JOINTS, GRADES, GEOMETRICS
2-L5 - 2-L6	SIGNING & STRIPING
2-L7 - 2-L8	TRAFFIC SIGNALIZATION
3	PLAN & PROFILE SHEET
4	SPECIAL PLAN 1C CONCRETE FLUME, TYPE I
5	SPECIAL PLAN 2C EROSION CHECKS (ALL TYPES) & FABRIC SILT CHECKS
6 - 7	SPECIAL PLAN 3C TEMPORARY SILT CHECKS
R1	RIGHT-OF-WAY SHEET
X1 - X4	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
435-R1	(3 SHEETS) MANHOLE
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
910-R2	SIGNAL FACE CONFIGURATION
911-R1	SIGNAL MOUNTING
912-R4	TRAFFIC SIGNAL POLE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION (ESTABLISHED QUANTITY)	1,976	CY
REMOVE PAVEMENT	1,848	SY
SAWING PAVEMENT	164	LF
GRAVEL SURFACE COURSE	27	TON
CONC 47B-3500 DRIVEWAY	80	SY
9" CONC PVMT, 47B-3500	2,495	SY
ADJUST MANHOLE TO GRADE	2	EACH
FLUME SPILLWAY	17	LF
CONCRETE FLUME, TYPE I	2	EACH
ONLY, PREF PVMT MRKING T-4, GROOVED	1	EACH
ARROW, PREF PVMT MRKING T-4 GROOVED	2	EACH
4" WHITE PREF PVMT MRKNG T-4 GROOVED	556	LF
4" YEL PREF PVMT MRKNG, T-4, GROOVED	1,452	LF
12" WHT PREF PVMT MRKING T-4 GROOVED	72	LF
12" YEL PREF PVMT MRKING T-4 GROOVED	64	LF
FOUNDATION COURSE	2,495	SY
PREP OF INTER & DRIVE	80	SY
WATER	11	MGAL
EARTH SHOULDER CONSTRUCTION	11	STA
SUBGRADE PREPARATION	2,495	SY
EROSION CONTROL, CLASS 1D	2,260	SY
EROSION CHECKS, TYPE WATTLE	48	LF
ADJUST VALVE BOX TO GRADE	2	EACH

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
REMOVE SIGN	3	EACH
INSTALL SIGN	4	EACH
STREET NAME SIGN	4	EACH
18"		
REMOVE SIGN AND POST	9	EACH
TRAFFIC SIGNAL, TYPE TS-1	4	EACH
TRAFFIC SIGNAL, TYPE TS-1A	7	EACH
TRAF SIG CONTROL, TYPE TC-8	1	EACH
LUMINAIRE, TYPE HPS-200W	2	EACH
C.M.A. SIG & LGHT P CMP-25-6	1	EACH
C.M.A. SIG & LGHT POLE, CMP-30-6	1	EACH
MAST ARM SIGNAL POLE, MP-30	1	EACH
MAST ARM SIGNAL POLE, MP-45	1	EACH
2" CONDUIT IN TRENCH	152	LF
3" CONDUIT IN TRENCH	20	LF
2" CONDUIT, JACKED	14	LF
3" CONDUIT, JACKED	48	LF
12/C #14 AWG TRAF SIG CABLE	650	LF
#8 GROUNDING CONDUCTOR	300	LF
SERVICE CABLE	200	LF
STREET LIGHT CABLE, NO. 6 3/C	320	LF
REMOVE LIGHTING UNIT	1	EACH
VIDEO VEHICLE DETECTION SYSTEM	LUMP	LUMP

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III	738	B DAY
SIGN DAY	738	EACH
CONTRACTOR FURNISHED SIGN DAY	328	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	5	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	5	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	5	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	5	HOUR
TEMPORARY SILT CHECK	200	LF
TEMPORARY SILT FENCE	100	LF
TEMPORARY EARTH CHECK	100	LF