

NOTICE TO CONTRACTORS

CALL ORDER 500
FEDERAL PROJECT NO. URB-5709(3)
LOCATION: AVE 'B', SOUTH BELTLINE-OVERLAND, SCOTTSBLUFF
COUNTIES: SCOTTS BLUFF

The Nebraska Department of Roads will receive sealed bids for the CITY OF SCOTTSBLUFF in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on March 04, 2010. At that time the bids will be opened and read for GRAD CONC PAVE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT
START DATE 07/19/2010 WORKING DAYS 75
Price Range \$ 250,000 to \$ 1,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 6.0 %

Plans and specifications may be seen beginning February 09, 2010 at the Lincoln Central Office and February 15, 2010 at the District Engineer's Office at GERING
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	28 SHEETS	\$	7.00
CROSS SECTIONS (SHEETS X1 THRU X4)	4 SHEETS	\$	1.00
STANDARD PLANS	5 SHEETS	\$	1.25

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
2-T	TYPICAL CROSS SECTIONS
3	LEGEND & GENERAL NOTES
4	TRAFFIC CONTROL PLAN & DETOUR LOCATION MAP
5 - 8	REMOVAL PLANS
9 - 12	CONSTRUCTION PLAN & PROFILE SHEETS
13	INTERSECTION DETAIL
14 - 17	PAVEMENT MARKING PLANS
18 - 22	SPECIAL DETAILS
23 - 25	TYPICAL URBAN TRAFFIC CONTROL PLAN
26 - 27	SPECIAL PLAN 1C TEMPORARY SILT CHECKS
X1 - X4	CROSS SECTIONS

STANDARD PLANS

428-R3	CONCRETE PLUGS AND FIELD PIPE TAP DETAILS
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EXCAVATION		1,407 CY
WATER		16 MGAL
REMOVE PAVEMENT		9,950 SY
REMOVE DRIVEWAY		655 SY
REMOVE WALK		915 SY
REMOVE COMBINATION CURB AND GUTTER		2,622 LF
REMOVE MANHOLE		10 EACH

REMOVE INLET	11 EACH
REMOVE SEWER PIPE	71 LF
47B-3000 CONC FOR PIPE PLUG	1 CY
CURB INLET SEDIMENT FILTER	20 EACH
SEEDING, TYPE B	1 ACRE
FABRIC SILT FENCE-LOW POROSITY	1,523 LF
MULCH	2 TON

GROUP 3 CONCRETE PAVEMENT

	LUMP	LUMP
MOBILIZATION		
COMB CONC 47B-3500 CURB & GUTTER	4,311 LF	
CONC 47B-3000 SIDEWALKS	2,257 SY	
CONC 47B-3500 DRIVEWAY	815 SY	
8" CONC PVMT, 47B-3500	11,381 SY	
CAST IRON RING & COVER	8,800 LB	
CURB INLET	20 EACH	
RECONSTRUCT MANHOLE	15 EACH	
MANHOLE	5 EACH	
TAPPING EXISTING MANHOLE	5 EACH	
18" REINF CONCRETE SEWER PIPE	244 LF	
24" WHITE PREF PVMT MKING T-4 GROOVED	100 LF	
4" WHT WET RFLC PRF PVMT MKNG T4 GVD	328 LF	
6" WHT WET RFLC PRF PVMT MKNG T4 GVD	860 LF	
4" YEL WET RFLC PRF PVMT MKNG T4 GVD	5,149 LF	
ARROW, WET RFLC PRF PVMT MKNG, T 4 GVD	10 EACH	
ONLY, WET RFLC PRF PVMT MKNG, T 4 GVD	1 EACH	
WATER	47 MGAL	
EARTH SHOULDER CONSTRUCTION	45 STA	
SUBGRADE PREPARATION	12,196 SY	
ADJUST PULL BOX TO GRADE	2 EACH	
VALVE BOX	10 EACH	
RELOCATE FIRE HYDRANT AND VALVE	2 EACH	

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,320 BDAY
BARRICADE, TYPE III	2,112 BDAY
SIGN DAY	1,584 EACH
CONTRACTOR FURNISHED SIGN DAY	1,848 EACH
FLAGGING	20 DAY
MOBILIZATION	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	20 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	20 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	20 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	20 HOUR
TEMPORARY SILT CHECK	750 LF
TEMPORARY SILT FENCE	750 LF
TEMPORARY MULCH	2 TON