

NOTICE TO CONTRACTORS

CALL ORDER 650
STATE PROJECT NO. STR-26-2(1023)
LOCATION: US-26, LEWELLEN SOUTHEAST
COUNTIES: GARDEN

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 18, 2010. At that time the bids will be opened and read for BR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES
START DATE 04/19/2010 WORKING DAYS 115
Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning February 23, 2010 at the Lincoln Central Office and March 01, 2010 at the District Engineer's Office at NORTH PLATTE
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	56 SHEETS	\$	14.00
CROSS SECTIONS (SHEETS X1 THRU X8)	8 SHEETS	\$	2.00
STANDARD PLANS	6 SHEETS	\$	1.50

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N	GENERAL INFORMATION
2-P1 - 2-P4	PHASING PLANS
3 - 4	PLAN SHEETS
5	TYPICAL TRAFFIC SIGNAL CONTROL PLAN--FOR ONE LANE, TWO WAY OPERATION WITH BARRIERS
6	TEMPORARY TRAFFIC SIGNAL
7	TYPICAL TRAFFIC CONTROL PLAN--INERTIAL BARRIER SYSTEM
8	TEMPORARY PAVEMENT MARKING PLAN
9 - 23	SPECIAL PLAN 1 DECK STEEL GIRDER BRIDGE (REHAB) STA. 694+45.86
24 - 37	SPECIAL PLAN 2 DECK STEEL GIRDER BRIDGE (REHAB) STA. 708+95.86
38 - 45	SPECIAL PLAN 1C GUARDRAIL PLAN
46 - 47	SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER
X1 - X8	CROSS SECTIONS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 694+45.86

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000	193	CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	34,530	LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT, TYPE B	341	LF
CLASS I REPAIR	1,915	SY

CLASS II REPAIR	383 SY
CLASS III REPAIR	5 SY
PLACE, FINISH, & CURE CONC OVERLAY-SF	2,028 SY
47B-3000 CONC FOR BRIDGE	52 CY
47BD-4000 CONC FOR BRIDGE	128 CY
CONCRETE FOR OVERLAYS-SF	143 CY
PREP BRIDGE	1 EACH
AT STA. 694+45.86	
STRUC STEEL FOR SUPERSTRUCTURE	2,360 LB
EPOXY COATED RE-STEEL	36,510 LB
PIN REPLACEMENT	1 EACH
ABUTMENT REPAIR	30 SF
GRANULAR BACKFILL	190 CY
COLD MILLING, CLASS 4	1,999 SY

GROUP 6A BRIDGE AT STA. 708+95.86

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000		193 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	34,530	LB
ABUTMENT NO.1 EXCAVATION	LUMP	LUMP
ABUTMENT NO.2 EXCAVATION	LUMP	LUMP
PRECOMPRESSED POLY FOAM JOINT, TYPE B		256 LF
CLASS I REPAIR	1,490	SY
CLASS II REPAIR	298	SY
CLASS III REPAIR	5	SY
PLACE, FINISH, & CURE CONC OVERLAY-SF	1,578	SY
47B-3000 CONC FOR BRIDGE	52	CY
47BD-4000 CONC FOR BRIDGE	100	CY
CONCRETE FOR OVERLAYS-SF	108	CY
PREP BRIDGE	1	EACH
AT STA. 708+95.86		
STRUC STEEL FOR SUPERSTRUCTURE	1,705	LB
EPOXY COATED RE-STEEL	31,700	LB
ABUTMENT REPAIR	20	SF
GRANULAR BACKFILL	190	CY
COLD MILLING, CLASS 4	1,556	SY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL	450	LF
BRIDGE APPROACH SECTIONS	8	EACH
GUARDRAIL END TREATMENT, TYPE I	8	EACH

GROUP 9 BITUMINOUS

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT	115	CY
REMOVE PAVEMENT	888	SY
REMOVE GUARDRAIL	1,615	LF
HYDRATED LIME FOR ASPHALT MIXTURES	2	TON
ASPH CONC, TYPE SP4(0.5)	120	TON
PERF GRADED BINDER (64-28)	6	TON
TACK COAT	160	GAL
WATER	8	MGAL
EARTH SHOULDER CONSTRUCTION	16	STA
COLD MILLING, CLASS 3	1,067	SY
SURFACE UNDER GUARDRAIL	641	SY
EROSION CONTROL, CLASS 1D	1,747	SY
FABRIC SILT FENCE-LOW POROSITY	1,809	LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	5,265	BDAY
BARRICADE, TYPE III	1,170	BDAY
SIGN DAY	11,505	EACH
TEMP PAVEMENT MARKING REMOVAL	10,800	LF
PAVEMENT MARKING REMOVAL	5,200	LF
TEMP PVMT MARKING, TYPE PAINT	10,800	LF
TEMP PVMT MARKING SURF PREP	4,800	LF
FLAGGING	10	DAY
CONCRETE PROTECTION BARRIER	1,875	LF
RELOCATE CONC PROTECTION BARRIER	1,875	LF
RELOC INERTIAL BARRIER SYSTEM	2	EACH
INERTIAL BARRIER SYSTEM	2	EACH
REPLACEMENT MODULE	7	EACH
TEMPORARY RUMBLE STRIP	4	EACH
TEMPORARY TRAFFIC SIGNAL	1	EACH
TRAFFIC CONTROL MANAGEMENT	195	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	20	HOURL
RENTAL OF DUMP TRUCK, FULLY OPERATED	20	HOURL
RENTAL OF SKID LOADER, FULLY OPERATED	20	HOURL
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	20	HOURL
TEMPORARY SILT FENCE	400	LF