

NOTICE TO CONTRACTORS

CALL ORDER 750
 FEDERAL PROJECT NO. STPAA-6602(1)
 LOCATION: 11th AVENUE, SHERMAN-LINCOLN, HOLDREGE
 COUNTIES: PHELPS

The Nebraska Department of Roads will receive sealed bids for the CITY OF HOLDREGE in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on March 18, 2010. At that time the bids will be opened and read for CONC PAVE CULV WATER MAIN SAN ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT
 START DATE 07/12/2010 WORKING DAYS 80
 Price Range \$ 500,000 to \$ 2,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 6.0 %

Plans and specifications may be seen beginning February 23, 2010 at the Lincoln Central Office and March 01, 2010 at the District Engineer's Office at MCCOOK
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	88 SHEETS	\$	22.00
CROSS SECTIONS (SHEETS X1 THRU X19)	19 SHEETS	\$	4.75
STANDARD PLANS	22 SHEETS	\$	5.50

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-H1 - 2-H2	HORIZONTAL & VERTICAL CONTROL
2-N	GENERAL INFORMATION
2-P1 - 2-P6	PHASING PLANS
2-P7 - 2-P10	PHASING PLANS--DETOURS
2-L1 - 2-L7	GEOMETRICS, JOINTS, & GRADES
2-L8 - 2-L14	REMOVALS
2-L15 - 2-L21	CONSTRUCTION
2-L22 - 2-L25	DRAINAGE
2-L26 - 2-L33	EROSION CONTROL
3 - 9	PLAN & PROFILE SHEETS
10	PLAN & PROFILE SHEETS--SANITARY SEWER
11 - 15	PLAN & PROFILE SHEETS--WATER MAIN
16 - 22	PAVEMENT MARKINGS
23 - 30	STREET LIGHTING PLANS
31	SPECIAL PLAN 1C CURB RAMPS
32 - 33	SPECIAL PLAN 2C TEMPORARY SILT CHECKS
R1 - R8	RIGHT-OF-WAY SHEETS
X1 - X19	CROSS SECTIONS

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
309	MAILBOX SUPPORT POST
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
435-R1	(3 SHEETS) MANHOLE
443-R7	(2 SHEETS) CURB INLETS AND JUNCTION BOX
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
923	TRAFFIC CONTROL--ROAD CLOSURE
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
LARGE TREE REMOVAL		2 EACH
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
REM AND REP'MENT OF UNSUITABLE MATERIAL		4,000 CY
EARTHWORK MEASURED IN EMBANKMENT		1,200 CY
REMOVE PAVEMENT		11,293 SY
REMOVE DRIVEWAY		1,215 SY
REMOVE WALK		2,053 SY
GRAVEL SURFACE COURSE		200 TON
CRUSHED ROCK SURFACE COURSE		300 TON
REMOVE AND RESET MAILBOX		5 EACH
REMOVE AND SALVAGE		1 EACH
FLAGPOLE		
CONC 47BX-3000 SIDEWALK		2,295 SY
DETECTABLE WARNING PANEL		82 EACH
6" CONC CLASS 47B-3000 MEDIAN SURFACING		43 SY
CONC 47B-3500 DRIVEWAY		1,151 SY
8" CONC PVMT, 47B-3500		13,124 SY
ADJUST MANHOLE TO GRADE		7 EACH
4" YEL POLYUREA PVMT MRKING		1,270 LF
8" YEL POLYUREA PVMT MRKING		140 LF
4" WHT POLYUREA PVMT MRKING, GROOVED		50 LF
4" YEL POLYUREA PVMT MRKING, GROOVED		1,657 LF
WATER		56 MGAL
EARTH SHOULDER CONSTRUCTION		55 STA
SUBGRADE PREPARATION		14,275 SY
HYDRO-SEEDING		4,451 SY
FABRIC SILT FENCE-LOW PROF LOW PORO		1,928 LF
HYDROMULCH		1 TON
REMOVE AND RESET TREE		1 EACH
ADJUST VALVE BOX TO GRADE		9 EACH

GROUP 4 CULVERTS

MOBILIZATION	LUMP	LUMP
CURB INLET		10 EACH
Y=8'		
CURB INLET		12 EACH
Y=10'		
MANHOLE		1 EACH
AT STA. 205+30 RT.		
MANHOLE		1 EACH
AT STA. 209+00 RT.		
MANHOLE		1 EACH
AT STA. 209+68 RT.		
MANHOLE		1 EACH
AT STA. 209+84 RT.		
MANHOLE		1 EACH
AT STA. 212+65 RT.		
MANHOLE		1 EACH
AT STA. 215+43 RT.		
MANHOLE		1 EACH
AT STA. 217+69 RT.		
18" REINF CONCRETE SEWER PIPE		258 LF
24" REINF CONCRETE SEWER PIPE		665 LF
30" REINF CONCRETE SEWER PIPE		122 LF
36" REINF CONCRETE SEWER PIPE		651 LF
42" REINF CONCRETE SEWER PIPE		84 LF
48" REINF CONCRETE SEWER PIPE		475 LF
36" RND EQUIV RCSP		278 LF
CURB INLET SEDIMENT FILTER		22 EACH

GROUP 4A WATER MAIN AND SANITARY

	LUMP	LUMP
MOBILIZATION		
CONNECT SANITARY SERVICE		4 EACH
4" SANITARY SEWER PIPE		12 LF
6" SANITARY SEWER PIPE		4 LF
8" SANITARY SEWER PIPE		345 LF
SANITARY MANHOLE		2 EACH
CURB STOP		17 EACH
1"		
WET TAP CUT-IN		11 EACH
1" CORPORATION STOP		17 EACH
1" WATER SERVICE		437 LF
4" WATER MAIN PIPE		67 LF
6" WATER MAIN PIPE		102 LF
8" WATER MAIN PIPE		1,464 LF
4" GATE VALVE		3 EACH
6" GATE VALVE		5 EACH
8" GATE VALVE		9 EACH
FIRE HYDRANT		3 EACH
SALVAGE FIRE HYDRANT		2 EACH
4" SOLID SLEEVE		5 EACH
6" SOLID SLEEVE		5 EACH
8" SOLID SLEEVE		1 EACH
8" X 4" TEE		4 EACH
8" X 6" TEE		8 EACH
8" X 8" TEE		1 EACH
6" - 45 DEGREE BEND		8 EACH
8" - 45 DEGREE BEND		6 EACH
4" - 11 1/4 DEGREE BEND		2 EACH
4" - 22 1/2 DEGREE BEND		3 EACH
6" - 22 1/2 DEGREE BEND		1 EACH
8" X 6" REDUCER		1 EACH
8" X 4" REDUCER		1 EACH
8" - 4" WYE		3 EACH
SANITARY SERVICE		
8" - 6" WYE		1 EACH
SANITARY SERVICE		
ADJUST METER PIT TO GRADE		8 EACH
ADJUST FIRE HYDRANT TO GRADE		1 EACH
RECONNECT WATER SERVICE		17 EACH
RELOCATE WATER METER PIT		18 EACH
RELOCATE FIRE HYDRANT		1 EACH

GROUP 8B ELECTRICAL

	LUMP	LUMP
MOBILIZATION		
PULL BOX, TYPE PB-5		3 EACH
ST LIGHT UNIT, SL-A-35-6-0.15 F		16 EACH
LIGHTING CONTROL CENTER, R		2 EACH
2" CONDUIT IN TRENCH		2,804 LF
2" CONDUIT UNDER ROADWAY		467 LF
STREET LIGHT CABLE, NO. 1/0 USE		9,813 LF
STREET LIGHT CABLE, NO. 6 BARE		3,271 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE III		2,934 BDAY
SIGN DAY		3,762 EACH
CONTRACTOR FURNISHED SIGN DAY		726 EACH
FLAGGING		30 DAY
TRAINING		500 HOUR
MOBILIZATION	LUMP	LUMP

RENTAL OF LOADER, FULLY OPERATED	25 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	25 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	25 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	25 HOUR
TEMPORARY SILT CHECK	200 LF
TEMPORARY SILT FENCE	500 LF
TEMPORARY MULCH	2 TON