

## NOTICE TO CONTRACTORS

CALL ORDER 705  
FEDERAL PROJECT NO. HSIP-6-4(127)  
LOCATION: E. JCT US-6/N-44  
COUNTIES: KEARNEY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on April 29, 2010. At that time the bids will be opened and read for ELEC BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

START DATE 09/13/2010 WORKING DAYS 25  
Price Range \$ 0 to \$ 500,000  
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning April 06, 2010 at the Lincoln Central Office and April 12, 2010 at the District Engineer's Office at MCCOOK. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

## NOTICE TO BIDDERS

To be eligible for the award of this contract, bidders shall submit a completed bidding proposal for Call Order No. 700, {Project No. RD-44-1(1003)} and Call Order No. 705, {Project No. HSIP-6-4(127)}. Award of Contract, if awarded, will be made on the combined bid for these call order nos. Separate contracts will be awarded for each Call Order Number. Please order plans and proposals accordingly.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	28	SHEETS	\$ 7.00
CROSS SECTIONS (SHEETS X1 THRU X7)	7	SHEETS	\$ 1.75
STANDARD PLANS	17	SHEETS	\$ 4.25

### SHEET NO.

1	TITLE PAGE
2-T1 - 2-T3	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W2	WETLANDS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
3 - 5	PLAN SHEETS--GEOMETRICS
6 - 8	PLAN SHEETS--REMOVALS
9 - 11	PLAN SHEETS--CONSTRUCTION
12	TYPICAL TRAFFIC CONTROL PLAN--VEHICLE SIGNING FOR PAINT STRIPING
13	PAVEMENT MARKING PLAN
14	TYPICAL PAVEMENT MARKING PLAN--4" PAVEMENT MARKING
15	TEMPORARY PAVEMENT MARKING PLAN
16 - 19	ROADWAY LIGHTING PLANS
20	EARTHWORK DATA SHEET
X1 - X7	CROSS SECTIONS

### STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
410-R3	(2 SHEETS) FLARED END SECTIONS FOR CULVERT PIPES
502	SILT FENCE DETAILS
914-R6	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
921-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
PULL BOX, TYPE PB-5		1 EACH
ST LIGHT UNIT SL-BT-40-12-0.25		2 EACH
1 1/2" CONDUIT IN TRENCH		752 LF
STREET LIGHT CABLE, NO. 6 BARE		752 LF
STREET LIGHT CABLE, NO. 6 USE		1,504 LF
RELOCATE STREET LIGHTING UNIT		3 EACH

GROUP 9 BITUMINOUS

BARRICADE, TYPE II		1,000 BDAY
BARRICADE, TYPE III		288 BDAY
TEMPORARY SIGN DAY		350 EACH
SIGN DAY		2,165 EACH
OVERLAY BROKEN LINES		40 STA
OVERLAY SOLID LINES		80 STA
FLAGGING		50 DAY
MOBILIZATION	LUMP	LUMP
MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
EARTHWORK MEASURED IN EMBANKMENT		247 CY
REMOVE PAVEMENT		586 SY
SAWING PAVEMENT		2,476 LF
REMOVE ASPHALT SURFACE		1,770 SY
TIE BARS		1,304 EACH
CONC 47B-3000 MEDIAN SURFACING		127 SY
6" CONCRETE BASE COURSE		2,110 SY
10" CONCRETE BASE COURSE		847 SY
REMOVE FLARED- END SECTION		1 EACH
EXC FOR PIPE, PIPE-ARCH CULV, AND HDWL		5 CY
24" CORRUGATED METAL PIPE		6 LF
24" METAL FLARED-END SECTION		1 EACH
12" WHT PREF PVMT MRKING T-4 GROOVED		15 LF
4" WHT WET RFLC PRF PVMT MKNG T4 GVD		7,400 LF
12" WHT WET RFLC PRF PVMT MKNG T4 GVD		1,350 LF
4" YEL WET RFLC PRF PVMT MKNG T4 GVD		9,600 LF
HYDRATED LIME FOR ASPHALT MIXTURES		22 TON
ASPH CONCRETE FOR PATCHING, TYPE SP4(0.5)		50 TON
ASPH CONC, TYPE SP4(0.5)		1,940 TON
PLACE ASPH CONC FOR DRIVE & INTER		244 SY
PERF GRADED BINDER (64-28)		93 TON
TACK COAT		2,210 GAL
RENTAL OF LOADER, FULLY OPERATED		10 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED		5 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED		10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED		10 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.		5 HOUR
WATER		10 MGAL
EARTH SHOULDER CONSTRUCTION		9 STA
SUBGRADE PREPARATION		2,154 SY
COLD MILLING, CLASS 3		11,372 SY
SEEDING, TYPE B		1 ACRE
FABRIC SILT FENCE-LOW POROSITY		450 LF
MULCH		2 TON