

NOTICE TO CONTRACTORS

CALL ORDER 115
FEDERAL PROJECT NO. STP-79-2(113)
LOCATION: N-79, VALPARAISO-N-92
COUNTIES: SAUNDERS

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 13, 2010. At that time the bids will be opened and read for GR GDRL BIT

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 8.9 MILES
START DATE 06/28/2010 WORKING DAYS 70
Price Range \$ 1,000,000 to \$ 3,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning April 20, 2010 at the Lincoln Central Office and April 26, 2010 at the District Engineer's Office at LINCOLN
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING CROSS SECTIONS OR STANDARDS)	51	SHEETS	\$ 12.75
CROSS SECTIONS (SHEETS X1 THRU X53)	53	SHEETS	\$ 13.25
STANDARD PLANS	13	SHEETS	\$ 3.25

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T2	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W9	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--SUPERELEVATION DIAGRAMMATIC PROFILES
2-L	GEOMETRICS
3 - 11	PLAN SHEETS
12	TEMPORARY PAVEMENT MARKING PLAN
13 - 14	EARTHWORK DATA SHEETS
15 - 16	SPECIAL PLAN 1C BRIDGE RAIL REMODEL STA. 735+25.00
17 - 18	SPECIAL PLAN 2C BRIDGE RAIL REMODEL STA. 2132+50.00
19 - 28	SPECIAL PLAN 3C GUARDRAIL PLAN
29 - 31	SPECIAL PLAN 4C CABLE GUARDRAIL
32	SPECIAL PLAN 5C CURB RAMPS
X1 - X53	CROSS SECTIONS

STANDARD PLANS

108-R3	SUPERELEVATION PLAN FOR CONCRETE AND BITUMINOUS SURFACING
301-R10	(3 SHEETS) PAVEMENT DETAILS
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 1 GRADING

MOBILIZATION	LUMP	LUMP
GENERAL CLEARING AND GRUBBING	LUMP	LUMP
REMOVAL OF UNSUITABLE MATERIAL		90 CY
WATER		168 MGAL
EARTHWORK MEASURED IN EMBANKMENT	12,939	CY
REMOVE PAVEMENT		24 SY
SAWING PAVEMENT		154 LF
REMOVE ASPHALT SURFACE		38 SY
REMOVE WALK		39 SY
REMOVE INLET		2 EACH
REMOVE GUARDRAIL	4,343	LF
COVER CROP SEEDING		1 ACRE
EROSION CONTROL, CLASS 1D	21,031	SY
FABRIC SILT FENCE-LOW POROSITY	6,768	LF

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
47BD-4000 CONC FOR CONC. RAIL		4 CY
EPOXY COATED RE-STEEL FOR CONC RAIL	1,240	LB
PREP BRIDGE		1 EACH
735+25		
PREP BRIDGE		1 EACH
2132+50		
W-BEAM GUARDRAIL	2,150	LF
CABLE GUARDRAIL	3,797	LF
BRIDGE APPROACH SECTIONS		8 EACH
TERMINAL ANCHORAGE SECTIONS		18 EACH
GUARDRAIL END TREATMENT, TYPE II		14 EACH

GROUP 9 BITUMINOUS

OVERLAY BROKEN LINES		1,407 STA
OVERLAY SOLID LINES		2,814 STA
MOBILIZATION	LUMP	LUMP
MAILBOX POST		13 EACH
CONC 47B-3500 CURB TYPE II		104 LF
CONC 47B-3000 SIDEWALKS		39 SY
DETECTABLE WARNING PANEL		4 EACH
CONC 47B-3000 MEDIAN SURFACING		24 SY
ADJUSTING INLET TO GRADE		2 EACH
MEMBRANE WATERPROOFING		299 SY
HYDRATED LIME FOR ASPHALT MIXTURES		278 TON
ASPH CONCRETE FOR PATCHING, TYPE SPR		250 TON
ASPH CONC, TYPE SPR	27,580	TON
PERF GRADED BINDER (64-34)	1,057	TON
CONSTRUCTING ASPH CONC CURB		40 LF
TACK COAT	25,360	GAL
COLD MILLING, CLASS 3		474 STA
COLD MILLING, CLASS 4		299 SY
SURFACE UNDER GUARDRAIL	4,729	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		1 ACRE
MULCH		2 TON

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	22,500	BDAY
BARRICADE, TYPE III	1,105	BDAY
TEMPORARY SIGN DAY		980 EACH
SIGN DAY	13,475	EACH
FLAGGING	130	DAY
FURNISHING AND OPERATING PILOT VEHICLE	65	DAY
FIELD OFFICE		1 EACH

MOBILIZATION	LUMP	LUMP
RENTAL OF LOADER, FULLY OPERATED	120	120 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	40	40 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	120	120 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	120	120 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	80	80 HOUR
TEMPORARY SILT FENCE	1,000	1,000 LF