

NOTICE TO CONTRACTORS

CALL ORDER 215
FEDERAL PROJECT NO. HSIP-50-2(133)
LOCATION: N-50/GILES ROAD
COUNTIES: SARPY

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on May 13, 2010. At that time the bids will be opened and read for CONC PAVE ELEC

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: CONCRETE PAVEMENT

START DATE 07/06/2010 WORKING DAYS 15
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning April 20, 2010 at the Lincoln Central Office and April 26, 2010 at the District Engineer's Office at OMAHA

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	11 SHEETS	\$	2.75
STANDARD PLANS	15 SHEETS	\$	3.75

SHEET NO.

1	TITLE PAGE
2-T	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-H	HORIZONTAL ALIGNMENT & ORIENTATION
2-N	GENERAL INFORMATION
2-L1 - 2-L2	GEOMETRICS
3 - 4	PLAN SHEETS--CONSTRUCTION & REMOVAL
5	TRAFFIC SIGNAL PLAN--S. APPROACH TO GILES ROAD
6	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
329-R7	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
910-R2	SIGNAL FACE CONFIGURATION
911-R1	SIGNAL MOUNTING
912-R4	TRAFFIC SIGNAL POLE DETAILS
914-R6	PULL BOX DETAIL
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 3 CONCRETE PAVEMENT

MOBILIZATION	LUMP	LUMP
REMOVE PAVEMENT		210 SY
SAWING PAVEMENT		969 LF
REMOVE CONCRETE MEDIAN SURFACING		1,528 SY
TIE BARS		352 EACH
CONC 47B-3000 MEDIAN SURFACING		581 SY
10" DOWELED CONC PVMT, 47B-3500		1,158 SY
FOUNDATION COURSE		1,158 SY
WATER		4 MGAL
SUBGRADE PREPARATION		1,158 SY

GROUP 8B ELECTRICAL

MOBILIZATION	LUMP	LUMP
INSTALL SIGN		1 EACH
PULL BOX, TYPE PB-1		1 EACH
TRAFFIC SIGNAL, TYPE TS-1		2 EACH
MAST ARM SIGNAL POLE, MP-35		1 EACH
2" CONDUIT IN TRENCH		4 LF
3/C #14 AWG TRAF SIG CABLE		4 LF
GROUNDING CONDUCTOR		4 LF
REMOVE PEDESTAL POLE		2 EACH
REMOVE TRAFFIC SIGNAL CABLE		84 LF

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II		810 BDAY
BARRICADE, TYPE III		135 BDAY
SIGN DAY		810 EACH
FLASHING ARROW PANEL		27 DAY
FLAGGING		5 DAY
MOBILIZATION	LUMP	LUMP