

NOTICE TO CONTRACTORS

CALL ORDER 100
 FEDERAL PROJECT NO. BRD-159-7(106)
 LOCATION: US-159, RULO BRIDGE, MAIN SPANS
 COUNTIES: RICHARDSON HOLT MO

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on July 08, 2010. At that time the bids will be opened and read for BRIDGE

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES
 START DATE 08/23/2010 CALENDAR DAYS 762
 Price Range \$ 15,000,000 to \$ 22,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning June 17, 2010 at the Lincoln Central Office and June 21, 2010 at the District Engineer's Office at LINCOLN
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.
 This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	75	SHEETS	\$	18.75
STANDARD PLANS	9	SHEETS	\$	2.25

SHEET NO.

1	TITLE PAGE
2-T1	TYPICAL CROSS SECTIONS
2-S1	SUMMARY OF QUANTITIES
2-W1 - 2-W3	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & CONTROL POINTS
2-N1	GENERAL INFORMATION
3 - 5	PLAN & PROFILE SHEETS
6	TYPICAL PAVEMENT MARKING PLAN--5" PAVEMENT MARKING
7 - 60	SPECIAL PLAN 1 STEEL PLATE GIRDER BRIDGE STA. 200+00.29
61 - 62	SPECIAL PLAN 1C TEMPORARY SILT CHECKS
R1 - R4	RIGHT-OF-WAY SHEETS

STANDARD PLANS

501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 200+00.29

MOBILIZATION	LUMP	LUMP
PIER	LUMP	LUMP
NO. R1 EXCAVATION		
PIER	LUMP	LUMP
NO. R2 EXCAVATION		
PIER	LUMP	LUMP
NO. R3 EXCAVATION		
PIER	LUMP	LUMP
NO. R4 EXCAVATION		
DECK JOINT SEAL, TYPE IV	86	LF
EXPANSION BEARING, TFE TYPE	8	EACH
FIXED BEARING DVC, TYPE I	8	EACH

47BD-4000 CONC FOR BRIDGE	5,361	CY
ACCESS BRIDGE	LUMP	LUMP
STEEL SUPERSTRUCTURE	LUMP	LUMP
200+00.29		
EPOXY COATED RE-STEEL	804,116	LB
HP 14"X89# STEEL PILING	1,360	LF
TEST PILE		1 EACH
TEST DRILLED SHAFT		1 EACH
AT PIER NO. R2		
TEST DRILLED SHAFT		1 EACH
AT PIER NO. R4		
ROCK SOCKET	150	LF
66"		
ROCK SOCKET	517	LF
78"		
DRILLED SHAFT	263	LF
72"		
DRILLED SHAFT	558	LF
84"		
FOUNDATION INSPECTION HOLES	161	LF
DRAINAGE SYSTEM		1 EACH
192+91.35		
DRAINAGE SYSTEM		1 EACH
203+17.35		
1 1/2" CONDUIT IN BRIDGE	1,026	LF
NAVIGATION LIGHTING SYSTEM		1 EACH
TEMPORARY NAVIGATION LIGHTING SYSTEM		1 EACH
CLEARANCE GAUGE	LUMP	LUMP

GROUP 6A BRIDGE AT STA. 200+00.29

MOBILIZATION	LUMP	LUMP
PIER	LUMP	LUMP
NO. R1 EXCAVATION		
PIER	LUMP	LUMP
NO. R2 EXCAVATION		
PIER	LUMP	LUMP
NO. R3 EXCAVATION		
PIER	LUMP	LUMP
NO. R4 EXCAVATION		
DECK JOINT SEAL, TYPE IV	86	LF
EXPANSION BEARING, TFE TYPE	8	EACH
FIXED BEARING DVC, TYPE I	8	EACH
47BD-4000 CONC FOR BRIDGE	5,401	CY
ACCESS BRIDGE	LUMP	LUMP
STEEL SUPERSTRUCTURE	LUMP	LUMP
200+00.29		
EPOXY COATED RE-STEEL	806,116	LB
TEST DRILLED SHAFT		1 EACH
AT PIER NO. R2		
TEST DRILLED SHAFT		1 EACH
AT PIER NO. R4		
ROCK SOCKET	298	LF
66"		
ROCK SOCKET	517	LF
78"		
DRILLED SHAFT	585	LF
72"		
DRILLED SHAFT	558	LF
84"		
FOUNDATION INSPECTION HOLES	209	LF
DRAINAGE SYSTEM		1 EACH
192+91.35		

DRAINAGE SYSTEM	1 EACH
203+17.35	
1 1/2" CONDUIT IN BRIDGE	1,026 LF
NAVIGATION LIGHTING SYSTEM	1 EACH
TEMPORARY NAVIGATION LIGHTING SYSTEM	1 EACH
CLEARANCE GAUGE	LUMP LUMP

GROUP 10 GENERAL ITEMS

SIGN DAY	2,862 EACH
PERMANENT PAVEMENT MARKING PAINT	4,120 LF
FLAGGING	200 DAY
FIELD OFFICE	1 EACH
TRAINING	6,000 HOUR
MOBILIZATION	LUMP LUMP
GENERAL CLEARING AND GRUBBING	LUMP LUMP
CONSTRUCTION STAKING AND SURVEYING	LUMP LUMP
RENTAL OF LOADER, FULLY OPERATED	10 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10 HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10 HOUR
SEEDING, TYPE B	1 ACRE
COVER CROP SEEDING	1 ACRE
TEMPORARY SILT CHECK	500 LF
TEMPORARY SILT FENCE	1,000 LF
TEMPORARY EARTH CHECK	500 LF
MULCH	3 TON