

NOTICE TO CONTRACTORS

CALL ORDER 215
FEDERAL PROJECT NO. MAPA-5049(4)
LOCATION: OMAHA MAJOR STREET RESURFACING-PKG 1
COUNTIES: DOUGLAS

The Nebraska Department of Roads will receive sealed bids for the CITY OF OMAHA in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on October 21, 2010. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS
START DATE 05/09/2011 CALENDAR DAYS 125
Price Range \$ 3,000,000 to \$ 6,000,000
THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning September 28, 2010 at the Lincoln Central Office and October 04, 2010 at the District Engineer's Office at OMAHA
Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded by the American Recovery and Reinvestment Act of 2009, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	104	SHEETS	\$	26.00
STANDARD PLANS	5	SHEETS	\$	1.25

SHEET NO.

1	TITLE PAGE
2-S1 - 2-S2	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION
3 - 70	PLAN SHEETS--RESURFACING
71 - 97	PLAN SHEETS--STRIPING
98 - 99	SIGNS & BARRICADES
100	SPECIAL PLAN 1C ASPHALT PAVEMENT RESURFACING-- MH RING & COVER ADJUSTMENT DETAILS
101	SPECIAL PLAN 2C ASPHALT PAVEMENT RESURFACING-- INLET ADJUSTMENT DETAILS
102	SPECIAL PLAN 3C RECONSTRUCT GRATE INLET TYPE "A"

STANDARD PLANS

920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
924	(3 SHEETS) TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	15,909 BDAY
BARRICADE, TYPE III	414 BDAY
TEMPORARY SIGN DAY	513 EACH
SIGN DAY	281 EACH
CONTRACTOR FURNISHED SIGN DAY	235 EACH
FLASHING ARROW PANEL	259 DAY
FLAGGING	72 DAY
TOWING	16 HOUR
MOBILIZATION	LUMP LUMP
9" CONCRETE BASE COURSE	810 SY
CAST IRON RING & COVER	22,230 LB
RECONSTRUCT INLET	4 EACH
ADJUSTING INLET TO GRADE	5 EACH

ADJUST MANHOLE TO GRADE	151 EACH
ADJUST	390 EACH
UTILITY TO GRADE	
ARROW, PREF PVMT MRKING T-4	51 EACH
ONLY, PREF PVMT MRKING T-4	53 EACH
5" WHT PREF PVMT MRKING T-4	28,794 LF
5" YEL PREF PVMT MRKING T-4	72,197 LF
ASPH CONC, TYPE CMM	36,370 TON
ASPH CONC, TYPE FMM	3,961 TON
PERF GRADED BINDER (70-28)	2,097 TON
COLD MILLING, CLASS 3	251,619 SY
CONC SURF MILLING	68,200 SY