

NOTICE TO CONTRACTORS

CALL ORDER 220
 FEDERAL PROJECT NO. MAPA-5038(17)
 LOCATION: OMAHA MAJOR STREET RESURFACING-PKG 2
 COUNTIES: DOUGLAS

The Nebraska Department of Roads will receive sealed bids for the CITY OF OMAHA in Room 104 of the Central Office Building at 1500 Hwy 2 at Lincoln, until 1:30 P.M. on November 04, 2010. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

START DATE 07/18/2011 CALENDAR DAYS 104
 Price Range \$ 3,000,000 to \$ 6,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning October 12, 2010 at the Lincoln Central Office and October 18, 2010 at the District Engineer's Office at OMAHA. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$ 5.00
PLANS (NOT INCLUDING STANDARDS)	112	SHEETS	\$ 28.00
STANDARD PLANS	5	SHEETS	\$ 1.25

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
2-N	GENERAL INFORMATION
3 - 69	PLAN SHEETS--RESURFACING
70 - 107	PLAN SHEETS--STRIPING
108 - 109	SIGNS & BARRICADES
110	SPECIAL PLAN 1C ASPHALT PAVEMENT RESURFACING-- MH RING & COVER ADJUSTMENT DETAILS
111	SPECIAL PLAN 2C ASPHALT PAVEMENT RESURFACING-- INLET ADJUSTMENT DETAILS

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
924	(3 SHEETS)	TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	13,649	BDAY
BARRICADE, TYPE III	320	BDAY
TEMPORARY SIGN DAY	430	EACH
SIGN DAY	186	EACH
CONTRACTOR FURNISHED SIGN DAY	396	EACH
FLASHING ARROW PANEL	117	DAY
FLAGGING	73	DAY
TOWING	16	HOUR
MOBILIZATION	LUMP	LUMP
9" CONCRETE BASE COURSE	380	SY
CAST IRON RING & COVER	10,944	LB
ADJUSTING INLET TO GRADE	13	EACH
ADJUST MANHOLE TO GRADE	71	EACH
ADJUST	95	EACH
UTILITY TO GRADE		

ARROW, PREF PVMT MRKING T-4	94 EACH
ONLY, PREF PVMT MRKING T-4	84 EACH
5" WHT PREF PVMT MRKING T-4	37,891 LF
5" YEL PREF PVMT MRKING T-4	41,627 LF
ASPH CONC, TYPE CMM	36,000 TON
ASPH CONC, TYPE FMM	2,185 TON
PLACE ASPH CONC FOR DRIVE & INTER	4,361 SY
PERF GRADED BINDER (70-28)	1,981 TON
COLD MILLING, CLASS 3	251,720 SY
COLD MILLING, CLASS 4	17,020 SY
CONC SURF MILLING	25,465 SY