

NOTICE TO CONTRACTORS

CALL ORDER 125
STATE PROJECT NO. STR-80-8(1041)
LOCATION: I-80, SEWARD INTERCHANGE BRIDGE
COUNTIES: SEWARD

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 09, 2010. At that time the bids will be opened and read for BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES

START DATE 07/05/2011 WORKING DAYS 40
Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning November 16, 2010 at the Lincoln Central Office and November 22, 2010 at the District Engineer's Office at LINCOLN. Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	23 SHEETS	\$	5.75
STANDARD PLANS	2 SHEETS	\$	0.50

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES
3	PLAN SHEET
4	TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
5	TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR NARROW BRIDGE, ONE LANE, TWO WAY OPERATION WITH BARRIERS (10')
6	TEMPORARY TRAFFIC SIGNAL
7	TEMPORARY PAVEMENT MARKING PLAN
8 - 14	SPECIAL PLAN 1 REMODEL BRIDGE ENDS STA. 15+00.00
15 - 21	SPECIAL PLAN 1C GUARDRAIL PLAN
22 - 23	SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER

STANDARD PLANS

920-R5 (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STATION 15+00.00

MOBILIZATION	LUMP	LUMP
PREFORMED SILICONE JOINT, TYPE A		64 LF
47BD-4000 CONC FOR BRIDGE		60 CY
PREP BRIDGE		1 EACH
15+00.00		
EPOXY COATED RE-STEEL	7,370	LB
GRANULAR BACKFILL		35 CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
W-BEAM GUARDRAIL		443 LF
REMOVE GUARDRAIL		481 LF
BRIDGE APPROACH SECTIONS		4 EACH
GUARDRAIL END TREATMENT, TYPE II		4 EACH

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	488	BDAY
BARRICADE, TYPE III	244	BDAY
SIGN DAY	3,416	EACH
TEMP PAVEMENT MARKING REMOVAL	2,400	LF
PAVEMENT MARKING REMOVAL	2,400	LF
TEMP PVMT MARKING, TYPE PAINT	2,400	LF
TEMP PVMT MARKING SURF PREP	2,400	LF
CONCRETE PROTECTION BARRIER	500	LF
RELOCATE CONC PROTECTION BARRIER	500	LF
TEMPORARY RUMBLE STRIP	4	EACH
TEMPORARY TRAFFIC SIGNAL	1	EACH
TRAFFIC CONTROL MANAGEMENT	61	DAY
MOBILIZATION	LUMP	LUMP