

NOTICE TO CONTRACTORS

CALL ORDER 400
 FEDERAL PROJECT NO. STP-92-4(111)
 LOCATION: N-92, WEST OF ST. PAUL
 COUNTIES: HOWARD

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 09, 2010. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 5.8 MILES
 START DATE 07/25/2011 WORKING DAYS 55
 Price Range \$ 1,000,000 to \$ 3,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 3.0 %

Plans and specifications may be seen beginning November 16, 2010 at the Lincoln Central Office and November 22, 2010 at the District Engineer's Office at GRAND ISLAND
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL		EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	10	SHEETS	\$	2.50
STANDARD PLANS	7	SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T3	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-N1 - 2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TEMPORARY PAVEMENT MARKING PLAN
4	TYPICAL PAVEMENT MARKING PLAN--RURAL LEFT TURN BAYS
5	PAVEMENT MARKING DETAILS

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING
924	(3 SHEETS)	TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	28,960	B DAY
BARRICADE, TYPE III	388	B DAY
TEMPORARY SIGN DAY	960	EACH
SIGN DAY	5,334	EACH
OVERLAY BROKEN LINES	923	STA
OVERLAY SOLID LINES	1,847	STA
FLAGGING	920	DAY
FURNISHING AND OPERATING PILOT VEHICLE	65	DAY
MOBILIZATION	LUMP	LUMP
CONC PVMT REPAIR TYPE A FULL DEPTH	1	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	149	CY
24" WHT WET RFLC PRF PVMT MKNG T4 GVD	72	LF
RR XING SYMBOL PREF PVMT MRKING T-4 GRVD	2	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	190	TON
FOUNDATION COURSE REPLACEMENT	6	CY
ASPH CONC, TYPE SPS	7,510	TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	9,210	TON

ASPH CONC, TYPE SPR	9,340 TON
ASPH CONCRETE FOR PATCHING, TYPE SPR	500 TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	500 TON
PERF GRADED BINDER (52-34)	304 TON
PERF GRADED BINDER (64-34)	816 TON
TACK COAT	27,370 GAL
RENTAL OF LOADER, FULLY OPERATED	100 HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	100 HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	100 HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	100 HOUR
COLD MILLING, CLASS 3	320 STA
COLD MILLING, CLASS 3	615 STA
TYPE 'A'	
RUMBLE STRIPS, ASPHALT	615 STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP LUMP