

NOTICE TO CONTRACTORS

CALL ORDER 500
 STATE PROJECT NO. RD-30-1(1031)
 LOCATION: US-385/US-30, LODGEPOLE-CHAPPELL
 COUNTIES: CHEYENNE DEUEL

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on December 09, 2010. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 10.5 MILES
 START DATE 08/01/2011 WORKING DAYS 50
 Price Range \$ 500,000 to \$ 2,000,000

Plans and specifications may be seen beginning November 16, 2010 at the Lincoln Central Office and November 22, 2010 at the District Engineer's Office at GERING
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	7 SHEETS	\$	1.75
STANDARD PLANS	7 SHEETS	\$	1.75

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T4	TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
3	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING
924	(3 SHEETS)	TYPICAL URBAN TRAFFIC CONTROL PLAN

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	32,280	B	DAY
BARRICADE, TYPE III	360	B	DAY
TEMPORARY SIGN DAY	1,036	E	EACH
SIGN DAY	8,100	E	EACH
OVERLAY BROKEN LINES	1,069	S	TA
OVERLAY SOLID LINES	2,069	S	TA
FLAGGING	112	D	DAY
FURNISHING AND OPERATING PILOT VEHICLE	56	D	DAY
FIELD OFFICE	1	E	EACH
MOBILIZATION	LUMP	L	LUMP
CONCRETE CURB REPAIR	65	L	LF
CONC PVMT REPAIR TYPE A FULL DEPTH	2	C	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	53	C	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	77	C	CY
HYDRATED LIME FOR ASPHALT MIXTURES	174	T	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	T	TON
FOUNDATION COURSE REPLACEMENT	4	C	CY
BIT FOUNDATION COURSE 5.5"	21,355	S	Y
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	500	T	TON
ASPH CONC, TYPE SPR	16,900	T	TON
ASPH CONCRETE FOR PATCHING, TYPE SPR	500	T	TON
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	19	T	TON
PERF GRADED BINDER (64-34)	661	T	TON

TACK COAT	28,580 GAL	
RENTAL OF LOADER, FULLY OPERATED	60 HOUR	
RENTAL OF MOTOR GRADER, FULLY OPERATED	60 HOUR	
RENTAL OF DUMP TRUCK, FULLY OPERATED	60 HOUR	
RENTAL OF SKID LOADER, FULLY OPERATED	60 HOUR	
WATER	240 MGAL	
EARTH SHOULDER CONSTRUCTION	961 STA	
TRENCHED WIDENING	961 STA	
COLD MILLING, CLASS 3	502 STA	
COLD MILLING, CLASS 3	35,203 SY	
TYPE A		
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		13 ACRE
MULCH		30 TON