

NOTICE TO CONTRACTORS

CALL ORDER 405
 STATE PROJECT NO. STR-D4(1017)
 LOCATION: DISTRICT 4, HAMILTON COUNTY
 COUNTIES: HAMILTON

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on February 03, 2011. At that time the bids will be opened and read for BR GDRL

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BRIDGES
 START DATE 06/13/2011 WORKING DAYS 65
 Price Range \$ 0 to \$ 500,000

Plans and specifications may be seen beginning January 11, 2011 at the Lincoln Central Office and January 18, 2011 at the District Engineer's Office at GRAND ISLAND
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	28 SHEETS	\$	7.00
STANDARD PLANS	7 SHEETS	\$	1.75

SHEET NO.

- 1 TITLE PAGE
- 2-S SUMMARY OF QUANTITIES
- 2-A PHOTO MAP
- 2-H HORIZONTAL ALIGNMENT & ORIENTATION
- 2-N GENERAL INFORMATION
- 3 PLAN SHEET
- 4 TYPICAL TRAFFIC CONTROL PLAN--TYPICAL LANE CLOSURE (FREEWAY-INTERSTATE)
- 5 TYPICAL TRAFFIC SIGNAL CONTROL PLAN FOR NARROW BRIDGE, ONE LANE, TWO WAY OPERATION WITH BARRIERS (11')
- 6 TEMPORARY TRAFFIC SIGNAL
- 7 TEMPORARY PAVEMENT MARKING PLAN
- 8 - 18 SPECIAL PLAN 1 PSC GIRDER BRIDGE ABUTMENTS & END OF FLOOR REPAIR STA. 15+00.00
- 19 - 23 SPECIAL PLAN 1C GUARDRAIL PLAN
- 24 - 25 SPECIAL PLAN 2C CONCRETE PROTECTION BARRIER

STANDARD PLANS

- 501-R5 (3 SHEETS) EROSION CONTROL
- 920-R5 (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
- 921-R5 (2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 6 BRIDGE AT STA. 15+00

MOBILIZATION	LUMP	LUMP
CONC FOR PVMT APPROACHES CLASS 47BD-4000		124 CY
EPOXY COATED RE-STEEL FOR PVMT APPROACH	20,033 LB	
PREFORMED EXPANSION JOINT, TYPE A		56 LF
CLASS II REPAIR		158 SY
CLASS III REPAIR		5 SY
PLACE, FINISH, & CURE CONC OVERLAY-SF		791 SY
47B-3000 CONC FOR BRIDGE		38 CY
47BD-4000 CONC FOR BRIDGE		37 CY
CONCRETE FOR OVERLAYS-SF		43 CY

PREP BRIDGE	1 EACH
15+00	
EPOXY COATED RE-STEEL	5,323 LB
CONCRETE REPAIR	461 SF
GRANULAR BACKFILL	27 CY

GROUP 7 GUARDRAIL

MOBILIZATION	LUMP	LUMP
REMOVE & SALVAGE GUARDRAIL	100 LF	
RESET GUARDRAIL	100 LF	
SURFACE UNDER GUARDRAIL	48 SY	
EROSION CONTROL, CLASS 1D	72 SY	

GROUP 10 GENERAL ITEMS

BARRICADE, TYPE II	1,888 BDAY	
BARRICADE, TYPE III	1,135 BDAY	
TEMPORARY SIGN DAY	300 EACH	
SIGN DAY	8,658 EACH	
TEMP PAVEMENT MARKING REMOVAL	2,400 LF	
PAVEMENT MARKING REMOVAL	2,400 LF	
TEMP PVMT MARKING, TYPE PAINT	2,400 LF	
FLASHING ARROW PANEL	25 DAY	
CONCRETE PROTECTION BARRIER	600 LF	
RELOCATE CONC PROTECTION BARRIER	600 LF	
TEMPORARY RUMBLE STRIP	4 EACH	
TEMPORARY TRAFFIC SIGNAL	1 EACH	
MOBILIZATION	LUMP	LUMP
24" WHT PREF PVMT MKING T-4	80 LF	