

NOTICE TO CONTRACTORS

CALL ORDER 505
 FEDERAL PROJECT NO. NH-20-1(137)
 LOCATION: US-20, HARRISON WEST
 COUNTIES: SIOUX

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on February 03, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 8.7 MILES
 START DATE 07/25/2011 WORKING DAYS 55
 Price Range \$ 1,000,000 to \$ 3,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning January 11, 2011 at the Lincoln Central Office and January 18, 2011 at the District Engineer's Office at GERING

Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	5 SHEETS	\$	1.25
STANDARD PLANS	4 SHEETS	\$	1.00

SHEET NO.

1	TITLE PAGE
2-S	SUMMARY OF QUANTITIES & TYPICAL CROSS SECTIONS
2-N1 - 2-N2	GENERAL INFORMATION--MILLED RUMBLE STRIPS
3	TEMPORARY PAVEMENT MARKING PLAN

STANDARD PLANS

920-R5	(2 SHEETS)	TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS)	TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	16,000	B DAY
BARRICADE, TYPE III	388	B DAY
TEMPORARY SIGN DAY	770	EACH
SIGN DAY	8,962	EACH
OVERLAY BROKEN LINES	1,848	STA
OVERLAY SOLID LINES	3,696	STA
FLAGGING	110	DAY
FURNISHING AND OPERATING PILOT VEHICLE	50	DAY
FIELD OFFICE	1	EACH
MOBILIZATION	LUMP	LUMP
HYDRATED LIME FOR ASPHALT MIXTURES	272	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
ASPH CONC FOR ST MAINT PTCHING, TYPE SPR	500	TON
ASPH CONC, TYPE SPS	9,060	TON
ASPH CONC, TYPE SPR	26,810	TON
ASPH CONCRETE FOR PATCHING, TYPE SPR	400	TON
ASPH CONCRETE FOR PATCHING, TYPE SPS	100	TON
PERF GRAD BIND (64-34) FOR ST MAINT PATCH	19	TON
PERF GRADED BINDER (52-34)	348	TON
PERF GRADED BINDER (64-34)	1,033	TON

TACK COAT	36,980 GAL	
RENTAL OF LOADER, FULLY OPERATED	50 HOUR	
RENTAL OF MOTOR GRADER, FULLY OPERATED	50 HOUR	
RENTAL OF DUMP TRUCK, FULLY OPERATED	50 HOUR	
RENTAL OF SKID LOADER, FULLY OPERATED	50 HOUR	
COLD MILLING, CLASS 3	462 STA	
COLD MILLING, CLASS 3	924 STA	
TYPE A		
RUMBLE STRIPS, ASPHALT	924 STA	
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP