

NOTICE TO CONTRACTORS

CALL ORDER 305
 FEDERAL PROJECT NO. NH-81-4(119)
 LOCATION: US-81, US-20-N-59
 COUNTIES: CEDAR PIERCE

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 03, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 7.0 MILES
 START DATE 06/13/2011 WORKING DAYS 85
 Price Range \$ 2,000,000 to \$ 4,000,000
 THIS PROJECT CONTAINS A DBE GOAL OF 5.0 %

Plans and specifications may be seen beginning February 08, 2011 at the Lincoln Central Office and February 14, 2011 at the District Engineer's Office at NORFOLK
 Additional letting information may be found at the Nebraska Department of Roads Web Site at <http://www.dor.state.ne.us/letting/>.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL	EACH	\$	5.00
PLANS (NOT INCLUDING STANDARDS)	48 SHEETS	\$	12.00
STANDARD PLANS	16 SHEETS	\$	4.00

SHEET NO.

1	TITLE PAGE
2-T1 - 2-T8	TYPICAL CROSS SECTIONS
2-S1 - 2-S7	SUMMARY OF QUANTITIES
2-A1 - 2-A7	PHOTO MAPS
2-H1 - 2-H2	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1	GENERAL INFORMATION
2-N2 - 2-N3	GENERAL INFORMATION--MILLED RUMBLE STRIPS
2-L1	CONSTRUCTION & REMOVALS
2-L2	EROSION CONTROL
3 - 9	PLAN SHEETS
10	PAVEMENT MARKING PLAN--LEFT TURN LANE DETAIL
11	PAVEMENT MARKING DETAILS
12	TEMPORARY PAVEMENT MARKING PLAN
13 - 19	SPECIAL PLAN 1C GUARDRAIL PLAN
20	SPECIAL PLAN 2C PAVEMENT APPROACH REPAIR STA. 109+87.00

STANDARD PLANS

301-R10	(3 SHEETS) PAVEMENT DETAILS
309	MAILBOX SUPPORT POST
329-R8	(4 SHEETS) 8 TO 16 INCH CONCRETE PAVEMENT
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

GROUP 9 BITUMINOUS

BARRICADE, TYPE II	10,000 BDAY
BARRICADE, TYPE III	1,175 BDAY
TEMPORARY SIGN DAY	1,190 EACH
SIGN DAY	12,844 EACH

OVERLAY BROKEN LINES	741	STA
OVERLAY SOLID LINES	1,482	STA
FLAGGING	170	DAY
FURNISHING AND OPERATING PILOT VEHICLE	160	DAY
TRAINING	500	HOUR
MOBILIZATION	LUMP	LUMP
CONSTRUCTION STAKING AND SURVEYING	LUMP	LUMP
REMOVE PAVEMENT	72	SY
SAWING PAVEMENT	342	LF
REMOVE CONCRETE MEDIAN SURFACING	83	SY
GRAVEL SURFACE COURSE	140	CY
CRUSHED ROCK SURFACE COURSE	5	CY
MAILBOX POST	2	EACH
TIE BARS	125	EACH
CROSS STITCHING	1,705	EACH
CONC 47B-3000 MEDIAN SURFACING	15	SY
8" CONCRETE BASE COURSE	140	SY
CONC PVMT REPAIR TYPE A FULL DEPTH	159	CY
CONC PVMT REPAIR TYPE B FULL DEPTH	365	CY
CONC PVMT REPAIR TYPE C FULL DEPTH	268	CY
CONC PVMT REPAIR TYPE A PARTIAL DEPTH	56	CY
CONC PVMT REPAIR TYPE B PARTIAL DEPTH	12	CY
CONC PVMT, PR-3500	117	CY
JOINT REPAIR		
BRIDGE APPROACH REPAIR	1	CY
W-BEAM GUARDRAIL	225	LF
REMOVE GUARDRAIL	580	LF
BRIDGE APPROACH SECTIONS	4	EACH
GUARDRAIL END TREATMENT, TYPE II	4	EACH
STOP AHD SYM, WET REF PRE PVMT MRK, T-4	1	EACH
5" WHT WET RFLC PRF PVMT MKNG T4 GVD	200	LF
12" WHT WET RFLC PRF PVMT MKNG T4 GVD	72	LF
5" YEL WET RFLC PRF PVMT MKNG T4 GVD	4,700	LF
12" YEL WET RFLC PRF PVMT MKNG T4 GVD	300	LF
RR XING WET RFLC PRF PVMT MKNG, T 4 GVD	2	EACH
HYDRATED LIME FOR ASPHALT MIXTURES	223	TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC	5	TON
FOUNDATION COURSE REPLACEMENT	24	CY
ASPH CONC ST MAINT PATCH TYPE SP4 (0.5)	500	TON
ASPH CONC, TYPE SPS	9,390	TON
ASPH CONC, TYPE SP4(0.5)	16,640	TON
ASPH CONC, TYPE LC	5,620	TON
PLACE ASPH CONC FOR DRIVE & INTER	2,702	SY
PERF GRAD BIND (64-34)FOR ST MAINT PATCH	25	TON
PERF GRADED BINDER (52-34)	469	TON
PERF GRADED BINDER (64-34)	1,259	TON
TACK COAT	38,710	GAL
FOG SEAL	830	GAL
RENTAL OF LOADER, FULLY OPERATED	10	HOUR
RENTAL OF DUMP TRUCK, FULLY OPERATED	10	HOUR
RENTAL OF SKID LOADER, FULLY OPERATED	10	HOUR
RENT CRAWLER MNTED HYD EXCAVATOR, F.O.	10	HOUR
WATER	189	MGAL
EARTH SHOULDER CONSTRUCTION	751	STA
RUMBLE STRIPS, ASPHALT	722	STA
CONCRETE SURFACE MILLING	102,239	SY
SURFACE UNDER GUARDRAIL	310	SY
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B	7	ACRE
EROSION CONTROL, CLASS 1D	525	SY
FABRIC SILT FENCE-LOW POROSITY	480	LF
TEMPORARY SILT FENCE	300	LF
MULCH	16	TON