## NOTICE TO CONTRACTORS

CALL ORDER 605

FEDERAL PROJECT NO. NH-26-1(158) LOCATION: US-26, LEWELLEN SOUTH COUNTIES: GARDEN KEITH

The Nebraska Department of Roads will receive sealed bids in Room 104 of the Central Office Building at 1500 Hwy. 2 in Lincoln, until 1:30 P.M. on March 03, 2011. At that time the bids will be opened and read for BITUMINOUS

BIDDING PROPOSAL FORMS WILL BE ISSUED AND A CONTRACT AWARDED TO A CONTRACTOR WHO IS QUALIFIED FOR: BITUMINOUS

Length: 9.7 MILES

START DATE 07/05/2011 WORKING DAYS 70 Price Range \$ 2,000,000 to \$ 4,000,000 THIS PROJECT CONTAINS A DBE GOAL OF 2.0 %

Plans and specifications may be seen beginning February 08, 2011 at the Lincoln Central Office and February 14, 2011 at the District Engineer's Office at NORTH PLATTE Additional letting information may be found at the Nebraska Department of Roads Web Site at http://www.dor.state.ne.us/letting/.

This project is funded under the Federal-Aid Highway Act, all appropriate Federal requirements will apply.

INFORMATIONAL PROPOSAL EACH \$ 5.00 PLANS (NOT INCLUDING STANDARDS) 38 SHEETS \$ 9.50 STANDARD PLANS 15 SHEETS \$ 3.75

## SHEET NO.

1 2-T1 - 2-T3	TITLE PAGE TYPICAL CROSS SECTIONS
2-S	SUMMARY OF QUANTITIES
2-W1 - 2-W9	WETLANDS
2-H1 - 2-H4	HORIZONTAL ALIGNMENT & ORIENTATION
2-N1 - 2-N4	GENERAL INFORMATION
2-N5	GENERAL INFORMATIONMILLED RUMBLE STRIPS
2-L	LARGE SCALE PLAN SHEET
3 - 11	PLAN SHEETS
12	TEMPORARY PAVEMENT MARKING PLAN
13	TYPICAL PAVEMENT MARKING PLANRURAL LEFT TURN BAYS
14 - 16	SPECIAL PLAN 1C CABLE GUARDRAIL

## STANDARD PLANS

108-R4	SUPERELEVATION PLAN FOR CONCRETE AND
	BITUMINOUS SURFACING
301-R10	(3 SHEETS) PAVEMENT DETAILS
307-R1	MAILBOX TURNOUT
309	MAILBOX SUPPORT POST
501-R5	(3 SHEETS) EROSION CONTROL
502	SILT FENCE DETAILS
901-R9	HIGHWAY DELINEATORS
920-R5	(2 SHEETS) TRAFFIC CONTROL, CONSTRUCTION AND MAINTENANCE
922-R8	(2 SHEETS) TRAFFIC CONTROL FOR ASPHALT SURFACING

Quantities shown herein are FOR INFORMATION ONLY and should not be used for bidding purposes. The Department reserves the right to change these quantities without notice.

## GROUP 9 BITUMINOUS

BARRICADE, TYPE II	22,000	BDAY
BARRICADE, TYPE III	702	BDAY
TEMPORARY SIGN DAY	980	EACH
SIGN DAY	12,098	EACH
OVERLAY BROKEN LINES	1,537	STA

OVERLAY SOLID LINES	3,074	STA
FLAGGING	135	DAY
FURNISHING AND OPERATING PILOT VEHICLE	65	DAY
FIELD OFFICE	1	EACH
TRAINING	500	HOUR
MOBILIZATION	LUMP	LUMP
DELINEATOR, TYPE II		EACH
DELINEATOR, TYPE III	102	EACH
INSTALL CHEVRONS		EACH
REMOVE DELINEATOR UNITS		EACH
ROADWAY GRADING		STA
REMOVE ASPHALT SURFACE		SY
REMOVE CURB		LF
SPEC SURF CRSE FOR MAILBOX TURNOUTS		SY
MAILBOX POST		EACH
CONCRETE 47B-3500 MEDIAN CURB	291	
CONC 47B-3000 MEDIAN SURFACING		SY
CONCRETE CLASS 47B-3500 ISLAND NOSE		EACH
REMOVE GUARDRAIL	48	
TERMINAL ANCHORAGE SECTIONS	2	EACH
4" YEL WET RFLC PRF PVMT MKNG T4 GVD	4,600	
12" YEL WET RFLC PRF PVMT MKNG T4 GVD	580	LF
HYDRATED LIME FOR ASPHALT MIXTURES		TON
HYD LIME FOR ASPH MIXES FOR ST MAIN PATC ASP CON ST MAIN PTCH TYPE SP4 SPEC(0.5)	5	TON
ASP CON ST MAIN PTCH TYPE SP4 SPEC(0.5)	500	TON
ASPH CONC, TYPE SPS	7,810	TON
ASPH CONC, TYPE SP4 SPECIAL(0.5)	17,980	TON
ASPH CONC, TYPE SPR	18,080	TON
PLACE ASPH CONC FOR DRIVE & INTER	1,244	SY
ASPH CONCRETE FOR PATCHING, TYPE SPR	300	TON
PERF GRAD BIND (64-34) FOR ST MAINT PATCH	24	TON
PERF GRADED BINDER (52-34)	296	TON
PERF GRADED BINDER (64-34)	1,460	TON
CONSTRUCTING ASPH CONC CURB	619	
TACK COAT	45,250	GAL
FOG SEAL	250	GAL
RENTAL OF LOADER, FULLY OPERATED	125	HOUR
RENTAL OF MOTOR GRADER, FULLY OPERATED	120	HOUR
TACK COAT FOG SEAL RENTAL OF LOADER, FULLY OPERATED RENTAL OF MOTOR GRADER, FULLY OPERATED RENTAL OF DUMP TRUCK, FULLY OPERATED RENTAL OF SKID LOADER, FULLY OPERATED RENT CRAWLER MNTED HYD EXCAVATOR, F.O. WATER	125	HOUR
RENTAL OF SKID LOADER FILLY OPERATED	125	HOUR
DENT CDAWLED MATER BYD EYCAMATOD E O	125	HOUR
WATER	6.1	MGAL
EARTH SHOULDER CONSTRUCTION	0 1	STA
		-
COLD MILLING, CLASS 3		STA
COLD MILLING, CLASS 3 TYPE A	900	STA
RUMBLE STRIPS, ASPHALT	841	STA
ASPH PVMT SMOOTHNESS TESTING I/D	LUMP	LUMP
SEEDING, TYPE B		ACRE
EROSION CONTROL, CLASS 1D	199	
TEMPORARY SILT FENCE	200	-
MULCH		TON
11011011	0	T O 1/4