

STATE OF NEBRASKA  
DEPARTMENT OF ROADS  
ADDENDUM NO. 2  
PROJECT NO. HSIP-6-6(159)  
CONTROL NO. 12953  
CALL NO. 105  
JCT. US-6/N-103  
LETTING DATE: APRIL 14, 2011

On plan sheet 2-N1, the EARTHWORK table is void and superseded by new EARTHWORK table depicted on the attached sheet.

It should be noted that quantities for the bid items "Excavation" and "Excavation, Borrow" are correct as shown in the plans and proposal.

\* \* \* \* \*

Upon execution of the contract, the plans will be revised to reflect this change.

DEPARTMENT OF ROADS

***Original Signed By Kendall Stege***

*for* Claude Oie  
Construction Engineer

Issued: April 6, 2011

CO:105AD204

NOTICE: Only the contractors issued bidding proposals receive this addendum and responsibility for notifying any potential subcontractors or suppliers remains with the contractor.

EARTHWORK					
LOCATION	STATION TO STATION	EXCAVATION (CU. YDS.)	EMBANKMENT (CU. YDS.)	BALANCE FACTOR	(+) LONG (-) SHORT
ROUNDBABOUT	0+00.00 - 5+02.86	0	6,289	1.45	-9,118
HWY. US-6	100+00.00 - 125+00.00	39,714	17,968	1.45	+13,661
HWY. N-103	614+50.00 - 626+00.00	4,444	2,611	1.45	+659
RAMP 1 (SW)	1000+00.00 - 1002+40.20	94	5,361	1.45	-7,679
RAMP 2 (SE)	2000+00.00 - 2002+39.08	379	1,395	1.45	-1,644
RAMP 3 (NE)	3000+00.00 - 3002+37.51	463	1,369	1.45	-1,522
RAMP 4 (NW)	4000+00.00 - 4002+37.38	130	3,910	1.45	-5,539
DRIVEWAY	5001+00.00 - 5003+75.00	3,222	0	1.45	+3,222
EARTH DRIVE	6000+12.00 - 6006+25.93	245	209	1.45	-56
TOTALS		48,691	39,112	1.45	-8,016